# RAJKOT MUNICIPAL CORPORATION

e - Tender No.RMC/ENGG/EZ/24-25/191



# **Bid Documents For**

વોર્ડ નં.૦૧ માં એસ.આર.પી.(ધંટેશ્વર)પ્રાથમિક શાળામાં કલર કરવાનું તેમજ પરચુરણ સિવિલ કામ રીટેન્ડર.



| Milestone Dates for e-tendering is as under   |                                      |  |
|---|--------------------------------------|--|
| 1. Downloading of e-Tender documents  | 12-03-25 To 26-03-25 upto 17.00 Hrs. |  |
| 2. Online submission of e – Tender  | 26-02-25 upto 18.00 Hrs.             |  |
| 3. Physical submission of EMD, Tender fee<br>and other documents required as per<br>Tender Checklist by Regd. Post. A.D. /<br>Speed Post ONLY | Before 02-04-25 upto 18.00 Hrs.      |  |
| 4. Opening of online technical bid  | 03-04-25 at 11.00 Hours onwards      |  |
| 5. Verification of submitted documents (EMD, e - Tender fee, etc.)  | 03-04-25 at 11.00 Hours onwards      |  |
| 6. Opening of Price Bid (If possible)   | 05-04-25 at 11.00 Hours onwards      |  |
| 7. Bid Validity   | 120 Days                             |  |
| For further details, pre-qualification criteria etc. visit www.rmc.nprocure.com   |                                      |  |

2024-25

CITY ENGINEER (I/C)
RAJKOT MUNICIPAL CORPORATION
SHRI HARISINHJI GOHIL BHAWAN
WEST ZONE, 150 FT RING ROAD,
RAJKOT - 360005 (GUJARAT)

# **RAJKOT MUNICIPAL CORPORATION**

# **BID DOCUMENT FOR**

વોર્ડ નં.૦૧ માં એસ.આર.પી.(ઘંટેશ્વર)પ્રાથમિક શાળામાં કલર કરવાનું તેમજ પરયુરણ સિવિલ કામ રીટેન્ડર

## PART-I

Section-1 Invitation to Bid, Instructions to Bidders and Formats.

Section-2 General Conditions of Contract

# **PART-II**

Section-3 Technical Specifications

# **PART-III**

Bill of Quantities (With Price)

# **ABBREVIATIONS**

## Statement showing the details of abbreviations

| Full Form                                 | Abbreviation |
|---|--------------|
| CITY ENGINEER                             | ACE          |
| Operation and Maintenance                 | O&M          |
| Net Present Value                         | NPV          |
| Engineering Procurement and Construction  | EPC          |
| Paschim Gujarat Vij Co. Ltd.              | PGVCL        |
| Critical Path Method                      | СРМ          |
| Reinforced Cement Concrete                | RCC          |
| High Ground Level Reservoir               | HGLR         |
| Kilometer                                 | KM           |
| Mild Steel                                | MS           |
| Bureau of Indian Standard                 | BIS          |
| American Water Works Association          | AWWA         |
| American Petroleum Industries             | API          |
| Million Liter per Day                     | MLD          |
| High Yield Strength Deformed bar          | HYSD         |
| Corrosion Residence Steel                 | CRS          |
| Ordinary Portland Cement                  | OPC          |
| American Standard for Testing of Material | ASTM         |
| Flux Compensated Magnetic Amplifier       | FCMA         |
| Cost Insurance and Freight                | CIF          |
| Free On Board                             | FOB          |
| EX – Works                                | EXW          |

# PART - I SECTION - 1

# **INVITATION FOR BIDS**

# RAJKOT MUNICIPAL CORPORATION e-TENDER NOTICE

The e-Tenders are invited with two bid system by e-Tendering from the experienced contractors registered in GWSSB / State Government / Central Government / Semi Government in appropriate class for below mentioned work:

| Sr<br>No | Name of work   | a) Estimated cost in Rs. b) EMD c) E-TENDER fee d) Time limit for completion of work e) Class Of Registration |
|----------|--|---|
| 1        | વોર્ડ નં.૦૧ માં એસ.આર.પી.(ઘંટેશ્વર)પ્રાથમિક<br>શાળામાં કલર કરવાનું તેમજ પરચુરણ<br>સિવિલ કામ રીટેન્ડર | a) Rs.12,31,500/- (without GST) b) Rs.12,315/- c) Rs.1,125/- d) 3 Months e) E-2 Class                         |
|          | e-TENDER No.RMC/ENGG/WZ/24-25/155  |   |

| Milestone Dates for e-tendering is as under   |                                      |  |
|---|--------------------------------------|--|
| 1. Downloading of e-Tender documents  | 12-03-25 To 26-03-25 upto 17.00 Hrs. |  |
| 2. Online submission of e – Tender  | 26-02-25 upto 18.00 Hrs.             |  |
| 3. Physical submission of EMD, Tender fee<br>and other documents required as per<br>Tender Checklist by Regd. Post. A.D. /<br>Speed Post ONLY | Before 02-04-25 upto 18.00 Hrs.      |  |
| 4. Opening of online technical bid  | 03-04-25 at 11.00 Hours onwards      |  |
| 5. Verification of submitted documents (EMD, e - Tender fee, etc.)  | 03-04-25 at 11.00 Hours onwards      |  |
| 6. Opening of Price Bid (If possible)   | 05-04-25 at 11.00 Hours onwards      |  |
| 7. Bid Validity   | 120 Days                             |  |
| For further details, pre-qualification criteria etc. visit www.rmc.nprocure.com   |                                      |  |

- 1. The e-tender fee will be accepted only in form of Demand Draft in favor of "Rajkot Municipal Corporation" Rajkot, payable at Rajkot from any Nationalized Bank or Scheduled Bank (except Co-operative Bank) in India and must be delivered to above address.
- 2. All bidders must submit Bid security (EMD) as above (1% of Tender Amount) either directly deposited in ICICI Bank Account No.015305010638 (Rajkot Municipal Corporation) IFSC Code ICIC0000153 (NEFT/RTGS or ONLINE TRANSFER) or submit at the below mentioned address in form of Demand Draft in favour of "Rajkot Municipal Corporation", Rajkot, from any Nationalized Bank or Scheduled Bank (except Co-operative Bank) in India.

3. Submission of required documents shall have to be done at the below mentioned address:

Office of the CITY ENGINEER RAJKOT MUNICIPAL CORPORATION SHRI HARISINHJI GOHIL BHAWAN WEST ZONE, 150 FT RING ROAD, RAJKOT - 360005 (GUJARAT)

4. The pre-qualification requirement is as under:

#### i) Financial Criteria:

- The Bidder must have achieved a minimum annual Turnover (defined as billing work in progress and completed in all classes of civil engineering construction works only) in any one year over the last seven financial years of the annual value of contracts value.
- The Bidder should give undertaking that he has access to or has available, liquid assets(Aggregate of Working capital, cash in hand & uncommitted bank guarantees) and/or credit facility equal to 25% of the value of the contract / contracts applied.
- Available Bid Capacity (ABC) must be more than the estimated tender cost.

Available bid capacity (ABC) =  $(A \times N \times 2) - B$ , where,

- **A** = Maximum of updated total amount of work executed in any one year of the last seven financial years.
- **B** = Amount of the existing commitments and ongoing works to be discharge during time interval of N years from the bid due date.

**N** = Number of years prescribed for completion of the proposed works

- 4. Bidder must have minimum "**E-2**" Class registration.
- 5. Solvency should not be less than Rs.1.00 Lakh

#### ii) Experience Criteria:

The bidder should posses following minimum experience:

- 1. Experience in successfully completing or substantially completing at least one contract of similar nature of work of at least **40 percent** of the value of proposed contract within the last seven years.
- 2. The works may have been executed by the applicant as prime contractor or as a member of a joint venture. In case a project has been executed by a joint venture weight towards experience of the project would be given to each joint venture in proportion of their final participation in the joint venture.
- 3. Substantially completed works means those works which are at least 90% completed as on the date of submission (i.e. Gross value of work done up to the last date of submission is 90% or more of the original contract price) and continuing satisfactorily.

For these, a certificate from the employers shall be submitted along with the application incorporating clearly the name of the work, contract value, billing amount, date of commencement of works satisfactory performance of the contract & any other relevant information.

**NOTE:-** For O&M financial criteria will be calculated on Tender amount of 1 Year.

4.—The work shall be awarded irrespective of any experience to unemployed Engineer.

NOTE: Only applicable for Ele/Mech/Civil Work

5.

#### Note on pre-qualification requirement:

1. Enhancement factor at 10% per year for last seven years will be applicable to arrive at average annual turnover and experience to finalize the magnitude of work done in last seven years.

| Sr.<br>No. | Year                   | Enhance<br>Factor |
|------------|------------------------|-------------------|
| 1          | Current Year (2024-25) | 1.00              |
| 2          | - 1 (2023-24)          | 1.10              |
| 3          | - 2 (2022-23)          | 1.21              |
| 4          | - 3 (2021-22)          | 1.33              |
| 5          | - 4 (2020-21)          | 1.46              |
| 6          | - 5 (2019-20 <u>)</u>  | 1.61              |
| 7          | - 6 (2018-19)          | 1.77              |
| 8          | - 7 (2017-18)          | 1.95              |

- 2. For Financial and Experience criteria, the estimated cost of **Rs.14,54,000/-** will be considered.
- 5. **Bidder has to quote their rates without GST**. The invoice should be submitted by contractor showing the breakup of GST in the bill. GST will be paid extra at the prevailing rate at the time of execution.
- 6. The contractor shall have to purchase the material required for this tender work, only from the supplier having registered GST Number. RMC will not be responsible to pay any amount towards GST if the material is purchased from the unregistered supplier / not having GST Number.
- 7. After opening of Technical Bid, the procedure for the pre-qualification shall be adopted and the Price Bid of only successful qualified bidder shall be opened for final evaluation of the contract. The decision of Municipal Commissioner regarding the pre-qualification shall be final and binding to all the bidders.
- 8. The Tender of those bidder(s) those who fails to produce the required documents physically within the stipulated date and time, will be treated as non responsive and their Price Bid will not be opened.

- 9. The bidder should not have been Black Listed, suspended, terminated, backed out, debarred & delisted by any Municipal Body / Urban Local Body / Development Authority in any State Government Body or undertaking / any department or undertaking of Government of India, since inception of the firm / Company. Such a case will be rejected out rightly. A Declaration in this regard on Rs.300/- Stamp Paper duly Notarized shall have to be submitted as per Annexure along with the tender documents. Submission of the bid document without such Notarized declaration will be rejected out rightly.
- 10. The bidder should provide accurate information on any litigation history or arbitration resulting from contracts completed or under execution by him over the last ten years. This should also include such cases, which are in process / progress. A consistent history of awards against the bidder may result in failure of the bid. In case the bidder has not provided such information and has come to the notice of the authority, the tender will be rejected at what so ever stage and in such case all the losses that will arise out of this issue will be recovered from the Bidder / bidder and he will not have any defense for the same.
- 11. Joint Venture is not permitted for this tender.
- 12. Conditional Tenders will be out rightly rejected.
- 13. If no agency remains present and are no points for Prebid meeting, "NIL" minutes to be considered and the same will not be uploaded.
- 14. Rajkot Municipal Corporation, Rajkot, reserves the right to accept / reject any or all e-tender(s) without assigning any reasons thereof.

CITY ENGINEER (I/C)
Rajkot Municipal Corporation

#### **CHECKLIST FOR SUBMISSION OF DOCUMENTS (ONLINE AND OFFLINE)**

The bidder must submit the relevant documents as per below:

| Sr<br>No | Document Name  | ONLINE<br>SUBMISSION             | OFFLINE<br>SUBMISSION |
|----------|--|----------------------------------|-----------------------|
| 1        | Tender Fee   | ✓                                | ✓                     |
| 2        | EMD  | ✓                                | ✓                     |
| 3        | Tender Documents with Corrigendum, if any with Agency Sign & Stamp                     | <b>~</b>                         | <b>~</b>              |
| 4        | Agency Registration Certificate  | ✓                                |                       |
| 5        | GST Registration   | ✓                                |                       |
| 6        | PAN Card   | ✓                                |                       |
| 7        | PF Registration  | ✓                                |                       |
| 8        | ESIC Registration  | ✓                                |                       |
| 9        | Labour License & CESS<br>Registration  | As Per Prevailing<br>Govt. Rules |                       |
| 10       | Profession Tax (PEC and PRC)<br>(Current Year Receipt and<br>Registration Certificate) | <b>√</b>                         |                       |
| 11       | Solvency Certificate   | ✓                                |                       |
| 12       | Non-Blacklist Declaration and<br>Litigation History                                    | ✓                                | <b>√</b>              |
| 13       | Turnover Certificate from CA   | ✓                                |                       |
| 14       | Work Experience Certificates   | ✓                                |                       |
| 15       | Working Capital Certificate From C.A.  | <b>√</b>                         |                       |
| 16       | Other documents, if any  | ✓                                |                       |

**Note:** The bidder must submit all relevant documents as per qualification criteria and tender conditions. No correspondence to the agency will be done for shortfall documents.

Original documents to be brought by bidder/authorized person for verification on the date and time as communicated by engineer-in-charge. Successful bidder to submit hard copy of tender documents including addenda/Corrigendum, if any and other supportive documents as required in this tender, duly stamped & signed on all pages.

CITY ENGINEER (I/C)
Rajkot Municipal Corporation

Name and signature of Bidder

| Check List for submission of Documents Tab   |          |  |
|--|----------|--|
| Tender Fee submitted as per Tender   | Yes / No |  |
| Tender Earnest Money Deposit submitted as per Tender   | Yes / No |  |
| Registration documents submitted as per tender requirement   | Yes / No |  |
| Financial Details:   |          |  |
| Turnover details submitted as per requirement  | Yes / No |  |
| Working Capital as per requirement of tender is submitted  | Yes / No |  |
| Valid Bank Solvency submitted  | Yes / No |  |
| Validity of Bank Solvency  | Date:    |  |
| Experience Details:  |          |  |
| Details of Technical Staff and details of machineries submitted  | Yes / No |  |
| Address proof submitted  | Yes / No |  |
| Identity proof submitted   | Yes / No |  |
| Fresh Declaration on Non-Judicial<br>Stamp Paper regarding not black<br>listed or Terminated or Debarred, is | Yes / No |  |
| Professional Tax Receipt of current  | Yes / No |  |

#### Note:

Over and above, the agency shall also have to submit all other necessary documents as may be required for pre-qualification, failing which, the agency will be treated as Non-responsive and will be DISQUALIFIED and also the online price bid of such agency will notbe opened.

Signature of contractor with seal

# INSTRUCTIONS TO BIDDERS

#### **INSTRUCTIONS TO BIDDER**

#### IT 1. GENERAL

The contract documents may be secured in accordance with the Notice Inviting E-TENDER for the work called. The work shall include supply of materials necessary for construction of the work.

#### IT 2. INVITATION TO E-TENDER

The Rajkot Municipal Corporation hereinafter referred as the Corporation will receive e-Tenders for the work of as per the specifications and schedule of prices in the e-Tender document. The e-Tenders shall be opened online as specified in the e-Tender notice in the presence of interested Bidders or their representatives. The Corporation reserves the right to reject the lowest or any other or all e-Tenders or part of it which in the opinion of the Corporation does not appear to be in its best interest, and the Bidder shall have no cause of action or claim against the Corporation or its officers, employees, successors or assignees for rejection of his e-Tender.

#### IT 3. LANGUAGE OF e-TENDER

E-TENDERs shall be submitted in English, and all information in the e-Tender shall also be in English, Information in any other language shall be accompanied by its translation in English. Failure to comply with this may make the e-Tender liable to rejection.

#### IT 4. QUALIFICATIONS OF BIDDERS

- A. The Bidders shall abide by the laws of the Union of India and of Gujarat State and legal jurisdiction of the place where the works are located.
- B. The Bidder shall furnish a written statement of financial and technical parameters with details and documents along with his e-Tender which contains namely as below:
  - i. The Bidder's experience in the fields relevant to this contract.
  - ii. The Bidder's financial capacity/resources and standing over at least 7 (Seven) years.
  - iii. The Bidder's present commitments (Jobs on hand).
  - iv. The Bidder's capability and qualifications of himself and his regular staff etc.
  - v. Plants and Machinery available with the Bidder for the work e-Tendered.

#### **C.** Joint venture : **(N.A.)**

- i. For the work mentioned above Joint Venture shall be allowed with maximum number of partner two, however all the fees, guarantee amount etc will be in the name of lead partner.
- ii. In Joint Venture, the lead partner as well as any other partner should have experience of similar nature of work, minimum 15 % of the estimated cost.

In case of Joint venture the tender evaluation will be as under:

#### Financial:-

The finance of each partner will be consider proportionate to their share in the Joint venture agreement.

#### Technical:-

The experienced of each partner will be added in the tender evaluation.

Bids submitted by a joint venture of two firms as partners shall comply with the following requirements.

- i. Tender fee, Earnest Money Deposit, Security Deposit and other financial details will be in the name of the lead partner.
- ii. All the partners shall have to enter into the Joint venture agreement and original agreement duly notarized shall have to be submitted along with tender documents.
- iii. The bid, and in case of a successful bid, the Form of Contract Agreement, shall be signed so as to be legally binding on all partners.
- iv.One of the partners shall be authorized to be in charge, and his authorization shall be evidenced by submitting a power of attorney by legally authorized signatories of all the partners.
- v. The partner in charge shall be authorized to incur liabilities, receive payments and receive instructions for and on behalf of any or all partners of the joint venture and the entire execution of the Contract.
- vi.All partners of the joint venture shall be jointly and severally liable for the execution of the Contract in accordance with the Contract terms and relevant statement to this effect shall be included in the authorization mentioned under (iv) above as well as in the Bid Form and the Form of Contract Agreement ( in case of successful bid ); and
- vii. Permissible Joint venture partners shall be restricted to two numbers.

The owner or the Engineer-in-charge is not obliged to disclose his findings or his Assessment.

The Bidder shall furnish original documents on the date mentioned in tender notice. The bid for those bidder will be treated as non-responsive who failing to produce original documents on specified date.

#### IT 5. e-TENDER DOCUMENTS

The e-Tender documents and drawings shall comprehensively be referred to as e-TENDER document. The several sections form in the document are the essential parts of the contract and a requirement occurring in one shall be as binding as though occurring in all, they are to be taken as mutually, explanatory and describe and provide for complete works.

#### IT 6. EXAMINATION BY BIDDERS

- A. At this own expense and prior to submitting his e-Tender, each Bidder shall (a) examine the Contract Documents, (b) visit the site and determine local conditions which may affect the work including the prevailing wages and other pertinent cost factors, (c) familiarize, himself with all central, state and local laws, ordinance, rules regulations and codes affecting the material supply including the cost of permits and licenses required for the work and (d) correlate his observations, investigations, and determinations with the requirements of the e-TENDER Documents, site & subsoil investigation.
- B. The e-Tender is invited on ..%. rate and contractor shall have to quote his price on % bases above or below in the schedule -B./ Price Schedule.

The works shall have to be completed in all respect as stated in the e-Tender document to the satisfaction of the Corporation.

**C.** The following comprises in Contract Documents at a price of **Rs.1,125-00**.

#### e-TENDER Document:

#### Part-I

- 1. Notice inviting Bidders.
- 2. Instructions to the Bidder.
- 3. Check List
- 4. Formats
- 5. General conditions of contract

#### Part-II

Technical specifications

#### Part-III

- a. Bid Form (With Price)
- b. Preamble to Price schedule
- c. Price Schedule (Schedule-B)

#### **General Specifications**

- 1. General note & site description.
- 2. Definition.
- 3. Scope of Contract.
- 4. e-Tender price.
- 5. Completion Schedule.
- 6. Site investigation.
- 7. Contractor's responsibility.
- 8. Safety.
- 9. Quality Assurance.
- 10. Classification of Strata.
- D. Copy of the E-TENDER Document should be completed, checked in a responsible manner, digitally signed, and submitted. Security Bond shall be submitted in person by the stipulate date, which shall form the e-Tender.

The e-Tender is required to complete with all the pages in which entries are required to be made by the Bidder are contained in the e-Tender documents and the Bidder shall not take out or add to or amend the text of any of the documents except in so far as may be necessary to comply with any addenda issued pursuant to Clause IT.17 hereof.

#### IT 7. EARNEST MONEY DEPOSIT:

- A. Each Bidder must submit a receipt of deposit as Tender guarantee towards **Earnest money** amounting to **Rs.12,315/-** in any form mentioned below:
  - a) By a Demand Draft on the Rajkot Branch of any Nationalized Bank or Scheduled Bank except co-operative bank.

- b) It can be directly deposited in the account of Rajkot Municipal Corporation.
- c)—A Bank Guarantee from Rajkot Branch of any Nationalized Bank or Scheduled Bank except co-operative bank. It shall be valid for a period of not less than Three hundred and Sixty (360) days from the date of submission.

EMD shall comply with the requirements for Bond as stipulated in the General conditions of contract. The Tender guarantee bond will be held by the owner as a guarantee that the Bidder, if awarded the contract, will enter into the contract agreement in good faith and furnish the required bonds. Any e-Tender not accompanied by a Tender guarantee in the form of earnest money deposited for the sum stipulated in the e-Tender Document will be summarily rejected.

- B. The Earnest Money Deposit will be refunded to the unsuccessful Bidders after an award has been finalized.
- C. The Earnest Money Deposit (Tender Guarantee) will be forfeited in event the successful Bidder fails to accept the contract and fails to submit the "Performance Guarantee Bonds to the Owner as stipulated in this e-Tender document within ten (10) days after receipt of notice of award of contract.

The successful Bidder shall furnish the required Security Deposit for performance and plus additional security if any for unbalanced bids in accordance with the condition of the contract and attend the office of the Engineer In-charge for execution of the contract documents. If he fails to furnish the Security Deposit for performance or enter into an agreement to execute the contract for the work offered to him, his Earnest Money Deposit will be forfeited and the Bidder will be Black Listed / Debarred from tendering for further works of Rajkot Municipal Corporation for the period of three years.

- D. The Earnest Money Deposit of the successful Bidder shall be returned after the performance guarantee bond, as required, is furnished by the contractor.
- E. No interest shall be paid by the owner on any e-Tender guarantee.

#### IT 8. INCOME TAX CLEARANCE CERTIFICATE: (DELETED)

Latest Income Tax clearance Certificates must accompany with the e-Tender without which the e-Tender is liable to be summarily rejected. The Income Tax Clearance Certificate obtained from the Income Tax Officer shall clearly indicate the Income Tax Pan No/Circle/Ward, District and the reference number of the assessment along with the assessment year.

#### IT 9. PREPARATION OF e-TENDER DOCUMENTS

Bidders are required to note the following while preparing the e-TENDER Documents:

- A. e-TENDER shall be submitted on the e-TENDER form bound here in English. All statements shall be properly filled in. Numbers shall be stated both in words and in figures were so indicated.
- B. All entries or prices and arithmetic shall be checked before submission of the e-TENDER. If there is discrepancy between the rates quoted in figures and in words, the rates expressed in words shall be considered as binding.
- C. Each e-Tender shall be accompanied by the prescribed e-Tender security bond and other required documents and drawings. All witnesses and sureties shall be persons of status and probity and their full names, occupations and addresses shall be stated below their signature.
- D. Variation to the contract Documents requested by the Bidder may be affixed and duly signed and stamped. Such variations may be approved or refused by the Corporation is not obliged to give reason for his decisions.

#### IT 10. SUBMISSION OF e-TENDER DOCUMENTS

Bidders are requested to submit the e-TENDER Documents on following lines.

- A. Volume containing following documents:
  - I. Earnest Money Deposit.
  - II. Certificates as registered contractor in appropriate class with Government of Gujarat or appropriate authority.
  - III.Bidder's financial capability statement including last three years Income tax returns, balance sheet, duly signed by registered chartered account.
  - IV. Bidder's experience in the field relevant to this contract.
  - V. A list of the equipment the Bidder possesses and that which he proposed to acquire and use for the purpose related to the work.

The time limit for receipt of e-Tender shall strictly apply in all cases. The Bidders should therefore ensure that their e-Tender is received by the competent authority **The Rajkot Municipal Corporation** at before expiry of the time limit. No delay on account of any cause for receipt of e-Tender shall be entertained.

The e-Tender must contain the name address of residence and place of business of the person or persons submitting the e-Tender and must be digitally signed.

e-TENDER by partnership firm must be furnished with the full names and addresses of all partners and be signed by one of the members of the partnership or by a legally authorized representative holding power of attorney followed by signature and designation of the person of person signing.

e-TENDER by Corporations/Companies must be signed with the legal name of the Corporation/Companies by the president/or by the secretary or other person or persons legally authorized to bind the Corporation/Company in the matter.

#### IT 11 TENDER VALIDITY PERIOD

The validity period of the e-Tender submitted for this work shall be of One Hundred and Twenty (120) calendar days from the date opening of the Technical bid of eTender and that the Bidder shall not be allowed to withdraw or modify the e-Tender offer on his own during the validity period. The Bidder will not be allowed to withdrawn the e-Tender or make any modifications or additions in the terms and conditions on his own e-Tender. If this is done then the owner shall, without prejudice to any other right or remedy, be at liberty to reject the e-Tender and forfeit the earnest money deposit in full.

#### **IT 12 GENERAL PERFORMANCE DATA**

Bidder shall present all the information which sought for in the e-Tender document in form of various schedules if given. e-TENDERs may not be considered if left blank or the schedules are not properly filled in.

#### IT 13 SIGNING OF e-TENDER DOCUMENTS

If the Tender is made by an individual it shall be signed with his full name above his current address. If the Tender is made by a proprietary firm, it shall be signed by the proprietor above his name and the name of his firm with his current address.

If the e-Tender is made by a firm in partnership, it shall be signed by all the partners of the firm above their full names and current address, or by a partner holding the power of attorney for the firm, in which case a certified copy of the power of attorney shall accompany the e-TENDER. A certified copy of the partnership deed, current addresses of all the partners of the firm shall also accompany the e-Tender.

If the e-Tender is made by a limited company or a limited corporation, it shall be signed by a duly authorized person holding the power of attorney, shall accompany the e-Tender. Such limited company or corporation may be required to furnish satisfactory evidence of its existence before the contract is awarded.

If the e-TENDER is made by a group of firms, the sponsoring firm shall submit complete information pertaining to each firms in the group and state along with the bid as to which of the firms shall have the responsibility for e-Tendering and for completion of the contract documents and furnish evidence admissible in law in respect of the authority to such firms on behalf of the group of firms for e-Tendering and for completion of contract documents. The full information and satisfactory evidence pertaining to the participation of each member of the group of firms in the e-Tender shall be furnished along with the e-Tender.

All witnesses and sureties shall be persons of status and probity and their full names, occupations and addresses shall be stared below their signatures. All the signatures in the e-Tender document shall be dated.

#### **IT 14 WITHDRAWAL OF TENDERS**

If, during the tender validity period, the Bidder withdraws his Tender, Tender security (Earnest Money) shall be forfeited and Bidder will be debarred for next three years to quote in R.M.C.

#### IT 15 INTERPRETATIONS OF e-TENDER DOCUMENTS

Bidders shall carefully examine the e-TENDER Document and fully inform themselves as to all the conditions and matters which may in any way affect the work or the cost thereof. If a Bidder finds discrepancies or omission from the specifications or other documents or should be in doubt as to their meaning, he should at once address query to the ADDL. CITY ENGINEER, R.M.C. The result of interpretation of the e-TENDER will be issued as addendum.

#### IT 16 ERRORS AND DISCREPANCIES IN e-TENDERS

In case of conflict between the figures and words in the rates the rate expressed in words shall prevail and apply in such cases.

#### **IT 17 MODIFICATION OF DOCUMENTS**

Modification of specifications and extension of the closing date of the e-Tender, if required will be made by an addendum. Each addendum will be made available online to all Bidders. These shall form a part of e-Tender. The Bidder shall not add to or amend the text of any of the documents except in so far as may be necessary to comply with any addendum.

#### **ADDENDA**

Addenda form part of the Contract Documents, and full consideration shall be given to all Addenda in the preparation of e-Tender. Bidders shall verify the number of Addenda issued, if any and acknowledge the receipt of all Addenda in the e-TENDER Failure to so acknowledge may cause the e-Tender to be rejected.

- A. RMC may issue Addenda to advise Bidders of changed requirements. Such addenda may modify previously issued Addenda.
- B. No addendum may be issued after the time stated in the notice inviting e-Tenders.

#### IT 18 TAX AND DUTIES ON MATERIALS

All charge on account of excise duties, Central / State, sales tax, work contract tax and other duties etc. on materials obtained for the works from any source shall be borne by the contractors. No (P) or `C' or `D' form shall be supplied.

#### IT 19 EVALUATION OF e-TENDERS

While comparing e-Tenders, the Rajkot Municipal Corporation shall consider factors like price offer is workable with the market price, efficiency and reliability of construction method proposed, compliance with the specifications, relative quality, work done in past with Rajkot Municipal Corporation or other Government Organizations, litigation issues etc.

Evaluation criteria specifically mentioned in the specification will also be taken into consideration in the evaluation of e- Tenders.

#### **IT 20 TIME REQUIRED FOR COMPLETION**

The completion period mentioned in this schedule is to be reckoned from the date of notice to proceed. Total completion period is **3 Months** from the date of issue of notice to proceed and contractor should adhere to this completion time. Monsoon period from  $1^{\rm st}$  July to  $30^{\rm th}$  September will be considered as non-working period and hence excluded in time limit.

#### IT 21 POLICY FOR TENDER UNDER CONSIDERATION

TENDER shall be termed to be under consideration from the opening of the e-Tender until such time any official announcement or award is made.

While e-Tenders are under consideration, Bidders and their representative or other interested parties are advised to refrain from contacting by any means any Corporation personnel or representatives on matters related to the e-Tenders under study. The Corporation's representatives if necessary will obtain clarification on e-Tenders by requesting such information from any or all the Bidders, either in writing or through personal contact, as may be necessary. The Bidder will not be permitted to change the substance of his e-Tender after e-Tenders have been opened. This includes any post Tender price revision. Non-compliance with his provision shall make the Tender liable for rejection.

#### **IT 22 PRICES AND PAYMENTS**

The Bidder must understand clearly that the prices quoted are for the total works or the part of the total works quoted for and include all costs due to materials, labour, equipment, supervision, other services, royalties, taxes etc. and to include all extra to cover the cost. No claim for additional payment beyond the prices quoted will be entertained and the Bidder will not be entitled subsequently to make any claim on any ground.

#### **IT 23 PAYMENT TERMS**

The terms of payment are defined in the General Conditions of Contract and Technical specifications. The Corporation shall not under any circumstances relax these terms of payment and will not consider any alternative payment terms. Bidders should therefore in their own interest note this provision to avoid rejection of their e-Tenders.

#### IT 24 AWARD

Award of the contract or the rejection or e-TENDERs will be made during the Tender validity period. A separate Schedule-B (Price Schedule) is given. The contractors are requested to quote their price offer in % below or above on the given price in the schedule-B of Price Schedule only.

A. After all contract contingencies are satisfied and the Notice of Award is issued, the successful Bidder shall execute the Contract Agreement within the time stated and shall furnish the Bond as required herein. The contract Agreement shall be executed, in form stipulated by the Owner.

- B. If the Bidder receiving the Notice of Award fails or refuses to execute the Contract Agreement within the stated time limit or fails or refuses to furnish the Bond as required herein. The Owner may annul his award and declare the e-Tender security forfeited and will take action as deemed fit.
- C. A Corporation, partnership firm or other consortium acting as the Bidder and receiving the award shall furnish evidence of its existence and evidence that the officer signing the contract agreement and Bonds for the corporation, partnership firm or other consortium acting as the Bidder is duly authorized to do so.

#### **IT 25 SIGNING OF CONTRACT**

The successful Bidder shall be required to execute the contract agreement within 10 days of receipt of intimation to execute the contract, failing which the Corporation will be entitled annul to the award and forfeit the Earnest Money Deposit. The person to sign the contract document shall be person as detailed in Article IT.13 (signing of e-Tender documents).

#### IT 26 DISOUALIFICATION

A e-Tender shall be disqualified and will not be taken for consideration if,

- (a) The envelope does not show on the outside the reference of bid and thus gets opened before the due date of opening (as per Article IT 10 i.e. submission of tender document)
- (b) The Tender fee and Tender Earnest Money Deposit is not deposited in full and in the manner as specified as per Article IT.7 i.e. Earnest Money Deposit.
- (c) The e-Tender is in a language other than English or does not contain its English Translation in case of other language adopted for e-Tender preparation.
- (d) The e-Tender documents are not signed by an authorized person (as per Article IT. 13 i.e. signing of e-Tender documents).
- (e) The general performance data for qualification is not submitted fully (as per Article IT 12 i.e. General performance Data).
- (f) Bidder does not agree to payment terms defined as per Article IT. 23 i.e. payment terms.

#### A. A e-Tender may further be disqualified if,

- (a) Price variation is proposed by the Bidder on any principle other than those provided in the e-TENDER Documents.
- (b) Completion schedule offered is not consistent with the completion schedule defined and specified in e-Tender document.
- (c) The validity of e-Tender bond is less than that mentioned in Article IT. 11 i.e. e Tender validity period.
- (d) Any of the page or pages of e-Tender is/are removed or replaced.
- (e) Any conditional tender.
- (f) All corrections or posted slips are not initiated by Bidder.
- (g) Any erasure is made in the e-tender.

#### IT 27 PERFORMANCE GUARANTEE (SECURITY DEPOSIT)

As a contract security the Bidder to whom the award is made shall furnish a performance guarantee (Security deposit) for the amount of **5%** of the contract price to guarantee the faithful performance, completion and maintenance of the works of the contract in accordance with all conditions and terms specified herein and to the satisfaction of the Engineer-in-charge and ensuring the discharge of all obligations arising from the execution of contract.

Additional performance guarantee is payable if,

- 1. the contract price offered by the selected bidder is lower than 10% but upto 20% of the estimated project cost than the additional performance security shall be calculated @ 20% of the difference in the estimated project cost minus 10% of the estimated project cost and Contract price offered by the selected bidder.
- 2. the contract price offered by the selected bidder is lower than 20% of the Estimated project cost than the additional performance security shall be calculated @ 30% of the difference in the Estimated project cost minus 10% of the Estimated project cost and Contract price offered by the selected bidder.

This additional performance security shall be treated as part of the performance security.

Performance security shall be valid beyond 60 days of the defect liability period and the additional performance security shall be valid beyond 28 days of project completion date.

Final SD will be calculated at the time of final bill i.e. actual completion amount.

Performance as mentioned above may be in the forms mentioned below:

- d) By a Demand Draft on the Rajkot Branch of any Nationalized Bank or Scheduled Bank except co-operative bank.
- e) A fixed deposit receipt of any Schedule Bank or Nationalized Bank (except Co-operative Bank) duly endorsed in favour of the <u>Rajkot</u> <u>Municipal Corporation</u>, <u>Rajkot</u>.
- f) A Bank Guarantee from Rajkot Branch of any Nationalized Bank or Scheduled Bank except co-operative bank.

The performance guarantee shall be delivered to the Corporation within ten (10) days of the notice of award and at least three (3) days before the contract agreement is signed unless otherwise specified by the Engineer-incharge. Alternatively, the contractor may at his option deposit an amount of **2.5%** of the value of the contract price within ten days and the balance **2.5%** to be recovered in installments through deduction @ the rate of 10% from the running account bills. It is further clarified that Performance Guarantee (SD) for extra work will also be recovered @ 10% from the bill of extra work i.e. works beyond tender amount.

On due performance and completion of the contract in all respects, THE PERFORMANCE GUARANTEE (SECURITY DEPOSIT) WILL BE RELEASED TO THE CONTRACTOR WITHOUT ANY INTEREST AFTER DEFECT LIABILITY PERIOD IS OVER.

#### **IT 28 STAMP DUTY**

The successful Bidder shall have to enter into an agreement on a non-judicial stamp paper of amount as per Stamp Duty Act in the form of the agreement approved by the Corporation. The cost of stamp paper and adhesive stamp shall be borne by the contractor.

#### **IT 29 BRAND NAMES**

Specific reference in the specifications to any material by manufacturer's name, or catalogue shall be constructed as establishing a standard or quality and performance and not as limiting competition and the Bidder in such cases, may at his option freely use only other product, provided that it ensures an equal of higher quality than the standard mentioned and meets Corporation approval.

#### **IT 30 NON TRANSFERABLE**

e-TENDER documents are not transferable.

#### IT 31 COST OF e-Tenderina

The owner will not defray expense incurred by Bidders in e-Tendering.

#### IT 32 EFFECT OF e-Tender

The e-Tender for the work shall remain for a period of One hundred and Twenty (120) calendar days from the date of opening of the e-Tenders for this work and that the Bidder shall not be allowed to withdraw or modify the offer in his own during the period. If any Bidder withdraws or makes any modification or additions in the terms and conditions of his own e-Tender, then the Corporation shall, without prejudice to any other right or remedy, be at liberty to reject the e-Tender and forfeit the earnest money in full.

#### **IT 33 CHANGE IN OUANTITY**

The Corporation reserves the right to waive any information in any e-Tender and to reject one or all e-Tenders without assigning any reasons for such rejection and also to vary the quantities of items or group as specified in the scheduled of prices as may be necessary.

#### **IT 34 NEW EQUIPMENT AND MATERIAL**

All materials, equipment and spare parts thereof shall be new, unused and originally coming from manufacturer's plant to the Corporation. The rebuilt or overhauled equipment/materials will not be allowed to be used on works.

#### **IT 35 RIGHTS RESERVED**

The owner reserves the right to reject any or all e-Tenders, to waive any informality or irregularity in any e-Tender without assigning any reason. The owner further reserves the right to withhold issuance of the notice to proceed, even after execution of the contract agreement. No payment will be made to the successful Bidder on account of such withholding. The owner is not obliged to give reasons for any such action.

#### IT 36 ADDITIONAL RIGHTS RESERVED

The Commissioner, Rajkot Municipal Corporation, reserves the right to reduce the scope of work & split the e-Tender in two or more parts without assigning any reason even after the awards of contract.

#### **IT 37 MOBILIZATION ADVANCE**

No mobilization advance or advance on machinery will be given.

#### **IT 38 CONDITIONAL e-Tenders**

The scope of work is clearly mentioned in the e-Tender documents. The contractor shall have to carry out the work in accordance with the details specifications. No condition will be accepted. The conditional e-Tender will liable to be rejected.

#### IT 39 CESS & REGISTRATION:

For the welfare of labour working under construction Industry, the agency shall have to take the registration with competent authority as per Circular No.CWA/2004/841/M-3 dated 30-01-2006 of Government of Gujarat. Rajkot Municipal Corporation will deduct prevailing CESS of the value of work and will deposit the same in Government.

#### **IT 40 ESI REGISTRATION:**

The contractors who are liable to be registered under ESI Act must possess ESI registration number at the time of filling of tender. The agency should follow all the rules and regulations of ESI Act as per prevailing norms.

#### **IT 41 PROFESSIONAL TAX**

The bidder shall have to pay the Professional Tax for current financial year imposed by Government of Gujarat, and also the bidder shall have to produce Enrollment Certificate for the same.

#### IT 42 PF CODE:

The contractors who are liable to be registered under EPF Act, 1950 must possess EFP code at the time of filling of tender. The agency should follow all the rules and regulations of the Act as prevailing currently.

#### **IT 43 LABOUR LICENSE:**

The contractors who are liable to be registered under Contract Labour Act, 1970 must possess online Labour License at the time of filling of tender. The agency should follow all the rules and regulations of the Act as prevailing currently.

#### IT 44 FILLING OF e-TENDER

The bidder shall have to fill all the details required in on-line bidding form of e-Tender. Incomplete OR inappropriate OR wrong information filled may cause the e-Tender to be rejected.

Addl/Asst. Engineer R.M.C.

R.M.C.

Dy.Ex.Engineer CITY ENGINEER (SPL) R.M.C.

Signature of Contractor with Seal

# **FORMATS**

Financial & Other Statements

Information / Details to be submitted by the Bidders in the Performa mentioned under Statement no 1 to 9. All the documents submitted herewith as supporting documents shall be duly attested and certified true copy.

**STATEMENT NO-1** 

## **DECLARATION**

| I / Wehereby declared  |
|--|
| that I am / We partner(s) are not black listed or Terminated or Debarred or suspended, backed out, delisted or connected with firm black listed or terminated or |
| debarred or suspended or backed out or delisted in any States, CPWD/ MES/ Railways   |
| or any Government, Semi- Government or Private body since the inception of the firm  |
| / company. Also, no Police complaint is lodged against the firm / company or Staff   |
| deployed by me / us.   |
|  |
| At present I am / we are registered as approved contractor(s), firms inState, CPWD / MES / Railways.   |
|  |
| I, owner / We, the partners of this firm, hereby give an undertaking that we are jointly and severally responsible to meet all the liabilities ever and above    |
| the business of this firm and make good the above financial loss sustained by the  |
| Rajkot Municipal Corporation as a result of our abandoning the works entrusted to  |
| us.  |
|  |
| I further undertake that if above declaration proves to be wrong/ incorrect  |
| or misleading, our tender/ contract stands to be cancelled/ terminated.  |
|  |
|  |
| Date:  Place: Signature of Authorized Person   |
| Signature of Authorized Ferson   |
| With Notarised   |
|  |

#### **STATEMENT NO-2**

# APPLICABILITY OF PROVIDENT FUND AND MISCELLANEOUS PROVISIONS ACT 1952

Successful bidder i.e. the agency whose tender is accepted by the RMC shall have to comply the necessary formalities under the employees provident fund and Miscellaneous Provisions Act, 1952 as Contributory Provident Fund Scheme is applicable to labourers engaged in construction activity and shall have to submit proofs regarding deduction of provident fund and other dues and depositing the same with government department under the act and the scheme regularly on monthly basis failing which no running / final bill payment will be made by the RMC to the contractor in any circumstances.

A certificate to the above effect has to be given by the contractor as under.

# Declaration Of Depositing Provident Fund contribution

| Date:   | Seal and Signature of the Bidder    |
|---|-------------------------------------|
|   |                                     |
| deduction and contribution deposited as ment    | ioned above.                        |
| We produce herewith the copies of the c         | hallans for the provident fund      |
| Fund Authority under our Provident Fund Code    | No                                  |
|   | with Provident                      |
| / wages paid by us to the labourers engaged for | or the work of                      |
| same along with employer's contribution towar   | ds provident fund on labour charges |
| This to certify that we have deducted the       | e employees' P.F. and deposited the |

# STATEMENT NO. -3

# **CURRICULAM VITAE**

| Sr.No. | Details of person                   |  |
|--------|-------------------------------------|--|
| 1.     | Name                                |  |
| 2.     | Age                                 |  |
| 3.     | Qualifications                      |  |
| 4.     | Experience in Project Related field |  |
| 5.     | Other experiences                   |  |
| 6.     | Employment Record.                  |  |

| Sr.No. | Perio<br>d<br>From - To | Organization<br>under which<br>work | Status<br>/position in<br>the |
|--------|-------------------------|-------------------------------------|-------------------------------|
|        |                         |                                     |                               |
|        |                         |                                     |                               |
|        |                         |                                     |                               |
|        |                         |                                     |                               |
|        |                         |                                     |                               |

## Note:

- (1) Separate sheet for each person to be furnished as above.
- (2) The contractor's Project Team should consist of persons in the following disciplines.
  - a) Senior Engineer with experience of Building work
  - b) Senior material Engineer.
  - c) Senior Quantity Surveyor.
  - d) Project management expert.
  - e) Site in charge

## STATEMENT - 4

# INFORMATION REGARDING FINANCIAL CAPACITY OF THE CONTRACTORS

| Sr. | Details   | Amount (Rs. in lakhs) | Remarks  |
|-----|---|-----------------------|--|
| 1   | Solvency  |                       | A Banker's Certificate of                      |
| 1.  | Solvency  |                       | current financial year may please be attached. |
| 2.  | Annual Turnover for the                         |                       | Certified true copy to                         |
|     | last seven years.                               |                       | be attached                                    |
| 3.  | Price of biggest similar nature job carried out |                       | Certified true copy to be attached             |

#### **STATEMENT NO. - 4/A**

#### **BIDDER'S FINANCIAL CAPACITY**

| Sr. No. | Financial Year | Annual<br>Turnover in<br>Engineering<br>Project Rs. | Net<br>worth<br>Rs. | Net Cash<br>Rs. | Working<br>Capital<br>Rs. |
|---------|----------------|---|---------------------|-----------------|---------------------------|
| 1       | 2023-2024      |   |                     |                 |                           |
| 2       | 2022-2023      |   |                     |                 |                           |
| 3       | 2021-2022      |   |                     |                 |                           |
| 4       | 2020-2021      |   |                     |                 |                           |
| 5       | 2019-2020      |   |                     |                 |                           |
| 6       | 2018-2019      |   |                     |                 |                           |
| 7       | 2017-2018      |   |                     |                 |                           |

#### Note:-

- 1) Figures to be taken from audited balance sheets. Duly certified attested true copy
- 2) Copies of the balance sheet to be attached..
- 3) The bidder shall have to provide that for a period of at least 1 Months the bidder has ability to sustain negative cash balance and how he proposes to meet with the same.
- 4) Cash Plan / Cash flow Statement.

#### STATEMENT NO. - 4 / B

#### **AVAILABLE BID CAPACITY**

|   | 2017- | 2018- | 2019- | 2020- | 2021- | 2022- | 2023- |
|---|-------|-------|-------|-------|-------|-------|-------|
|   | 18    | 19    | 20    | 21    | 22    | 23    | 24    |
| Value of<br>works<br>executed in<br>Rs. Crores. |       |       |       |       |       |       |       |

The available bid capacity will be worked out as follows.

## Available bid capacity = $(A \times N \times 2) - B$ ,

## where

- **A** = Maximum of updated total amount of work executed in any one year of the last five financial years.
- **B** = The amount of the existing commitments and ongoing works to be discharge during time interval of N years from the bid due date.
- **N** = Number of years prescribed for completion of the proposed works

## **STATEMENT NO. – 5**

# LIST OF SINGLE PROJECT WORK OF NOT LESS THAN 60% OF THE ESTIMATED COST COMPLETED DURING THE LAST SEVEN YEARS.

| Sr.<br>No | Year of<br>Constru<br>ct ion<br>work | Name of<br>Project | Name of<br>owner &<br>contact<br>person<br>of the<br>project,<br>address,<br>phone | Tot<br>al<br>cost<br>of<br>the<br>wor<br>k | Tot<br>al<br>valu<br>e of<br>wor<br>k<br>don<br>e | Date<br>of<br>starti<br>ng<br>work | Date of<br>Actual<br>completi<br>on of<br>work |
|-----------|--------------------------------------|--------------------|--|--|---|------------------------------------|--|
| 1         | 2                                    | 3                  | 4  | 5  | 6   | 7                                  | 8  |
| 1         |                                      |                    |  |  |   |                                    |  |
| 2         |                                      |                    |  |  |   |                                    |  |
| 3         |                                      |                    |  |  |   |                                    |  |
| 4         |                                      |                    |  |  |   |                                    |  |
| 5         |                                      |                    |  |  |   |                                    |  |
| 6         |                                      |                    |  |  |   |                                    |  |
| 7         |                                      |                    |  |  |   |                                    |  |
| 8         |                                      |                    |  |  |   |                                    |  |
| 9         |                                      |                    |  |  |   |                                    |  |
| 10        |                                      |                    |  |  |   |                                    |  |

**Note**: Certificate from the owners in support of above works may be enclosed with this statement.

## **STATEMENT NO. 5/A**

Detailed information of similar type of work costing not less than 50% of tender amount completed with good quality and workmanship in the past seven years.

Name of Contractor: \_\_\_\_\_

| Sr.<br>No | Nam<br>e of<br>wor<br>k | Nam<br>e of<br>clien<br>t | Estimate<br>d c o s t<br>o f work<br>(Rs.<br>Lakhs) | ed | Date of award of contra ct | Target<br>date of<br>completi<br>on | Actual<br>date of<br>completi<br>on | Reas<br>on<br>for<br>delay | Amount of work done during last seven years preceding this tender (Rs. Lakhs). |    |    |    | yea | rs | Amount of<br>work done<br>after March<br>2021<br>(Rs.<br>Lakhs | Remarks |  |
|-----------|-------------------------|---------------------------|---|----|----------------------------|-------------------------------------|-------------------------------------|----------------------------|--|----|----|----|-----|----|--|---------|--|
|           |                         |                           |   |    |                            |                                     |                                     |                            | 20   | 20 | 20 | 20 | 20  | 20 | 20   |         |  |
|           |                         |                           |   |    |                            |                                     |                                     |                            | 17   | 18 | 19 | 20 | 21  | 22 | 23   | 1       |  |
|           |                         |                           |   |    |                            |                                     |                                     |                            | -  | -  | -  | -  | -   | -  | -  |         |  |
|           |                         |                           |   |    |                            |                                     |                                     |                            | 18   | 19 | 20 | 21 | 22  | 23 | 24   |         |  |
|           |                         |                           |   |    |                            |                                     |                                     |                            |  |    |    |    |     |    |  |         |  |
|           |                         |                           |   |    |                            |                                     |                                     |                            |  |    |    |    |     |    |  |         |  |
|           |                         |                           |   |    |                            |                                     |                                     |                            |  |    |    |    |     |    |  |         |  |
|           |                         |                           |   |    |                            |                                     |                                     |                            |  |    |    |    |     |    |  |         |  |
|           |                         |                           |   |    |                            |                                     |                                     |                            |  |    |    |    |     |    |  |         |  |
|           |                         |                           |   |    |                            |                                     |                                     |                            |  |    |    |    |     |    |  |         |  |
|           |                         |                           |   |    |                            |                                     |                                     |                            |  |    |    |    |     |    |  |         |  |
|           |                         |                           |   |    |                            |                                     |                                     |                            |  |    |    |    |     |    |  |         |  |

**Note**: Certificate from the owners in support of above works may be enclosed with this statement.

# <u>STATEMENT NO - 5/B</u> DETAILS OF IMPORTANT CONSTRUCTION PROJECTS

| Sr.<br>No | Name of<br>Project | Estimat<br>ed<br>cost | Prescr<br>time o<br>perfor | f<br>mance      |               | Completion      | Actual<br>Completion<br>Cost Rs. | Name,<br>address<br>and |
|-----------|--------------------|-----------------------|----------------------------|-----------------|---------------|-----------------|----------------------------------|-------------------------|
|           |                    |                       | Start<br>Date              | Completion Date | Start<br>Date | Completion Date |                                  |                         |
| 1         | 2                  | 3                     | 4                          | 5               | 6             | 7               | 8                                | 9                       |
|           |                    |                       |                            |                 |               |                 |                                  |                         |
|           |                    |                       |                            |                 |               |                 |                                  |                         |
|           |                    |                       |                            |                 |               |                 |                                  |                         |
|           |                    |                       |                            |                 |               |                 |                                  |                         |
|           |                    |                       |                            |                 |               |                 |                                  |                         |
|           |                    |                       |                            |                 |               |                 |                                  |                         |
|           |                    |                       |                            |                 |               |                 |                                  |                         |
|           |                    |                       |                            |                 |               |                 |                                  |                         |
|           |                    |                       |                            |                 |               |                 |                                  |                         |
|           |                    |                       |                            |                 |               |                 |                                  |                         |

**Note**: Certificate from the owners in support of above works may be enclosed with this statement.

## **STATEMENT NO. – 5/C**

## **DETAILS OF ONGOING PROJECT**

| Sr.<br>No | Name of project | Value of<br>remaining<br>work Rs. in<br>lakhs. | Start<br>date | Likely<br>date of<br>completi<br>on | Name, address, telephone, fax no. of project authority and contact person. |
|-----------|-----------------|--|---------------|-------------------------------------|--|
|           |                 |  |               |                                     |  |
|           |                 |  |               |                                     |  |
|           |                 |  |               |                                     |  |

#### **STATEMENT NO.-6**

# DETAILS OF PLANT & MACHINERY TO BE DEPLOYED ON THIS WORK

| Name | of the | contractor | /com | pany | / |
|------|--------|------------|------|------|---|
|      |        |            |      |      |   |

| Sr.<br>No | Name of plants/machinery | Nos.<br>available<br>(with make<br>& year) | Nos.<br>proposed to<br>be deployed<br>for this<br>project | Present<br>location | Present<br>value of<br>plant/<br>machineries |
|-----------|--------------------------|--|---|---------------------|--|
| 1         | 2                        | 3  | 4   | 5                   | 6  |
|           |                          |  |   |                     |  |
|           |                          |  |   |                     |  |
|           |                          |  |   |                     |  |
|           |                          |  |   |                     |  |
|           |                          |  |   |                     |  |
|           |                          |  |   |                     |  |

#### Note:

Plant / machineries which are proposed to be procured shall have to be procured at the earliest after award of the work and before the start of the work.

#### **STATEMENT NO. 7**

#### **METHOD STATEMENT AND WORK PLAN**

The Bidder shall have to provide a brief write up to be enclosed with the "Technical Bids" covering his approach and methodology to handle the project construction activities including his details work plan. The brief shall include the following aspects.

| Sr.<br>No. | Components  |  |
|------------|---|--|
| 1.         | Methodology   |  |
| 2.         | Construction equipment availability and plan of deployment. |  |
| 3.         | PERT / Construction chart / Bar chart.                      |  |

# **Application Form(1)**General Information

All individual firms and each partner of a consortium applying for qualification are requested to complete the information in this form. Nationality information to be provided for all owners or applicants who are partnerships or individually-owned firms.

Where the Applicant proposes to use named subcontractors for critical components of the works, or for work contents in excess of 10 percent of the value of the whole works the following information should also be supplied for the specialist subcontractor(s).

| 1. | Name of Firm                        |  |
|----|-------------------------------------|--|
| 2. | Head office address                 |  |
| 3. | Telephone                           | Contact                                |
| 4. | Fax                                 | Telex                                  |
| 5. | Place of incorporation/registration | Year of incorporation/<br>registration |

|    | Nationality of owners |             |  |
|----|-----------------------|-------------|--|
|    | Name                  | Nationality |  |
| 1. |                       |             |  |
| 2. |                       |             |  |
| 3. |                       |             |  |
| 4. |                       |             |  |
| 5. |                       |             |  |

| Name of Bidders officers / Persons to be contacted |         |            |      |  |
|--|---------|------------|------|--|
| Name.  | Address | Phone Nos. | Fax. |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |
|  |         |            |      |  |

# Application Form (1A)

### Structure and Organization

| The applicant is an individual a proprietary firm a firm in partnership a Limited Company or Corporation a group of firms/consortium (if Yes, give completion information in respect of each partner) Attach the Organization Chart showing the structure of the organization including the names of the Directors and position of officers |  |
|---|--|
| Number of years of experience: as a Prime Contractor (contractor shouldering major responsibility in own country other countries (specify country) in a consortium in own country other countries (Specify country) as a sub-contractor (specify main contractor) in own country other countries (Specify country)                          |  |
| 4. Name and address of any associates the applicant has in India (in case the applicant happens to be from foreign country) who are knowledgeable in the procedures of customs, immigration, taxes and other information necessary to do the work.  For how many years has your organization been in business of                            |  |
| similar work under its present name? What were your fields when your organization was established? Whether any new fields were added in your organization? And if so, when?   |  |

| 5. Were you ever required to suspend construction for a period of more than six months continuously after you started? If so, give the name of project and give reasons thereof. |  |
|--|--|
| 6. Have you ever left the work awarded to you incomplete? If so, give name of project and reasons for not completing work.   |  |
| In which fields of civil engineering construction do you claim specialization and interest?  |  |
| Give details of your experience in mechanized cement concrete lining and in modern concrete technology for manufacture and quality control.                                      |  |
| Give details of your experience in using heavy earth moving equipment and quality control in compaction of soils.  |  |
| Give details of your experience in Underground Drainage work in rocky area.  |  |
| Give details of civil work for drainage pumping station  |  |
| Give details for construction of sewerage treatment plant  |  |
| Give details for pumping machinery in drainage pumping station   |  |

# GENERAL CONDITIONS OF CONTRACT

#### :: TABLE OF CONTESTS ::

| GC-1 Definitions and Interpretations GC-2 Location of site and accessibility GC-3 Scope of work GC-4 Ruling language GC-5 Interpretation of Contract Document GC-6 Contractor to understand himself fully GC-7 Errors in submissions GC-8 Sufficiency of E-TENDER GC-9 Discrepancies GC-10 Performance Guarantee (Security Deposit) GC-11 Inspection of work GC-12 Defect Liability GC-13 Power of Engineer-In-Charge to give further instructions. GC-14 Programme GC-15 Sub-letting of work GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's responsibility with the other Contractor and Agencies. GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Power of entry GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver GC-45 Laws governing the contract  | No.   | Description                 |
|--|-------|-----------------------------|
| GC-2 Location of site and accessibility GC-3 Scope of work GC-4 Ruling language GC-5 Interpretation of Contract Document GC-6 Contractor to understand himself fully GC-7 Errors in submissions GC-8 Sufficiency of E-TENDER GC-9 Discrepancies GC-10 Performance Guarantee (Security Deposit) GC-11 Inspection of work GC-12 Defect Liability GC-13 Power of Engineer-In-Charge to give further instructions. GC-14 Programme GC-15 Sub-letting of work GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-31 Rights of various interests GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Payments due from the Contractor GC-30 Power of Derive Office of Sub-contractor GC-31 Default of Contractor GC-32 Contractor's subordinates Sub-contractor GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-40 Breach of Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-44 Declaration against waiver |       | Description  Description    |
| GC-3 Scope of work GC-4 Ruling language GC-5 Interpretation of Contract Document GC-6 Contractor to understand himself fully GC-7 Errors in submissions GC-8 Sufficiency of E-TENDER GC-9 Discrepancies GC-10 Performance Guarantee (Security Deposit) GC-11 Inspection of work GC-12 Defect Liability GC-13 Power of Engineer-In-Charge to give further instructions. GC-14 Programme GC-15 Sub-letting of work GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-44 Declaration against waiver   |       |                             |
| GC-4 Ruling language GC-5 Interpretation of Contract Document GC-6 Contractor to understand himself fully GC-7 Errors in submissions GC-8 Sufficiency of E-TENDER GC-9 Discrepancies GC-10 Performance Guarantee (Security Deposit) GC-11 Inspection of work GC-12 Defect Liability GC-13 Power of Engineer-In-Charge to give further instructions. GC-14 Programme GC-15 Sub-letting of work GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Rights of various interests GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-40 Breach of Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   |       |                             |
| GC-5 Interpretation of Contract Document GC-6 Contractor to understand himself fully GC-7 Errors in submissions GC-8 Sufficiency of E-TENDER GC-9 Discrepancies GC-10 Performance Guarantee (Security Deposit) GC-11 Inspection of work GC-12 Defect Liability GC-13 Power of Engineer-In-Charge to give further instructions. GC-14 Programme GC-15 Sub-letting of work GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-44 Declaration against waiver   |       |                             |
| GC-6 Contractor to understand himself fully GC-7 Errors in submissions GC-8 Sufficiency of E-TENDER GC-9 Discrepancies GC-10 Performance Guarantee (Security Deposit) GC-11 Inspection of work GC-12 Defect Liability GC-13 Power of Engineer-In-Charge to give further instructions. GC-14 Programme GC-15 Sub-letting of work GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-44 Declaration against waiver  |       |                             |
| GC-7 Errors in submissions GC-8 Sufficiency of E-TENDER GC-9 Discrepancies GC-10 Performance Guarantee (Security Deposit) GC-11 Inspection of work GC-12 Defect Liability GC-13 Power of Engineer-In-Charge to give further instructions. GC-14 Programme GC-15 Sub-letting of work GC-16 Sub-letting of work GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's ubbordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Default of Contractor GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-8 Sufficiency of E-TENDER GC-9 Discrepancies GC-10 Performance Guarantee (Security Deposit) GC-11 Inspection of work GC-12 Defect Liability GC-13 Power of Engineer-In-Charge to give further instructions. GC-14 Programme GC-15 Sub-letting of work GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   |       |                             |
| GC-9 Discrepancies GC-10 Performance Guarantee (Security Deposit) GC-11 Inspection of work GC-12 Defect Liability GC-13 Power of Engineer-In-Charge to give further instructions. GC-14 Programme GC-15 Sub-letting of work GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-10 Performance Guarantee (Security Deposit) GC-11 Inspection of work GC-12 Defect Liability GC-13 Power of Engineer-In-Charge to give further instructions. GC-14 Programme GC-15 Sub-letting of work GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   |       |                             |
| GC-11 Inspection of work GC-12 Defect Liability GC-13 Power of Engineer-In-Charge to give further instructions. GC-14 Programme GC-15 Sub-letting of work GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-12 Defect Liability GC-13 Power of Engineer-In-Charge to give further instructions. GC-14 Programme GC-15 Sub-letting of work GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   |       |                             |
| GC-13 Power of Engineer-In-Charge to give further instructions. GC-14 Programme GC-15 Sub-letting of work GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-14 Programme GC-15 Sub-letting of work GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-15 Sub-letting of work GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-16 Sub-Contracts for temporary works, etc. GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-17 Time for completion GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-18 Extension of time GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-19 Contract Agreement GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-20 Liquidated damages GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   |       |                             |
| GC-21 Forfeiture of Security Deposit GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-22 Action of Forfeiture of Security Deposit GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   |       |                             |
| GC-23 No compensation for alteration in or restriction in work GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-24 In the event of death of contractor GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   |       |                             |
| GC-25 Members of the owner not individually liable GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   |       | •                           |
| GC-26 Owner not bound by personal representations GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-27 Contractor's office at site GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-28 Contractor's subordinate staff and their conduct GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-29 Termination of sub-contract by owner GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   |       |                             |
| GC-30 Power of entry GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-31 Contractor's responsibility with the other Contractor and Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   |       | ,                           |
| Agencies. GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   |       |                             |
| GC-32 Other Agencies at site GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   | GC-31 |                             |
| GC-33 Notices GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-34 Rights of various interests GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-35 Price adjustments GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-36 Terms of Payment GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-37 Retention Money GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   |       |                             |
| GC-38 Payments due from the Contractor GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   |       |                             |
| GC-39 Contingent Fee GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-40 Breach of Contract by Contractor GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver   |       |                             |
| GC-41 Default of Contractor GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-42 Bankruptcy GC-43 Ownership GC-44 Declaration against waiver  |       |                             |
| GC-43 Ownership GC-44 Declaration against waiver   |       |                             |
| GC-44 Declaration against waiver   |       |                             |
|  |       |                             |
| GC-45 Laws governing the contract  |       |                             |
|  |       |                             |
| GC-46 Over payment and under payment   |       |                             |
| GC-47 Settlement of disputes   |       |                             |
| GC-48 Disputes of differences to be referred to  |       | •                           |
| GC-49 Arbitration  |       |                             |
| GC-50 Termination of the Contract  | GC-50 | Termination of the Contract |

| GC-51 | Special risks  |
|-------|--|
| GC-52 | Change in Constitution                                     |
| GC-53 | Sub-contractual relations                                  |
| GC-54 | Patents and Royalties                                      |
| GC-55 | Lien   |
| GC-56 | Execution of work  |
| GC-57 | Work in monsoon  |
| GC-58 | Work on Sundays and Holidays                               |
| GC-59 | General Conditions for construction work                   |
| GC-60 | Drawings to be supplied by the Owner                       |
| GC-61 | Drawings to be supplied by the Contractor                  |
| GC-62 | Setting outwork  |
| GC-63 | Responsibilities of Contractor for correctness of work     |
| GC-64 | Materials to be supplied by the Owner                      |
| GC-65 | Conditions of issue of materials by the Owner              |
| GC-66 | Materials procured with assistance of the Owner            |
| GC-67 | Materials obtained from dismantling                        |
| GC-68 | Article of value of treasure found during construction     |
| GC-69 | Discrepancies between instructions                         |
| GC-70 | Alternations in specifications and designs and extra work. |
| GC-71 | Action when no specifications are issued                   |
| GC-72 | Abnormal rates   |
| GC-73 | Assistance to Engineer-In-Charge                           |
| GC-74 | Tests for quality of work                                  |
| GC-75 | Action and compensation in case of bad workmanship         |
| GC-76 | Suspension work  |
| GC-77 | Owner may do part of the work                              |
| GC-78 | Possession prior to completion                             |
| GC-79 | Completion Certificate                                     |
| GC-80 | Schedule of Rates  |
| GC-81 | Procedure for measurement of work in progress              |
| GC-82 | Running account payments to be regarded as advances        |
| GC-83 | Notice for claim for additional payment                    |
| GC-84 | Payment of Contractor's Bill                               |
| GC-85 | Final Bill   |
| GC-86 | Receipt for payment  |
| GC-87 | Completion Certificate                                     |
| GC-88 | Taxes, Duties, etc.  |
| GC-89 | Insurance  |
| GC-90 | Damage to Property   |
| GC-91 | Contractor to Indemnify Owner                              |
| GC-92 | Implementation of Apprentice Act 1954                      |
| GC-93 | Health and Sanitary arrangements for workers               |
| GC-94 | Safety Code  |
| GC-95 | Accidents  |

#### GC-01 DEFINITIONS AND INTERPRETATIONS:

- In the contract (as hereinafter defined) the following words and expressions shall, unless repugnant to the subject or context thereof, have the following means as signed to them.
- 1.1 The "Owner / Corporation" shall mean Rajkot Municipal Corporation and shall include its Municipal Commissioner or other Officers authorized by the Corporation and also include owner's successors and assignees.
- The "Contractor" shall mean the person or the persons, firm or Company whose e-Tender has been accepted by the Owner and includes the Contractors legal representative, his successors and permitted assigned.

#### 1.3 DELETED

- 1.4 The "Engineer-In-Charge" shall mean the person designated as such by the owner from time to time and shall include those who are expressly authorized by the Corporation to act for and on its behalf for all functions pertaining to the operation of this contract.
- 1.5 Engineer-In-Charge's Representative shall mean any resident Engineer or Assistant to the Engineer-In-Charge appointed from time to time by the owner to perform duties set forth in the E-TENDER Document whose authority shall be notified in writing to the Contractor by the Engineer-In-Charge.
- 1.6 "E-TENDER" the offer or proposal of the Bidder submitted in the prescribed form setting for the prices for the work to be performed, and the details thereof.
- 1.7 "Contract Price" shall mean total money payable to the Contractor under the contract. (This includes estimated amount as well as GST and Contractors' premium)
- 1.8 "Addenda" shall mean the written or graphic notices issued prior to submission of e-Tender which modify or interpret the contract documents.
- 1.9 "Contract Time" the time specified for the completion of work.
- 1.10 "Contract" shall mean agreement between the parties for the execution of works including therein all contract documents.
- "Contract Document" shall mean collectively the e-Tender documents, designs, drawings, specifications, agreed variations, if any and such other documents constituting the e-Tender and acceptance thereof.
- "The Sub-Contractor" shall mean any person, firm or company (other than the Contractor) to whom any part of the work has been entrusted by the Contractor with the written consent of the Engineer-In-Charge and the legal representative successors and permitted assignee of such person, firm or company.
- The "Specifications" shall mean all directions, the various Technical Specifications, provisions and requirements attached to the contract which pertains to the method and manner of performing the work, to the quantities and qualities of the work and the materials to be furnished under the contract for the work and any order(s) or instruction(s) there under. It shall also mean the latest Indian Standard Institute Specification

relative to the particular work or part thereof, so far as they are not contrary to the E-TENDER specifications and in absence of any other Country applied in Indian as a matter of standard engineering practice and approved in writing by the Engineer-In-Charge with or without modification.

- 1.14 The "Drawings" shall include maps, plans, tracings, or prints thereof with any modification approved in writing by the Engineer-In-Charge and as such other drawings as may, from time to time, be furnished or approved in writing by the Engineer-In-Charge in connection with the work.
- The "Work" shall mean the works to be executed in accordance with the contract or the part thereof as the case may be and shall include extra, additional, altered or substituted works as required for the purpose of the contract. It shall mean the totality of the work by expression or implication envisaged in the contract and shall include all materials, equipment and labour required for or relative or incidental to or in connection with the commencement, performance and completion of any work and / or incorporation in the work.
- 1.16 The "Permanent Work" shall mean works which will be incorporated in and form part of the work to be handed over to the owner by the Contractor on completion of the contract.
- 1.17 The "Temporary Work" shall mean all temporary works of every kind required in or about the execution, completion and maintenance of the work.
- "Site" shall mean the land and other places, on, under, in or through which the permanent works are to be carried out and any other lands or places provided by the Corporation for the purpose of the contract together with any other places designated in the contract as forming part of the site.
- 1.19 The "Construction Equipment" shall mean all appliances / equipment of whatever nature required in or for execution, completion or maintenance of works or temporary works (as herein before defined) but does not include materials or other things intended to form or forming part of the permanent work.
- "Notice in writing or written Notice" shall mean a notice written, typed or in printed form delivered personally OR sent by Registered Post to the last known private or business address or Registered Office of the Contractor OR through e-mail OR mobile message shall be deemed to have been received in the ordinary course of post it would have been delivered.
- 1.21 The "Alteration / variation order" shall mean an order given in writing by the Engineer-In-Charge to effect additions or deletions from or alterations in the work.
- 1.22 "Final Test Certificate" shall mean the final test certificate issued by the owner within the provisions of the contract.
- 1.23 The "Completion Certificate" shall mean the certificate to be issued by the Engineer-In-Charge when the work has been completed and tested to his satisfaction.

- 1.24 The "Final Certificate" shall mean the final certificate issued by the Engineer-In-Charge after the period of defects liability is over and the work is finally accepted by the owner.
- "Defects Liability Period" shall mean the specified period between the issue of Completion Certificate and the issue of final certificate during which the Contractor is responsible for rectifying all defects that may appear in the works.
- "Approved" shall mean approved in writing including subsequent confirmation in writing of previous verbal approval and "Approval" means approved in writing including as aforesaid.
- 1.27 "Letter of Acceptance" shall mean an intimation by a letter to Bidder that his e-Tender has been accepted in accordance with the provisions contained therein.
- 1.28 "Order" and "Instructions" shall respectively mean any written order or instruction given by the Engineer-In-Charge within the scope of his powers in terms of the contract.
- "Running Account Bill" shall mean a bill for the payment of "On Account" money to the Contractor during the progress of work on the basis of work done and the supply of non-perishable materials to be incorporated in the work.
- "Security Deposit" shall mean the deposit to be held by the owner as security for the due performance of the contractual obligations.
- 1.31 The "Appointing Authority" for the purpose of Arbitration shall be the Municipal Commissioner, Rajkot Municipal Corporation.
- 1.32. "Retention Money" shall mean the money retained from R.A.Bills for the due completion of the "LET WORS".
- 1.33 Unless otherwise specifically stated, the masculine gender shall include the feminine and neuter genders and vice-versa and the singular shall include the plural and vice-versa.

#### GC-02 LOCATION OF SITE AND ACCESSIBILITY:

The intending bidders should inspect the site & make thyself familiar with site conditions and available communication facilities.

Non-availability of access roads shall in no case be the cause to condone delay in the execution of the work and no claim or extra compensation will be paid.

#### GC-03 SCOPE OF WORK:

The scope of work is defined broadly in the special conditions of contract and specifications. The Contractor shall provide all necessary materials, equipment and labour etc. for the execution and maintenance of the work. All material that go with the work shall be approved by the Engineer-In-Charge prior to procurement and use.

#### **Power Supply:**

The Contractor shall make his own arrangement for power supply during installation.

#### **Land for Contractor's Field Office, Godown Etc.:**

Owner will not be in a position to provide land required for Contractor's field office, godown, etc. The Contractor shall have to make his own arrangement for the same.

#### GC-04 RULING LANGUAGE:

The language according to which the contract shall be construed and interpreted shall be English. All entries in the contract document and all correspondence between the contractor and the Corporation or the Engineer-In-Charge shall be in English/Gujarati. All dimensions for the materials shall be given in metric units only.

#### GC-05 <u>INTERPRETATION OF CONTRACT DOCUMENT</u>:

- 1. The provision of the General Conditions of Contract and Special Conditions of Contract shall prevail over those of any other documents of the contract unless specifically provided otherwise, should have there be any discrepancy, inconsistency, error or omission in the several documents forming the contract, the matter may be referred to the Engineer-In-Charge for his instructions and decision. The Engineer-In-Charge's decision in such case shall be final and binding to the Contractor.
- 2. Works shown upon the drawings but not described in the specifications or described in the specifications without showing on the drawings shall be taken as described in the specifications and shown on the drawings.
- The headings and the marginal notes to the clause of these General Conditions of Contract or to the specifications or to any other part of e-Tender documents are solely for the purpose of giving a concise indication and not a summary of contents thereof. They shall never be deemed to be part thereof or be used in the interpretation or construction of the contract.
- 4. Unless otherwise states specifically, in this contract documents the singular shall include the plural and vice-versa wherever the context so requires. Works imparting persons shall include relevant Corporations / Body of individual / firm of partnership.
- 5. Notwithstanding the sub-division of the documents into separate section and volumes every part of each shall be supplementary to and complementary of every other part and shall be read with and into the context so far as it may be practicable to do so.
- 6. Where any portion of the General Conditions of Contract is repugnant to or at variance with any provisions of the Special Conditions of Contract, then, unless a different intention appears, the provisions of the special conditions of contract shall be deemed to over ride the provisions of General Conditions of Contract to the extent of each repugnancy of variance.
- 7. The materials, design, and workmanship shall satisfy the relevant IS, and codes referred to. If additional requirements are shown in the specifications, the same shall be satisfied over and above IS and other codes.

8. If the specifications mention that the Contractor shall perform certain work or provide certain facilities, it shall mean that the Contractor shall do so at his own cost.

#### 9. Contractor to Collect His Own Information -

The details given in the e-Tender are arranged making necessary investigations for framing an estimate. However, when the work is being executed, changes in soil conditions are likely to be met with in view of the formation of soil, strata in Rajkot District. It is, therefore, desirable that the Contractor makes his own investigations or additional investigations as may be required for correctly assessing the cost of different items of work and submit his e-Tender accordingly. Any change in description or quantity of an item shall not vitiate the contract or release the Contractor from executing the work comprised in the contract according to the drawings and specifications at the e-Tendered rates.

He is deemed to have know the scope, nature and magnitude of the work and the requirements of materials and labour involved and as to whatever work he has to complete in accordance with the contract. The Contractor is expected to visit the site and surroundings to satisfy himself as to the nature of all existing structures, if any, and also as to the nature and the conditions of railways, roads, bridges and culverts, means of transport and communications whether by land, air or water and as to possible interruptions thereto and the access and gross from the site, to have examined and satisfied himself as to the sites for obtaining sand, stones, bricks and other materials, the site for disposal of surplus materials, the available accommodation and make such enquiries as may be necessary for executing and completing the work, to have local enquiries as to the sub-soil, subsoil water and variation thereof, storms, prevailing winds, climatic conditions and all other similar matters, effecting work. He is expected to be familiar with his liability for payment of Government taxes, customs and excise duty and other charges etc. in contract with the execution of this contract.

#### GC-06 CONTRACTOR TO UNDERSTAND HIMSELF FULLY:

The Contractor by e-Tendering shall be deemed to have satisfied himself, as to all considerations and circumstances affecting the e-Tender price, as to the possibility of executing the works as shown and described in the contract and to have fixed his prices according to his own view on these matters and to have understood that no additional allowances except as otherwise expressly provided, will afterwards be made beyond the contract price. The Contractor shall be responsible for any misunderstanding or incorrect information, however, obtained.

#### GC-07 <u>ERRORS IN SUBMISSIONS</u>:

The Contractor shall be responsible for any errors or omissions in the particulars supplied by him, whether such particulars have been approved by the Engineer-In-Charge or not.

#### GC-08 <u>SUFFICIENCY OF e-TENDER</u>:

The Contractor shall be deemed to have satisfied himself before e-Tendering as to the correctness of the e-Tender rates which rates shall, except as otherwise provides for, cover all the Contractor's liabilities and obligations set forth or implied in the contract for the proper execution of the work for compliance with requirements of Article GC-19 thereof.

#### GC-09 DISCREPANCIES:

The drawings and specifications are to be considered as mutually explanatory of each other, detailed drawings being followed in preference to small-scale drawings and figured dimensions in preference to scale and special conditions in preference to General Conditions. The special directions or dimensions given in the specifications shall supercede all else. Should any discrepancies however, appear or should any misunderstanding arise as to the meaning and intent of the said specifications or drawings, or as to the dimensions or the quality of the materials or the due and proper execution of the works, or as to the measurement or quality and valuation of the work executed under this contract or as extra there upon, the same shall be explained by the Engineer-In-Charge and his explanation shall be subject to the finaldecision of the Municipal Corporation in case reference be made to it, be binding upon the Contractor and the Contractor shall execute the work according to such explanation and without addition or to deduction from the contract price and shall also do all such works and things necessary for the proper completion of the works as implied by the drawings and specifications, even though such works and things are not specially shown and described in the said specifications. In cases where no particular specifications are given for any article to be used under the contract, the relevant specifications of the Indian Standard Institution shall apply.

#### GC-10 PERFORMANCE GUARANTEE (SECURITY DEPOSIT)

As a contract security the Bidder to whom the award is made shall furnish a performance guarantee (Security deposit) for the amount of **5%** of the contract price to guarantee the faithful performance, completion and maintenance of the works of the contract in accordance with all conditions and terms specified herein and to the satisfaction of the Engineer-in-charge and ensuring the discharge of all obligations arising from the execution of contract.

Additional performance quarantee is payable if,

- 3. the contract price offered by the selected bidder is lower than 10% but upto 20% of the estimated project cost than the additional performance security shall be calculated @ 20% of the difference in the estimated project cost minus 10% of the estimated project cost and Contract price offered by the selected bidder.
- 4. the contract price offered by the selected bidder is lower than 20% of the Estimated project cost than the additional performance security shall be calculated @ 30% of the difference in the Estimated project cost minus 10% of the Estimated project cost and Contract price offered by the selected bidder.

This additional performance security shall be treated as part of the performance security.

Performance security shall be valid beyond 60 days of the defect liability period and the additional performance security shall be valid beyond 28 days of project completion date.

Final SD will be calculated at the time of final bill i.e. actual completion amount.

Performance as mentioned above may be in the forms mentioned below:

- d) By a Demand Draft on the Rajkot Branch of any Nationalized Bank or Scheduled Bank except co-operative bank.
- e) A fixed deposit receipt of any Schedule Bank or Nationalized Bank (except Co-operative Bank) duly endorsed in favour of the <u>Raikot</u> <u>Municipal Corporation</u>, <u>Raikot</u>.
- f) A Bank Guarantee from Rajkot Branch of any Nationalized Bank or Scheduled Bank except co-operative bank.

The performance guarantee shall be delivered to the Corporation within ten (10) days of the notice of award and at least three (3) days before the contract agreement is signed unless otherwise specified by the Engineer-incharge. Alternatively, the contractor may at his option deposit an amount of **2.5%** of the value of the contract price within ten days and the balance **2.5%** to be recovered in installments through deduction @ the rate of 10% from the running account bills. It is further clarified that Performance Guarantee (SD) for extra work will also be recovered @ 10% from the bill of extra work i.e. works beyond tender amount.

On due performance and completion of the contract in all respects, THE PERFORMANCE GUARANTEE (SECURITY DEPOSIT) WILL BE RELEASED TO THE CONTRACTOR WITHOUT ANY INTEREST AFTER DEFECT LIABILITY PERIOD IS OVER.

#### **GC-11 INSPECTION OF WORK:**

1. The Engineer-In-Charge shall have full power and authority to inspect the work at any time wherever in progress either on the site or at the Contractor's or any other manufacturer's workshop or factories wherever situated and the Contractor shall afford to Engineer-In-Charge every facility and assistance to carry out such inspection, Contractor or his authorized representative shall, at all time during the usual working hours and all times when so notified, remain present to receive orders and instructions.

Orders given to Contractor's representative shall be considered to have the same force as if they had been given to the Contractor himself. Contractor shall give not less than ten (10) days notice in writing to the Engineer-In-Charge before covering up or otherwise placing beyond reach of inspection and measurement any work in order that the same may be inspected and measured. In the event of breach of the above, the same shall be uncovered at Contractor's expenses for carrying out such inspection or measurement.

2. The material shall be dispatched from Contractor's store on site of work before obtaining approval in writing of the Engineer-In-Charge. Contractor shall provide at all times during the progress of work and maintenance period of proper means of access with ladders, gangways, etc. and make necessary arrangement as directed for inspection or measurement of work by Engineer-In-Charge.

#### GC-12 DEFECT LIABILITY:

- Contractor shall guarantee the work for a period of **12 Months**. Any damage or defect that may arise or that may remain undiscovered at the time of issue of Completion Certificate connected in any way with the equipment or materials supplied by him or in the workmanship shall be rectified or replaced by Contractor at his own expense as desired by Engineer-In-Charge or in default Engineer-In-Charge may cause the same to be made good by other agency and deduct expenses of which the certificate of Engineer-In-Charge shall be final from any sums that may then or any time thereafter become due to Contractor or from his security deposit or the proceeds of sale thereof or of a sufficient portion thereof.
- 2. From the commencement to completion of work Contractor shall take full responsibility for the care of the work including all temporary works and in case any damages, occur from any cause whatsoever he shall at his own cost, repair and make good the same so that on completion, work shall be in good order and in conformity, in every respect, with the requirements of contract and as per the instructions of the Engineer-In-Charge.
- 3. If at any time before the work is taken over, the Engineer-In-Charge
  - a) Decide that any work done or materials used by the Contractor are defective or not in accordance with the contract or that work or any portion thereof is defective or do not fulfill the requirements of contract (all such materials being herein after called defects in this clause) he shall,

as soon as reasonably practicably, give notice to Contractor in writing of the said defect specifying particulars of the same then Contractor shall at his own expense and with all speed make good the defects so specified.

b) In case Contractor fails to do so, owner may take, at the cost of the Contractor, such stops as may in all circumstances be responsible to make good such defects. The expenditure so incurred by owner will be recovered from the amount due to Contractor. The decision of Engineer-In-Charge with regard to the amount to be recovered from Contractor will be final and binding on the Contractor.

# GC-13 <u>POWER OF ENGINEER-IN-CHARGE TO GIVE FURTHER INSTRUCTIONS</u>:

The Engineer-In-Charge shall have the power and authority from time to time and at all times to give further instructions and directions as may appear to him necessary or proper for the guidance of the Contractor and the works and efficient execution of the works according to the terms of the specifications, and the Contractor shall receive, execute, obey and be bound by the same, according to the true intent and meaning thereof, as fully and effectively as though the same had accompanied or had been mentioned or referred to in the specifications. No work which radically changes the original nature of the contract shall be ordered by the Engineer-In-Charge and in the event of any deviation being ordered, which in the opinion of the Contractor changes the original nature of the contract, he shall nevertheless carry it out and any disagreement as to the nature of the work and the rate to be paid to thereof shall be resolved.

The time of completion of works shall, in the event of any deviations being ordered resulting in additional cost or reduction in cost over the contract sum, be extended or reduced reasonably by the Engineer-In-Charge. The Engineer-In-Charge's decision in the case shall be final and binding.

#### GC-14 PROGRAMME:

The time allowed for execution of works shall be the essence of the contract. The contract period shall commence from the date of notice of intimation to proceed. The Bidder at the time of submitting his e-Tender shall indicate in the construction schedule his programme of execution of work commencement with the total time specified. The Contractor shall provide the Engineer-In-Charge a detailed programme of time schedule for execution of the works in accordance with the specifications and the completion date. The entire programme to be finalized by the Contractor, has to conform to the execution period mentioned along with the Bill of Quantities in the e-Tender documents. The Engineer-In-Charge upon scrutiny of such submitted programme by Contractor, shall examine suitability of it to the requirement of contract and suggest modifications, if found necessary.

#### GC-15 <u>SUB-LETTING OF WORK</u>:

No part of the contract nor any share of interest thereon shall in any manner or degree be transferred, assigned or sublet by the Contractor directly or indirectly to any person, firm or Corporation whosoever except as provided for in the succeeding sub-clause, without the consent in writing of the owner.

#### GC-16 SUB-CONTRACTS FOR TEMPORARY WORKS ETC.:

The owner may give written consent to sub-contractors for execution of any part of the works at the site, being entered upon the contractor provided each individual contract is submitted to the Engineer-In-Charge before being entered into and is approved by him. List of sub-contractors to be supplied.

Not-withstanding any subletting with such approval as aforesaid and notwithstanding the Engineer-In-Charge shall have received of any subcontractors, the Contractor shall be and shall remain solely responsible for the quality and proper and expeditious execution of the works and the performance of all the conditions of contract in all respects as if such subletting or subcontracting had not taken place and as if such works had been done directly by the Contractor.

#### GC-17 TIME FOR COMPLETION:

- The work covered under this contract shall be commenced from the date the Contractor is served with a notice to proceed with the work and shall be completed before the date as mentioned in the time schedule of work. The time is the essence of the contract and unless the same is extended as mentioned in Clause GC-18 "Extension of Time", the Contractor shall pay liquidated damages for the delay.
- 2. The general time schedule for construction is given in the e-Tender document. Contractor shall prepare a detailed weekly or monthly construction programme in consultation with the Engineer-In-Charge soon after the agreement and the work shall be strictly executed accordingly. The time for construction includes, the time required for testing, rectifications, if any, retesting and completion of the work in all respects to the entire satisfaction of the Engineer-In-Charge except the items which are not coming in the way to commission the project.
- 3. Monsoon period from 1st July to 30th September shall be considered as non-working period hence excluded in time limit.

#### GC-18 <u>EXTENSION OF TIME</u>:

Time shall be considered as the essence of the contract. If, however, the failure of the Contractor to complete the work as per the stipulated dates referred to above arises from delays on the part of Corporation in supplying the materials or equipment, it has undertaken to supply under the contract or from delays on the quantity of work to be done under the contract, or force majeure an appropriate extension of time will be given by the Corporation. The Contractor shall request for such extension within one month of the cause of such delay and in any case before expiry of the contract period.

#### GC-19 CONTRACT AGREEMENT:

The successful Bidder shall enter into and execute the contract agreement within 10 (ten) days of the notice of award, in the form shown in e-Tender documents with such modifications as may be necessary in the opinion of the Corporation. It shall be incumbent on the Contractor to pay the stamp duty and the legal charges for the preparation of the contract agreement.

#### GC-20 <u>LIQUIDATED DAMAGES</u>:

If the Contractor fails to complete the work or designated part thereof within the stipulated completion date for the work or for the part, he shall pay liquidated damages at 0.1 (zero point one) percent of contract value

for per day of delay subject to maximum of 10% of the contract value or as decided by Municipal Commissioner.

The Contractor shall complete one-sixth quantum of work within one fourth period, four-tenth quantum of work within one-half period and eight-tenth quantum of work within three-fourth period, failing which, the Contractor shall be liable to pay liquidated damages an amount as specified above, or as decided by Municipal Commissioner.

The amount of liquidated damages shall, however, be subjected to a maximum of 10 percent of the contract value.

#### **GC-21 FORFEITURE OF SECUEITY DEPOSIT:**

Whenever any claim against the Contractor for the payment of a sum of money out of or under the contract arises, the Corporation shall be entitled to recover such sum by appropriating in part or whole, the security deposit of the Contractor. In case the security deposit is insufficient, the balance recoverable shall be deducted from any sum then due or which at any time thereafter may become due to the Contractor. The Contractor shall pay to the owner on demand any balance remaining due.

#### GC-22 ACTION OF FORFEITURE OF SECURITY DEPOSIT:

In any case in which under any Clause or Clauses of the contract, the Contractor shall committed a breach of any of the terms contained in this contract, the owner shall have power to adopt any of the following courses as he may deem best suited to his interest.

- a) To rescind the contract (of which recession notice in writing to the contractor under the hand of the owner shall be conclusive evidence) in which case the security deposit of the Contractor shall stand forfeited and be absolutely at the disposal of the owner.
- b) To employ labour and to supply materials to carry out the balance work debiting Contractor with the cost of labour employed and the cost of materials supplied for which a certificate of the Engineer-In-Charge shall be final and conclusive against the Contractor and 10% of costs on above to cover all departmental charges and crediting him with the value of work done at the same rates as if it has been carried out by the Contractor under the terms of his contract. The certificate of Engineer-In-Charge as to the value of the work done shall be final and conclusive against the Contractor.
- c) To measure up the work of the contractor and to take such part thereof as shall be unexecuted out of his hand and give it to another Contractor to complete, the same. in this case the excess expenditure incurred than what would have been paid to the original Contractor, if the whole work had been executed by him, shall be borne and paid by the original Contractor and shall be deducted from any money due to him by the owner under the contract or otherwise and for the excess expenditure, the certificate of the Engineer-In-Charge shall be final and conclusive.

In the event any of the above courses being adopted by the owner, the Contractor shall have no claims for compensation for any loss sustained by him by reason of his having purchased or procured any materials or entered into any agreements or made any advance on account of or with a view to the execution of the work or the performance of the contract.

In purchase the Contractor shall not be entitled to recover or be paid any sum for any work actually performed under this contract unless the Engineer-In-Charge will certify in writing the performance of such work and the value payable in respect thereof and he shall only be entitled to be paid the value so certified.

In the event of the owner putting in force the powers as stated in a, b, c, above vested in him under the proceeding clause, he may, if he so desires, take possession of all or any tools and plant, materials and stores in or upon the works or the site thereof belonging to the Contractor, or procured by him and intended to be used for the execution of the work or any part thereof paying or allowing for the same in account at the contract rates to be certified by the Engineer-In-Charge. The Engineer-In-Charge may give notice in writing to the Contractor or his representative requiring him to remove such tools, plant, materials or stores from the premises within the time specified in the notice and in the event of the Contractor failing to comply with any such notice, the Engineer-In-Charge may remove them at the Contractor's expenses or sell them by auction or private sale on account of the Contractor and his risks in all respects without any further notice as to the date, time or place of the sale and the certificate of Engineer-In-Charge as to the expense of any such removal and the amount of the proceeds and the expenses of any such sale shall be final and conclusive against the Contractor.

#### GC-23 COMPENSATION FOR ALTERATION IN OR RESTRICTION IN WORK:

If at any time from the commencement of the work, the owner shall for any reasons whatsoever not require the whole work or part thereof as specified in the e-Tender to be carried out, the Engineer-In-Charge shall give notice in writing of the fact to the Contractor, who shall have no claim to any payment or compensation whatsoever on account of any profit or advantage which he might have derived from the execution of the work in full but which he did not derive in consequence of full amount of the work not having been carried out. He also shall not have any claim for compensation by reasons of any alterations having been made in original specifications, drawings, designs and instructions which shall involve any curtailment of the work as originally contemplated.

When the Contractor is a partnership firm, the prior approval in writing of the owner shall be obtained before any change is made in the Constitution of the firm. Where the Contractor is an individual or a Hindu Undivided Family or business concern, such approval as aforesaid shall, likewise be obtained before Contractor enters into an agreement with other parties where under, the reconstituted firm would have the right to carry out the work hereby undertaken by the Contractor. In either case, if prior approval as aforesaid is not obtained, the contract shall be deemed to have been allotted contravention of subletting clause hereof and the same action may be taken and the same consequence shall ensure as provided in the subletting clause.

#### GC-24 IN THE EVENT OF DEATH OF THE CONTRACTOR:

Without prejudice to any of the rights or remedies under the contract, if the Contractor dies, the owner shall have the option of terminating the contract without compensation to the Contractor.

#### GC-25 <u>MEMBERS OF THE OWNER NOT INDIVIDUALLY LIABLE</u>:

No official or employee of the owner shall in any way be personally bound or liable for the acts or obligation of the owner under the contract, or answerable for any default or omission in the observance or performance of any acts, matters or things, which are herein, contained.

#### GC-26 OWNER NOT BOUND BY PERSONAL REPRESENTATIONS:

The Contractor shall not be entitled to any increase on the schedule of rates or any other rights or claims whatsoever by reason of representation, promise or guarantees given or alleged to have been given to him by any person.

#### GC-27 CONTRACTOR'S OFFICE AT SITE:

The Contractor shall provide and maintain an office at the site for the accommodation of his agent and staff and such office shall remain open at all reasonable hours to receive information, notices or other communications.

#### GC-28 CONTRACTOR'S SUBORDINATE STAFF AND THEIR CONDUCT:

- The Contractor on award of the work shall name and depute a qualified Engineer having experience of carrying out work of similar nature, whom equipments, materials, if any, shall be issued and instructions for work given. the Contractor shall also provide to the satisfaction of Engineer-In-Charge sufficient and qualified staff, competent sub-agents, foreman and loading hands including those specially qualified by previous experience to supervise the type of works comprised in the contract in such manner as will ensure work of the best quality and expeditious working. If, in the opinion of the Engineer-In-Charge additional properly qualified supervision staff is considered necessary, it shall be employed by the Contractor, without additional charge on account thereof. The Contractor shall ensure to the satisfaction of the Engineer-In-Charge that sub-contractors, if any, shall provide competent and efficient supervision over the work entrusted to them.
- If and whenever any of the Contractor's or sub-contractor's agents, sub-2. agents, assistants, foreman or other employees shall, in the opinion of the Engineer-In-Charge, be guilty of any misconduct or be incompetent or insufficiently qualified or negligent in the performance of their duties or that in the opinion of the owner or Engineer-In-Charge, it is undesirable for administrative or any other reason for person or persons to be employed in the works, the Contractor if so directed by the Engineer-In-Charge, shall at once remove such person or persons from employment thereon. Any person or persons so removed shall not again be reemployed in connection with the works without the written permission of the Engineer-In-Charge. Any person, so removed from the works shall be immediately replaced at the expense of the Contractor by a qualified and competent substitute. Should the Contractor be required to repatriate any person removed from the works he shall do so after approval of Engineer-In-Charge and shall bear all costs in connection therewith.
- 3. The Contractor shall be responsible for the proper behavior of all the staff, foreman, workmen and others and shall exercise proper control over them and in particular and without prejudice to the said generality, the Contractor shall be bound to prohibit and prevent any employee from trespassing or acting in any way detrimental or prejudicial to the interest of the community or of the properties or occupiers of land and properties

in the neighborhood and in the event of such employees so trespassing, the Contractor shall be responsible therefore and relieve the owner of all consequent claims, actions for damages or injury or any other ground whatsoever. The decision of the Engineer-In-Charge upon any matter arising under this claim shall be final.

4. If and when required by the owner, the Contractor's personnel entering upon the owner's premises shall be properly identified by badges of a type acceptable to the owner which must be worn at all times on owner's premises.

#### GC-29 <u>TERMINATION OF SUB-CONTRACT BY OWNER</u>:

If any sub-contractor engaged upon the works at the site execute any work which in the opinion of Engineer-In-Charge is not accordance with the contract documents, the owner may by written notice to the Contractor request him to terminate such sub-contract and the Contractor upon the receipt of such notice shall terminate such sub-contracts and the latter shall forthwith leave the works, failing which, the owner shall have the right to remove such sub-contractors from the site.

No action taken by the owner under the above clause shall relieve the Contractor of his liabilities under the contract or give rise to any right to compensation, extension of time or otherwise.

#### GC-30 POWER OF ENTRY:

If the Contractor shall not commence the work in the manner previously described in the contract documents or if he shall at any time, in the opinion of Engineer-In-Charge –

- i) Fail to carry out works in conformity with the contract documents, or
- ii) Fail to carry out the works in accordance with the time schedule, or
- iii) Substantially suspend work or the works for a period of seven days without authority from Engineer-In-Charge, or
- iv) Fail to carry out and execute the work to the satisfaction of the Engineer-In-Charge, or
- v) Fail to supply sufficient or suitable construction plant, temporary works, labour, materials or things, or
- vi) Commit breach of any other provisions of the contract on his part to be performed or observed or persists in any of the above mentioned breaches of the contract for seven days after notice in writing shall have been given to the Contractor by the Engineer-In-Charge requiring such breach to be remedied, or
- vii) Abandon the work, or
- viii) During the continuance of the contract becomes bankrupt, make any arrangement or compromise with his creditors, or permit any execution to be levied or go into liquidation whether compulsory or voluntary not being merely a voluntary liquidation for the purpose of amalgamation or reconstruction then in any such case.

The owner shall have the power to enter upon the works and take possession thereof and of the materials, temporary works, constructional plant and stores therein and to revoke the Contractor's license to use the same and to complete the works by his agents, other Contractor or workmen, to relate the same upon any terms to such other person firm or Corporation as the owner in his absolute discretion may think proper to employ, and for the purpose aforesaid to use or authorize the use of any materials, temporary works, constructional plant, and stores as aforesaid

with making payments or allowance to the Contractor for the said materials other than such as may be certified in writing by the Engineer-In-Charge to be reasonable and without making any payment or allowance to the Contractor for the use of said temporary works, constructional plant and stock or being liable for loss or damage thereto. If the owner shall be reason of his taking possession of the works or of the work being got completed by other Contractor incurred excess expenditure be deducted from any money which may be due for the work done by the Contractor under the contract and not paid for. Any deficiency shall forthwith be made good and paid to the owner by the Contractor and the owner shall have power to sell in such manner and for such price as he may think fit all or any of the constructional plant, materials etc., consist constructed by or belonging to and to recoup and retain the said deficiency or any part thereof out of the proceeds of the sale.

# GC-31 <u>CONTRACTOR'S RESPONSIBILITY WITH THE OTHER CONTRACTOR</u> AND AGENCIES:

Without repugnance to any other conditions, it shall be the responsibility of the Contractor executing the work, to work in close co-operation and co-ordination with other Contractors or their authorized representatives and the Contractor will put a joint scheme with the concurrence of other contractors or their authorized representatives showing the arrangements for carrying his portion of the work to the Engineer-In-Charge and get the approval. The Engineer-In-Charge before approving the joint scheme will call the parties concerned and modify the scheme if required. No claim will be entertained on account of the above. The Contractor shall conform in all respects with the provisions of any statutory regulations, ordinances or bylaws of any local or duly constituted authorities or public bodies which may be applicable from time to time to works or any temporary works. The Contractor s shall keep the owner indemnified against all penalties and liabilities of every kind arising out of non-adherence to such statutes, ordinance, laws, rules, regulations etc.

#### GC-32 OTHER AGENCIES AT SITE:

The Contractor shall have to execute the work in such place and condition where other agencies will also be engaged for other works, such as site grading, filling and leveling, electrical and mechanical engineering works etc. No claim shall be entertained for works being executed in the above circumstances.

#### GC-33 NOTICES:

Any notice under this contract may be served on the Contractor or his duly authorized representative at the job site or may be served by Registered Post direct to the official address of the Contractor. Proof of issue of any such notice could be conclusive of the Contractor having been duly informed of all contents therein.

#### GC-34 RIGHTS OF VARIOUS INTERESTS:

The owner reserves the right to distribute the work between more than one Contractor. Contractor shall co-operate and afford reasonable opportunity to other Contractor s for access to the works, for the carriage and storage of materials and execution of their works. Whenever the work being done by department of the owner or by other Contractor employed by the owner is contingent upon work covered by this contract, the respective rights of the various interests shall be determined by the Engineer-In-Charge to secure the completion of various portions of the work in general harmony.

#### GC-35 PRICE ADJUSTMENTS:

No adjustment in price shall be allowed and no price escalation will be allowed.

#### GC-36 <u>TERMS OF PAYMENT</u>:

The payment of bills shall be made progressively according to the rules and practices followed by the Corporation. The progressive payment unless otherwise provided in the contract agreement or subsequently agreed to by the parties shall be made generally monthly on submission of a bill by the Contractor in prescribed form of an amount according to the value of the work performed less the price of materials supplied by owner aggregate of previous progressive payments and as required by Clause GC-37 (Retention of Money) herein. All such progressive payments shall be regarded as payments by way of advance against final payment. Payment for the work done by the Contractor will be based on the measurement at various stages of the work, in accordance with the condition at clause GC-81 (measurement of work in progress).

#### GC-37 RETENTION MONEY:

Pursuance to clause GC-36 (Terms of Payment) any on at money due to the Contractor for work done, Corporation will hold as Retention money five (5) percent of the value of work. The retention money will not normally be due for payment until the completion of the entire work and till such period the work has been finally accepted by the Corporation and a completion certificate issued by the Corporation in pursuant to Clause-GC 79 (Completion Certificate).

#### GC-38 PAYMENTS DUE FROM THE CONTRACTOR:

All costs, damages or expenses, for which under the contract, Contractor is liable to the Corporation, may be deducted by the Corporation from any money due or becoming due to the Contractor under the contract or from any other contract with the Corporation or may be recovered by action at law or otherwise from the Contractor.

#### GC-39 <u>CONTINGENT FEE</u>:

- i) The Contractor warrants that he has not employed a person to solicit or secure the contract upon any agreement for a commission, percentage, and brokerage contingent fee. Breach of this warranty shall give the Corporation the right to cancel the contract or to take any drastic measure as the Corporation may deem fit. The warranty does not apply to commissions payable by the Contractor to establish commercial or selling agent for the purpose of securing business.
- ii) No officer, employer or agent of the Corporation shall be admitted to any share or part of this contract or to any benefit that may rise there from.

#### GC-40 BREACH OF CONTRACT BY CONTRACTOR:

If the Contractor fails to perform the work under the contract with due diligence or shall refuse or neglect to comply with instructions given to him in writing by the Engineer-In-Charge in accordance with the contract, or shall contravene the provisions of the contract, the Corporation may give notice in writing to the Contractor to make good such failure, neglect, or contravention. Should the Contractor fail to comply with such written notice within 10 (Ten) days of receipt, it shall be lawful for the Corporation, without prejudice to any other rights the Corporation may have under the contract, to terminate the contract for all or part of the

works, and make any other arrangements it shall deem necessary to complete the work outstanding under the contract at the time of termination. In this event, the performance Bond shall immediately become due and payable to the Corporation. The value of the work done on the date of termination and not paid for shall be kept as deposit for adjustment of excess expenditure incurred in getting the remaining work completed and the Corporation shall have free use of any works which the Contractor may have at the site at the time of termination of the contract.

If Contractor fails to carry out the work in timely manner as mentioned in clause 20 (Liquidated damages), Rajkot Municipal Corporation may give notice in writing to the Contractor to expedite the work, so that the work can be completed as per time schedule. If Contractor fails to expedite the work within 10 days of receipt of notice, Rajkot Municipal Corporation may terminate the contract and debar the Contractor for three years and the remaining work will be executed through other agency at the risk and cost of the Contractor.

#### GC-41 DEFAULT OF CONTRACTOR:

- i) The Corporation may upon written notice of default to the Contractor terminate the contract circumstances detailed as under:
  - a) If in the opinion of the Corporation, the Contractor fails to make completion of works within the time specified in the completion schedule or within the period for which extension has been granted by the Corporation to the Contractor.
  - b) If in the opinion of the Corporation, the Contractor fails to comply with any of the other provisions of this contract.
- ii) In the event, the Corporation terminates the contract in whole or in part as provided in Article GC-50 (Termination of the Contract) the Corporation reserves the right to purchase upon such terms and in such manner as it may be deem appropriate, plant similar to one which is not supplied by the Contractor and the Contractor will be liable to the Corporation for any additional costs for such similar plant and / or for liquidated damages for delay until such time as may be required for the final completion of works.
- iii) If this contract is terminated as provided in this paragraph GC-40 AND/OR GC-30 (Power of Entry) (1) the Corporation in addition to any other rights provided in this clause, may require the Contractor to transfer title and deliver to the Corporation.
  - a) Any completed works
  - b) Such partially completed information and contract rights as the Contractor has specifically produced or acquired for the performance of the contract so terminated.
- iv) In the event, the Corporation does not terminate the contract as provided in the paragraph GC-50 (Termination of Contract) the Contractor shall continue performance of the contract, in which case, he shall be liable to the Corporation for liquidated damages for delay until the works are completed and accepted.

#### GC-42 BANKRUPTCY:

If the Contractor shall become bankrupt or insolvent or has a receiving order made against him, or compound with his creditors, or being the

Corporation commence to be wound up not being a member voluntary winding up for the purpose of amalgamation or reconstruction, or carry on its business under a receiver for the benefit of his creditors or any of them, the Corporation shall be at liberty to either (a) terminate the contract forthwith by giving notice in writing to the Contractor or to the receiver or liquidator or to any person or Organization in whom the contract may become vested and to act in the manner provided in Article GC-41 (Default of Contractor) as thought the last mentioned notice had been the notice referred to in such article or (b) to give such receiver, liquidator or other persons in whom the contract may become vested the option of carrying out the contract subject to his providing a satisfactory guarantee for the due and faithful, performance of the contract up to an amount to be agreed. In the event that the Corporation terminates the contract in accordance with this article, the performance bond shall immediately become due and payable on demand to Corporation.

#### GC-43 OWNERSHIP:

Works hand over pursuant to the contract shall become the property of the Corporation from whichever is the earlier of the following times, namely;

- a) When the works are completed pursuant to the contract.
- b) When the contractor has been paid any sum to which he may become entitled in respect thereof pursuant to Clause GC-36 (Terms of Payment).

#### GC-44 <u>DECLARATION AGAINST WAIVER</u>:

The condemnation by the Corporation of any breach or breaches by the Contractor or an authorized sub-contractor of any of the stipulations and conditions contained in the contract, shall in no way prejudice or affect or be construed as a waiver of the Corporation's rights, powers and remedies under the contract in respect of any breach or breaches.

#### GC-45 LAWS GOVERNING THE CONTRACT:

This contract shall be construed according to and subject to the laws of India and the State of Gujarat and under the jurisdiction of the Courts of Gujarat at Rajkot.

#### GC-46 OVER PAYMENT AND UNDER PAYMENT:

Whenever any claim for the payment of a sum to the Corporation arises out of or under this contract against the Contractor, the same may be deducted by the Corporation from any sum then due or which at any time thereafter may become due to the Contractor under this contract and failing that under any other contract with the Corporation (which may be available with the Corporation), or from his retention money or he shall pay the claim on demand. The Corporation reserves the right to carry out post payment audit and technical examinations of the final bill including all supporting vouchers, abstracts etc. The Corporation further reserves the right to enforce recovery of any payment when detected, not withstanding the fact that the amount of the final bill may be included by one of the parties as an item of dispute before an Arbitrator, appointed under Article GC-49 (Arbitration) of this contract and notwithstanding the fact that the amount of the final bill figures in the arbitration award. If as a result of such audit and technical examinations any over payment is discovered in respect of any work done by the Contractor or alleged to have been done by him under the contract, it shall be recovered by the Corporation from the Contractor as prescribed above. If any under payment is discovered by the Corporation, the amount due to the Contractor under this contract,

may be adjusted against any amount then due or which may at any time thereafter become due before payment is made to the Contractor.

#### **GC-47 SETTLEMENT OF DISPUTES**:

Except as otherwise specifically provided in the contract, all disputes concerning questions of fact arising under the contract shall be decided by the Engineer-In-Charge subject to a written appeal by the Contractor to the Engineer-In-Charge and those decisions shall be final and binding on the parties hereto. Any disputes or differences including those considered as such by only one of the parties arising out of or in connection with this contract shall be to the extent possible settled amicably between the parties. If amicable settlement cannot be reached then all disputed issues shall be settled as provided in Article GC-48 (Disputes or differences to be referred to) and Article No.GC-49 (Arbitration).

#### GC-48 <u>DISPUTES OF DIFFERENCES TO BE REFERRED TO</u>:

If at any time, any question, disputes or differences of any kind whatsoever shall arise between the Engineer-In-Charge and the contractor upon or in relation to or in connection with this contract either party may forthwith give to the other, notice in writing of the existence of such question, dispute or difference as to any decision, opinion, instruction, direction, certificate or evaluation of the Engineer-In-Charge. The question, dispute or differences shall be settled by the Municipal Commissioner, Rajkot Municipal Corporation, who shall state his decision in writing and give notice of same to the Engineer-In-Charge and to the Contractor. Such decision shall be final and binding upon both parties. The contract and work on contract if not already breached or abandoned shall proceed normally unless and until the same shall be revised (or uphold) by any arbitration proceedings as hereinafter provided. Such decisions shall be final and binding on the Engineer-In-Charge and the Contractor unless the Contractor shall require the matter to be referred to an Arbitration panel as hereinafter provided.

#### GC-49 ARBITRATION:

In case of any dispute arising during the course of execution, the matter should be referred to Municipal Commissioner who will be sole Arbitrator whose decisions will be final and binding to the Contractor.

The word "Arbitration" or "Arbitration Clause" wherever mentioned in this tender document, is to be treated to be referred to GC-49. In this context, an Order bearing No.RMC/Legal/1858 dated 18-02-2017 of Legal Department of Rajkot Municipal Corporation is uploaded separately along with this tender, which Order, will hereafter referred and taken into consideration for Arbitration related purpose.

#### GC-50 <u>TERMINATION OF THE CONTRACT</u>:

- i) If the Contractor finds it impracticable to continue operation owing to force majeure reasons or for any reasons beyond his control and/or the Corporation find it impossible to continue operation, then prompt notification in writing shall be given by the party affected to the other.
- ii) If the delay or difficulties so caused cannot be expected to cease or become unavoidable or if operations cannot be resumed within two (2) months then either party shall have the right to terminate the contract upon ten (10) days written notice to the other. In the event of such termination of the contract, payment to the Contractor will be made as follows:

- a) The Contractor shall be paid for all works approved by the Engineer-In-Charge and for any other legitimate expenses due to him.
- b) If the Corporation terminates the contract owing to Force Majeure or due to any cause beyond its control, the Contractor shall additionally be paid for any work done during the said two (2) months period including any financial commitment made for the proper performance of the contract and which are not reasonably defrayed by payments under (a) above.
- c) The Corporation shall also release all bonds and guarantees at its disposal except in cases where the total amount of payment made to the Contractor exceeds the final amount due to him in which case the Contractor shall refund the excess amount within thirty (30) days after the termination and the Corporation thereafter shall release all bonds and guarantees. Should the Contractor fail to refund the amounts received in excess within the said period such amounts shall be deducted from the bonds or guarantees provided.
- iii) On termination of the contract for any cause the Contractor shall see the orderly suspension and termination of operations, with due consideration to the interests of the Corporation with respect to completion safeguarding of storing materials procured for the performance of the contract and the salvage and resale thereof.

#### GC-51 <u>SPECIAL RISKS</u>:

If during the contract, there shall be an outbreak of war (whether war is declared or not), major epidemic, earthquake or similar occurrence in any part of the world beyond the control of either party to the contract which financially or otherwise materially affects the execution of the contract, the Contractor shall unless and until, the contract is terminated under the provisions of this article use his best endeavors to complete the execution of the contract, provided always that the Corporation shall be entitled at any item after the onset of such special risks, to terminate the contract by giving written notice to the contractor and upon such notice being given this contract shall terminate but without prejudice to the rights of either party in respect of any antecedent breach thereof.

The Contractor shall not be liable for payment of compensation for delay or for failure to perform the contract for reasons of Force Majeure such as acts of public enemy, acts of Government, fires, floods, cyclones, epidemics, quarantine restrictions, lockouts, strikes, freight embargoes and provided that the Contractor shall within 10 (ten) days from the beginning of such delay notify the Engineer-In-Charge in writing, of the cause of delay, the Corporation shall verify the facts and grant such extension as the facts justify.

#### GC-52 CHANGE IN CONSTITUTION:

Where the Contractor is a partnership firm, the prior approval in writing of the owner shall be obtained before any change is made in the constitution of the firm. Where the Contractor is an individual or undivided family business concern such approval as aforesaid shall likewise be obtained before the Contractor enters into any partnership agreement where under the partnership firm would have the right to carry out the works hereby undertaken by the Contractor. If prior approval as aforesaid is not obtained, the contract shall be deemed to have been assigned in contravention of contract.

#### GC-53 <u>SUB-CONTRACTUAL RELATIONS</u>:

All works performed for the contract by a sub-contractor shall be pursuant to an appropriate agreement between the Contractor and the sub-contractor, which shall contain provision to –

- a) Protect and preserve the rights of the Corporation and the Engineer-In-Charge with respect to the works to be performed under the subcontracting party will not prejudice such rights.
- b) Require that such work be performed in accordance with the requirements of contract documents.
- c) Require under such contract to which the contractor is a party, the submission to the Contractor of application for payment and claims for additional costs, extension of time, damages for delay or otherwise with respect to the sub-contracted portions of the work in sufficient time, that the Contractor may apply for payment comply in accordance with the contract documents for like claims by the Contractor upon the Corporation.
- d) Waive all rights the contracting parties may have against one another for damages caused by fire or other perils covered by the property insurance except such rights as they may have to the proceeds of such insurance held by the Corporation as trustee and,
- e) Obligate each sub-contractor specifically to consent to the provisions of this Article.

#### GC-54 PATENTS AND ROYALTIES:

- 1. Contractor, if licensed under any patent covering equipment, machinery, materials or composition of matter to be used or supplied or methods and process to be practiced or employed in the performance of this contract agrees to pay all royalties and license fees, which may be due with respect thereto. If any equipment, machinery, materials, composition matters, to be used or supplied or methods practiced or employed in the performance of this contract, is covered by a patent under which Contractor is not licensed, then the Contractor before supplying / using the equipment, machinery, materials, compositions, methods of process shall obtain such license and pay such royalties and license fees as may be necessary for performance of this contract. In the event Contractor fails to pay such royalty or to obtain any such license, any suit for infringement of such patents which is brought against the Contractor or the owner as a result of such failure will be defended by the Contractor at his own expenses and the Contractor will pay any damages and costs awarded in such suit. The Contractor shall promptly notify the owner if the Contractor has acquired knowledge of any plant under which a suit for infringement could be reasonably brought because of the use by the owner of any equipment machinery, materials, process methods to be supplied in hereunder. Contractor agrees to and does hereby grant to owner together with the right to extend the same to any of the subsidiaries of the owner an irrevocable royalty fee license to use in any Country, any invention made by the Contractor or his employees in or as a result of the performance of work under contract.
- 2. With respect to any sub-contract entered into by Contractor pursuant to the provisions of the relevant clause hereof, the Contractor shall obtain from the sub-contractor an understanding to provide the owner with the same patent protection that contracts is required to provide under the provisions of the clause.

3. The Contractor shall indemnify and save harmless the owner from any loss on account of claims against owner for the contributory infringement of patent rights arising out of and based upon the claim that the use by the Corporation of the process included in the design prepared by the Contractor and used in the operation of the plant infringes on any patent rights.

#### GC-55 LIEN:

If, at any time, there should be evidence of any lien or claim for which owner might have become liable and which is chargeable to the Contractor, the owner shall have the right to retain out of any payment then due or thereafter to become due an amount sufficient to completely indemnify the owner against such lien or claim or if such lien or claim be valid the owner may pay and discharge the same and deduct the amount as paid from any money which may be due or become due and payable to the Contractor. If any lien or claims remaining unsettled after all payments are made, the Contractor shall refund or pay to the owner all money that the latter may be compelled to pay in discharging such lien or claim including all costs and reasonable expenses.

#### GC-56 EXECUTION OF WORK:

The whole work shall be carried out in strict conformity with the provisions of the contract document, detailed drawings, specifications and the instructions of the Engineer-In-Charge from time to time. The Contractor shall ensure that the whole work is executed in the most substantial, and proper manner with best workmanship using materials of best quality in strict accordance with the specifications to the entire satisfaction of the Engineer-In-Charge.

#### GC-57 <u>WORK IN MONSOON</u>:

When the work continues in monsoon if required, the Contractor shall maintain minimum labour force required for the work and plan and execute the construction and erection work according to the prescribed schedule. No extra rate will be considered for such work in monsoon. During monsoon and entire construction period, the Contractor shall keep the site free from water at his own cost. However, monsoon period from 1st July to 30th September will be excluded in time limit.

#### GC-58 WORK ON SUNDAYS AND HOLIDAYS:

No work except curing shall be carried out on Sunday and holidays. However, if the exigencies of the work need continuation of work on Sundays and Holidays, written permission of the Engineer-In-Charge shall be obtained in advance.

#### **GC-59 GENERAL CONDITIONS FOR CONSTRUCTION WORK:**

Working hours shall be eight every day. The over time work in two shifts could be carried out with the written permission of the Engineer-In-Charge but no compensation shall be paid for the same. The rate quoted shall include this. The Contractor shall plan his work in such a way that his labourers do not remain idle. The owner will not be responsible for idle labour of the Contractor. The Contractor shall submit to the owner progress report every week. The details and proforma of the report will be as per mutual agreement.

#### GC-60 DRAWINGS TO BE SUPPLIED BY THE OWNER: (N.A.)

The drawings attached with the e-Tender documents shall be for general guidance of the Contractor to enable him to visualize the type of work

contemplated and scope of work involved. Detail working drawings according to which the work is to be done shall be prepared by the Contractor for executing the work.

#### GC-61 DRAWINGS TO BE SUPPLIED BY THE CONTRACTOR:

Where drawings, data are to be furnished by the Contractor they shall be as enumerated in special conditions of contract and shall be furnished within the specified time. Where approval of drawings has been specified it shall be Contractor's responsibility to have these drawings got approved before any work is taken up with regard to the same. Any changes becoming necessary in those drawings during the execution of the work shall have to be carried out by the Contractor at no extra cost. All final drawings shall bear the certification stamp as indicated below duly signed by both the Contractor and Engineer-In-Charge.

|            |     | for |
|------------|-----|-----|
| rigicement | 110 |     |
| Signed     |     |     |

Engineer-In-

#### Contractor Charge

Drawings will be approved within three (3 weeks of the receipt of the same by the Engineer-In-Charge.

#### GC-62 <u>SETTING OUT WORK</u>:

The Contractor shall set out the work on the site handed over by the Engineer-In-Charge and shall be responsible for the correctness of the same. The work shall be carried out to the entire satisfaction of Engineer-In-Charge. The approval thereof or partaking by Engineer-In-Charge or setting out work shall not relieve Contractor of any of his responsibilities. The Contractor shall provide at his own cost all necessary level posts, pegs, bamboos, flags, ranging rods, strings and other materials and labourers required for proper setting out of the work. The Contractor shall provide fix and be responsible for the maintenance of all stakes, templates, level markets, profiles and similar other things and shall take all necessary precautions to prevent their removal or disturbance and shall be responsible for the consequences for such removal or disturbance. The Contractor shall also be responsible for the maintenance of all existing survey marks, boundary marks, and distance marks and centerline marks either existing or face lines and cross lines shall be marked by small masonry pillars. Each pillar shall have distance mark at the center for setting up the theodolite. The work shall not be started unless the setting out is choked and approved by Engineer-In-Charge in writing but such approval shall not relieve the Contractor of his responsibilities about the correctness of setting out. The Contractor shall provide all materials, labour and other facilities necessary for checking at his own cost. Pillars bearing geodetic marks on site shall be protected by the Contractor. On completion of the work, the Contractor shall submit the geodetic documents according to which the work has been carried out.

# GC-63 RESPONSIBILITIES OF CONTRACTOR FOR CORRECTNESS OF THE WORK:

The Contractor shall be entirely and exclusively responsible for the correctness of every part of the work and shall rectify completely any errors therein at his own cost when so instructed by Engineer-In-Charge. If any error has crept in the work due to non-observance of this clause,

the Contractor will be responsible for the error and bear the cost of corrective work.

#### 1. Materials to be supplied by the Contractor:

Contractor shall procure and provide all the material required for the execution and maintenance of work including M S rods; all tools, tackles, construction plant and equipment except, the materials to be supplied by the owner detailed in the contract documents. Owner, shall make recommendations for procurement of materials to the respective authorities if desired by the Contractor but assumes no responsibility of any nature. Owner shall insist for procurement of materials with ISI marks supplied by reputed firms of the DGS & D list.

If however, the Engineer-In-Charge feels that the work is likely to be delayed due to Contractor's inability to procure materials, the Engineer-In-Charge shall have the right to procure materials, from the market and the Contractor will accept these materials at the rates decided by Engineer-In-Charge.

#### GC-64 MATERIALS TO BE SUPPLIED BY THE OWNER:

- If the contract provided certain materials or stores to be supplied by the owner, such materials and stores transported by the Contractor at his cost from owner's stores or Railway Station. The cost from Contractor for the value of materials supplied by the owner will be recovered from the R.A.Bill on the basis of actual consumption of materials in the work covered and for which R A Bill has been prepared. After completion of the work, the Contractor has to account for the full quantity of materials supplied to him.
- The value of store materials supplied by owner to the Contractor shall be charged at rates shown in the contract document and in case any other material not listed in the schedule of materials is supplied by the owner, the same shall be charged at cost price including carting and other expenses incurred in procuring the same. All materials so supplied shall remain the property of the owner and shall not be removed from the site on any account. Any material remaining unused at the time of completion of work or termination of contracts shall be returned to owner's store or any other place as directed by the Engineer-In-Charge in perfectly good condition at Contractor's cost. When materials are supplied free of cost for use in work and surplus and unaccounted balance thereof are not returned to the owner, recovery in respect of such balance will be effected at double the applicable issue rate of the material or the market rates whichever is higher.

#### GC-65 CONDITIONS OF ISSUE OF MATERIALS BY THE OWNER: (N.A.)

The materials specified to be issued by the owner to the Contractor shall be issued by the owner at his store and all expenses for it carting site shall be borne by the Contractor will be issued during working hours and as per rules of owner from time to time.

Contractor shall bear all expenses for storage and safe custody at site of materials issued to him before use in work.

Material shall be issued by the owner in standard / non-standard sizes as obtained from manufacturer.

Contractor shall construct suitable godowns at site for storing the materials to protect the same from damage due to rain, dampness, fire, theft etc.

The Contractor should take the delivery of the materials issued by the owner after satisfying himself that they are in good condition. Once the materials are issued, it will be the responsibility of the Contractor to keep them in good condition and in safe custody. If the materials get damaged or if they are stolen, it shall be the responsibility of the Contractor to replace them at his cost according to the instructions of the Engineer-In-Charge.

For delay in supply or for non-supply of materials to be supplied by the owner, on account of natural calamities, act of enemies, other difficulties beyond the control of the owner, the owner carries no responsibilities. In no case the Contractor shall be entitled to claim any compensation for loss suffered by him on this account.

None of the materials issued to the contractor, shall be used by the Contractor for manufacturing items which can be obtained from the manufacturer's. The materials issued by the owner shall be used for the work only and no other purpose.

Contractor shall be required to execute indemnity bond in the prescribed form for the safe custody and account of materials issued by the owner.

Contractor shall furnish sufficiently in advance a statement of his requirements of quantities of materials to be supplied by the owner and the time when the same will be required for the work, so as to enable Engineer-In-Charge to make arrangements to procure and supply the materials.

A daily account of materials issued by the owner shall be maintained by the contractor showing receipt, consumption and balance on hand in the form laid down by Engineer-In-Charge with all connected paper and shall be always available for inspection in the site office.

Contractor shall see that only the required quantities of materials are got issued and no more. The Contractor shall be responsible to return the surplus materials at owner's store at his own cost.

#### GC-66 MATERIALS PROCURED WITH ASSISTANCE OF THE OWNER:

Notwithstanding anything contained to the contrary in any of the clauses of this contract, where any materials for the execution of the contract are procured with the assistance of the owner either by issue from owner's stock or purchase made under orders or permits or licenses issued materials as trustees for owner, and use such materials not disposed them off without the permission of owner and unserviceable materials that may be left with him after completion of the contract or at its termination for any reason whatsoever on his being paid or credited such price as Engineer-In-Charge shall determine having due regard to the conditions of the materials. The price allowed to Contractor shall not exceed the amount charged to him excluding the storage of breach of the aforesaid condition, the Contractor shall in terms of license or permits and/or for criminal breach of trust be liable to compensate owner at double the rate or any higher rates. In the event of these materials at that time having higher rate or not being available in the market then any other rate to be

determined by the Engineer-In-Charge at his decision shall be final and conclusive.

#### GC-67 <u>MATERIALS OBTAINED FROM DISMANTLING</u>:

If the Contractor, in the course of execution of work, is called upon to dismantle any part of work for reasons other than on account of bad or imperfect work, the materials obtained from dismantling will be property of the owner and will be disposed off as per instructions of Engineer-In-Charge in the best interest of the owner.

## GC-68 <u>ARTICLE OF VALUE OF TREASURE FOUND DURING CONSTRUCTION:</u>

All gold, silver and other minerals of any description and all precious stones, coins, treasures, relics, antiques and other similar things which shall be found in, under or upon site shall be the property of the owner and the Contractor shall properly preserve the same to the satisfaction of the Engineer-In-Charge and shall hand over the same to the owner.

#### GC-69 DISCREPANCIES BETWEEN INSTRUCTIONS:

If there is any discrepancy between various stipulations of the contract documents or instructions to the Contractor or his authorized representative or if any doubt arises as to the meaning of such stipulation or instructions, the Contractor shall immediately refer in writing to the Engineer-In-Charge and shall hand over the same to the owner.

#### GC-70 <u>ALTERATIONS IN SPECIFICATIONS & DESIGNS & EXTRA WORK</u>:

The Architect / Engineer-In-Charge shall have power to make any alterations in, omission from, addition to substitution for, the schedule of rates, the original specifications, drawings, designs and instructions that may appear to him to be necessary or advisable during the progress of work and the Contractor shall be bound to carry out such altered / extra / new items of work in accordance with any instructions which may be given to him in writing signed by Engineer-In-Charge and such alteration omissions, additions or substitutions, shall not invalidate contract and any altered, additional or substituted work shall be carried out by the Contractor on the same conditions of contract. The time of completion may be extended by Architect as may be considered just and reasonable by him. The rates for such additional, altered or substitute work shall be worked out as under:

- a) If the rates for additional, altered or substitutes work are specified in the contract for work, the Contractor is bound to carry out such work at the same rates as specified in the contract.
- b) If the rates for additional, altered or substituted work are not specifically provided in the contract for the work, the rates will be derived from the rates of similar items of work in the contract work. The opinion of Engineer-In-Charge as to whether the rates can be reasonably so derived the items of contract will be final and binding to the Contractors.
- c) If the rates of altered, additional or substitute work cannot be determined as specified in (a) or (b) above, the rate shall be paid as per S.O.R. of RMC and if not available in RMC SOR than it will be paid according to SOR of R&B/GWSSB.
- d) If the rates of altered, additional or substitute work cannot be determined as specified in (a) or (b) or (c) above, the Contractor shall within seven

days of the receipt of order to carry out the work inform the Architect / Engineer-In-Charge of the rate which he intends to charge for such work supported by rate analysis and the Architect / Engineer-In-Charge will determine the rate on the basis of prevailing market rates of materials, labour cost at schedule of labour plus 15% there on as Contractor's supervision overheads and profit. The opinion of Architect / Engineer-In-Charge as to the market rates of materials and the quantity of labour involved per unit of measurement will be final and binding on Contractor.

But under no circumstances, the Contractor suspends work or the plea of non settlement of items falling under this clause.

### GC-71 ACTION WHEN NO SPECIFICATIONS ARE ISSUED:

In case of any class of work for which no specifications is supplied by the owner in the e-Tender documents, such work shall be carried out in accordance with relevant latest ISS and if ISS do not cover the same, the work shall be carried out as per General Technical Specification for building work; and if not covered in then it is to be with standard Engineering Practice subject to the approval of Engineer-In-Charge.

### GC-72 ABNORMAL RATES:

Contractor is expected to quote rate for each item after careful analysis of cost involved for the performance of the completed item considering all specifications and conditions of contract.

### GC-73 <u>ASSISTANCE TO ENGINEER-IN-CHARGE</u>:

Contractor shall make available to Engineer-In-Charge free of cost all necessary instruments and assistance in checking of any work made by the Contractor setting out for taking measurement of work etc.

### GC-74 TESTS FOR QUALITY OF WORK:

- 1. All workmanship shall be of the best kind described in the contract documents and in accordance with the instructions of Engineer-In-Charge and shall be subjected from time to time to such tests at Contractor's cost as the Engineer-In-Charge may direct at the place of manufacture of fabrication or on the site or at any such place. Contractor shall provide assistance, instruments, labour and materials as are normally required for examining, measuring and testing of any work of workmanship as may be selected and required by Engineer-In-Charge.
- 2. All tests necessary in connection with the execution of work as decided by Engineer-In-Charge shall be carried out at an approved laboratory at Contractor's cost.
- 3. Contractor shall furnish the Engineer-In-Charge for approval when requested or if required by the specification, adequate samples of all materials and finished goods to be used in work sufficiently in advance to permit tests and examination thereof. All materials furnished and finished goods applied in work shall be exactly as per the approved samples.

### GC-75 <u>ACTION AND COMPENSATION IN CASE OF BAD WORKMANSHIP</u>:

If it shall appear to the Engineer-In-Charge that any work has been executed with materials of inferior description, or quality or are unsound or with unsound, imperfect or unskilled workmanship or otherwise not in accordance with the contract, the Contractor shall, on demand in writing

from Engineer-In-Charge or his authorized representative specifying the work, materials or articles complained of, notwithstanding that the same may have been inadvertently passed, certified and paid for, forthwith rectify or remove and reconstruct the work, so specified. In the event of failure to do so within a period to be specified by the Engineer-In-Charge in his aforesaid demand, Contractor shall be liable to pay compensation at the rate of half a percent of the estimated cost of work for every work limited to a maximum of ten (10%) percent of the value of work while his failure to do so continues and in the case of any such failure, the Engineer-In-Charge may on expiry of the notice period rectify and remove and re-execute the work or remove and replace with others at the risk and cost of the Contractor. The decision of the Engineer-In-Charge as to any question arising under this clause shall be final and conclusive.

### GC-76 SUSPENSION WORK:

Contractor shall, if ordered in writing by Engineer-In-Charge or his representative temporarily suspended the work or any part thereof for such time (not exceeding one month) as ordered and shall not after receiving such written notice proceed with the work until he shall have received a written order to proceed therewith. The Contractor shall not be entitled to claim compensation for any loss or damage sustained by him by reason of temporary suspension of work as aforesaid. An extension of time for completion of work will be granted to the Contractor corresponding to the delay caused by such suspension of work if he applies for the same provided the suspension was not consequent upon any default or failure on the part of the Contractor.

### GC-77 OWNER MAY DO PART OF THE WORK:

When the Contractor fails to comply with any instructions given in accordance with the provisions of this contract, the owner has the right to carry out such parts of work as the owner may designate whether by purchasing materials and engaging labour or by the agency of another Contractor. In such case the owner shall deduct from the amount which otherwise might become due to Contractor, the cost of such work and materials with then (10) percent added to cover all departmental charges and should the total amount thereof exceed the amount due to contract, Contractor shall pay the difference to owner.

### GC-78 <u>POSSESSION PRIOR TO COMPLETION</u>:

The Engineer-In-Charge shall have the right to take possession of or to use any completed or partly completed work or part of work. Such possession or use shall not be deemed to be an acceptance of any work completed in accordance with the contact. If such prior possession or use by Engineer-In-Charge delays the process of work, equitable adjustment in the time of completion will be made and the contract shall be deemed to be modified accordingly.

### GC-79 <u>COMPLETION CERTIFICATE</u>:

As soon as the work has been completed in accordance with contact (except in minor respects that do not effect their use for the purpose for which they are intended and except for maintenance thereof) as per General Conditions of Contract the Engineer-In-Charge shall issue a certificate (hereinafter called completion certificate) in which shall certify the date on which work has been completed and has passed the said tests and owner shall be deemed to have taken over work on the date so

certified. If work has been divided in various groups in contract, owner shall be entitled to take over any group or groups before the other or others and there upon the Engineer-In-Charge will issue a completion certificate, which will, however, be for such group or groups so taken over.

In order that Contractor could get a completion certificate, he shall make good will all speed any defect arising from the defective materials supplied by Contractor of workmanship or any act or omission of Contractor that may have been discovered or developed after the work or groups of works has been taken over. The period allowed for carrying out such work will be normally, one month. If any defect be not remedied within the time specified, owner may proceed to do work at Contractor's (Agency, or Firm) risk and expenses and deduct from the final bill such amount as may be decided by owner. If by reason of any default on the part of the Contractor, a completion certificate has not been issued in respect of every portion of work within one month after the date fixed by contract for completion of work, owner shall be at liberty to use work or any portion thereof in respect of which a completion certificate has been issued, provided that work or the portion thereof so used as aforesaid shall be afforded reasonable opportunity for completion of that work or the portion thereof so used as aforesaid shall be afforded reasonable opportunity for completion of that work for the issue of completion certificate.

### GC-80 <u>SCHEDULE OF RATES</u>:

- The rates quoted by the Contractor shall remain firm till the completion of the work and shall not be subject to escalation. Schedule of rates shall be deemed to include and cover all costs, expenses and liabilities of every description and risks or every kind to be taken in executing, completing and handing over the work to owner by Contractor. The contractor shall be deemed to have known the nature, scope, magnitude and the extent of work and materials required though contract documents may not fully and precisely furnish them. He shall make such provision in the Schedule of Rates as he may consider necessary to cover the cost of such items of work and materials as may be reasonable and necessary to complete the work. The opinion of Engineer-In-Charge as to the item of work which are necessary and reasonable for completion of the work shall be final and binding on Contractor although the same may be not shown on drawings or described specifically in contract documents.
- 2. The Schedule of Rates shall be deemed to include and cover the cost of all constructional plant, temporary work, materials, labour and all other matters in connection with each item in Schedule of Rates and the execution of work or any portion thereof finished complete in every respect and maintained as shown or described in the contract document or as may be ordered in writing during the continuance of the contract.
- The Schedule of Rates shall be deemed to include and cover the cost of all royalties and fees for the articles and processes, protected by letters patent or otherwise incorporated in or used in connection with work, also all royalties, rents and other payments in connection with obtaining material of whatsoever kind for work and shall include an indemnity to owner which Contractor hereby gives against all action, proceedings, claims, damages, costs and expenses arising from the incorporation in or use on the works of any such articles, processes or materials. Other Municipal or local Board charges if levied on material, equipment or machineries to be brought to site for use on work shall be borne by the Contractor.

- 4. No exemption or reduction of custom duties, excise duties, sales tax or any other taxes or charges of the Central or State Government or of any Local Body whatsoever will be granted or obtained and all such expenses shall be deemed to have been included in and covered by Schedule of Rates. Contractor shall also obtain and pay for all permits or other privileges necessary to complete the work.
- 5. The Schedule of Rates shall be deemed to include and cover risk on account of delay and interference with Contractor's conduct of work which may occur from any cause including orders of owner in the exercise of his powers and on account of extension of time granted due to various reasons.
- 6. For work under unit rate basis, no alteration will be allowed in the Schedule of Rates by reasons of work or any part of them being modified, altered, extended, diminished or omitted.

### **GC-81 PROCEDURE FOR MEASUREMENT OF WORK IN PROGRESS:**

- All measurements shall be in metric system. All the work in progress will be jointly measured by the representative of Engineer-In-Charge and Contractor's authorized agent. Such measurements will be got recorded in the Measurement Book by the Engineer-In-Charge or his authorized representative and signed by the Contractor or his authorized agent in token of acceptance. If the Contractor or his authorized agent fails to be present whenever required by the Engineer-In-Charge for taking measures for every reasons whatsoever, the measurement will be taken by the Engineer-In-Charge or his authorized representative not withstanding the absence of Contractor and these measurements will be deemed to be correct and binding on the Contractor.
- 2. Contractor will submit a bill in approved proforma in quadruplicate to the Engineer-In-Charge of the work giving abstract and detailed measurements of various items executed during a month as mutually agreed. The Engineer-In-Charge shall verify the bill and the claim, as far as admissible, adjusted if possible, within 10 days of presentation of the bills.

### GC-82 RUNNING ACCOUNT PAYMENTS TO BE REGARDED AS ADVANCES:

- 1. All running account payments shall be regarded as payments by way of advance against the final payment only and not as payment for work actually done and completed and shall not preclude the requiring of bad, unsound and imperfect or unskilled work to be removed and taken away and reconstructed or rejected or to be considered as an admission of the due performance of contract or any part thereof.
- 2. Five (5) percent of the gross R A Bill amount shall be retained from each bill as retention amount and the same will be paid with the final bill.

### GC-83 NOTICE FOR CLAIM FOR ADDITIONAL PAYMENT:

If the Contractor considers that he is entitled to extra payment or compensation or any claim whatsoever in respect of work, he shall forthwith give notice in writing to the Engineer-In-Charge about his extra payment and / or compensation. Such notice shall be given to the Engineer-In-Charge within ten (10) days from the happening of any event upon which Contractor basis such claims and such notice shall contain full

particulars of the nature of such claim with full details and amount claimed. Failure on the part of the Contractor to put forward any claim with the necessary particulars as above, within the time above specified shall be an absolute waiver thereof. No omission by owner to reject any such claim and no delay in dealing therewith shall waiver by owner or any rights in respect thereof.

### GC-84 PAYMENT OF CONTRACTOR'S BILL:

- 1. The price to be paid by the owner to Contractor for the work to be done and for the performance of all the obligations undertaken by the Contractor under contract shall be based on the contract price and payment to be made accordingly for the work actually executed and approved by the Engineer-In-Charge.
- 2. No payment shall be made for work costing less than Rs.2,00,000/- till the work is completed and a certificate of completion for Construction is given. But in case of work estimated to cost more than Rs.2,00,000/-, Contractor on submitting the bill thereof will be entitled to receive a monthly payment proportionate to the part thereof, approved and passed by Engineer-In-Charge, whose certificate of such approval and passing of the sum so payable shall be final and conclusive against contractor. This payment shall be made after necessary deductions as stipulated elsewhere in the contract documents for materials, security deposit etc. The payment shall be released to the Contractor within two (2) month of submission of the bill duly pre-occupied on proper revenue stamp. Payment due to Contractor shall be made by the owner by ECS/RTGS mode in Indian currency. Successful bidder must furnish his Bank details for RTGS/ECS with Account Branch of RMC.

### GC-85 FINAL BILL:

The final bill shall be submitted by Contractor within one (1) month of the date of physical completion of work, otherwise the Engineer-In-Charge's certificate of the measurement and of total amount payable for work shall be final and binding on all parties.

### **GC-86 RECEIPT FOR PAYMENT**:

Receipt for payment made on account of work when executed by a firm must be signed by a person holding Power of Attorney in this respect on behalf of Contractor except when described in the e-Tender as a limited company in which case the receipt must be signed in the name of the Company by one of its principal officers or by some person having authority to give effectual receipt for the Company.

### GC-87 COMPLETION CERTIFICATE:

. When the Contractor fulfils his obligation as per terms of contract, he shall be eligible to apply for Completion Certificate. Contractor may apply for separate Completion Certificate in respect of each such portion of work by submitting the completion documents along with such application for Completion Certificate.

The Engineer-In-Charge shall normally issue to Contractor the Completion Certificate within one (1) month after receiving an application thereof from Contractor after verifying, from the completion documents and satisfying himself that work has been completed in accordance with and as set out in the construction and erection drawings and the contract documents. Contractor after obtaining the Completion Certificate is eligible to present the final bill for work executed by him under the terms of contract.

- Within one month of completion of work in all respects Contractor shall be furnished with a certificate by the Engineer-In-Charge of such completion but no certificate shall be given nor shall work be deemed to have been executed until all (i) scaffolding, surplus materials and rubbish is cleaned off site completely, (ii) until work shall have been measured by the Engineer-In-Charge whose measurement shall be binding and conclusive and, (iii) until all the temporary works, labour and staff colonies etc. constructed are removed and the work site cleaned to the satisfaction of the Engineer-In-Charge. If Contractor shall fail to comply with the requirements as aforesaid or before date fixed for the completion of work, the Engineer-In-Charge may at the expense of Contractor remove such scaffolding, surplus materials and rubbish and dispose off the same as he thinks fit.
- 3. The following documents will form the completion documents:
  - a) Technical documents according to which the work has been carried out.
  - b) Three sets of construction drawings showing therein the modifications and corrections made during the course of execution signed by the Engineer-In-Charge.
  - c) Completion Certificate for "Embedded" or "Covered" up work.
  - d) Certificate of final levels as set out for various works.
  - e) Certificate of test performed for various work.
  - f) Material appropriation statement for the materials issued by owner for work and list of surplus materials returned to owner's store duly supported by necessary documents. (N.A.)
- 4. Upon expiry of the period of defect liability and subject to Engineer-In-Charge being satisfied that work has been duly maintained by Contractor during the defect liability period of fixed originally or as extended subsequently and that Contractor has in all respects made up any subsidence and performed all his obligations under contract, the Engineer-In-Charge (without prejudice to the rights of owner in any way) give final certificate to that effect. The Contractor shall not be considered to have fulfilled the whole of his obligation until final certificate shall have been given by the Engineer-In-Charge.

### 5. Final Certificate only evidence of completion:

Except the final certificate, no other certificate of payment against a certificate or on general account shall be taken to be an admission by owner of the due performance of contract or any part thereof of occupancy or validity or any claim by the Contractor.

### GC-88 TAXES, DUTIES, ETC.:

1. Contractor agrees to and does hereby accept full and exclusive liability for the payment of any and all taxes including Sales Tax, Duties, etc., now or hereinafter imposed, increased or modified from time to time in respect of work and materials and all contributions and taxes for unemployment, compensation, insurance and old age pension or annuities now or hereinafter imposed by the Central or State Government authorities with

respect to or covered by the wages, salaries or other compensation paid to the persons employed by Contractor.

If the Contractor is not liable to Sales Tax assessment, a certificate to that effect from the Competent Authority shall be produced without which final payment to the Contractor shall not be made No.P, 'C' and 'D' Form shall be supplied by the owner, and the Contractor shall be required to pay full tax as applicable.

- 2. Contractor shall be responsible for compliance with all obligations and restrictions imposed by the labour law or any other law affecting employer-employee relationship.
- 3. Contractor further agrees to comply and to secure the compliance of all sub contractors with applicable Central, State, Municipal and local laws and regulations and requirement. Contractor also agrees to defend, indemnify the hold harmless the owner from any liability or penalty which may be imposed by Central, State or local authority by reasons of any violation by Contractor or sub Contractor of such laws, regulations or requirements and also from all claims, suits or proceedings that may be brought against owner arising under, growing out of or by reasons or work provided for by this Contract by third parties or by Central or State Government authority or any administrative Sub-Division thereof.

The Sales Tax on work contract will be borne by Contractor.

### GC-89 <u>INSURANCE</u>:

Contractor shall at his own expenses carry and maintain the reputable Insurance Companies to the satisfaction of owner as follows:

1. Contractor agrees to and uses hereby accept full and exclusive liability for compliance with all obligations imposed by the Employer's State Insurance Act, 1948 and Contractor further agrees to defend, indemnify and hold owner hardness from any liability or penalty which may be imposed by the Central or State Government or local authority by reasons of any assorted violation by Contractor or Sub-Contractor or the Employees State Insurance Act, 1948 and also from all claims, suits or proceedings that may be brought against owner arising under, growing out of or by reasons of the work provided for by this contract whether brought by employees of Contractor by third parties or by Central or State Government authority or any administrative Sub-division thereof.

Contractor agrees to fill in with the Employees State Insurance Corporation, the declaration form and all forms which may be required in respect of Contractor's or sub-Contractor's employees whose aggregate remuneration is Rs.400/- p.m. or less and who are employed in work provided for or those covered by ESI from time to time under the agreement. The Contractor shall deduct and secure the agreement of the sub-Contractor to deduct the employees contribution as per the first schedule of the Employees State Insurance Act from wages. Contractor shall remit and secure the agreement of sub-contractor to remit to the State Bank of Indian Employees State Insurance Accounts, the employee's contribution as required by the Act. Contractor agrees to maintain all cards and records as required under the Act in respect of employees and payments and Contractor shall secure the agreements of the sub contractors to maintain in such records, any expenses incurred for the contributions, making contributions or maintaining records shall be to

Contractors or sub-contractors own account. owner shall retain such sum as may be necessary from the contract value until Contractor shall furnish satisfactory proof that all contribution as required by the Employees State Insurance Act, 1948 have been paid.

- 2. **Workman's compensation and employees liability insurance:** Insurance shall be effected for all Contractors employees engaged in the performance of this contract. If any part of work is sublet, Contractor shall require the sub-Contractor to provide workman's compensation and employer's liability insurance, which may be required by owner.
- 3. Other Insurance required under law of regulations or by owner Contractor shall also carry and maintain any and all other insurance which may be required under any law or regulation from time to time. He shall also carry and maintain any other insurance, which may be required by owner.

### GC-90 DAMAGE TO PROPERTY:

- 1. Contractor shall be responsible for making good to the satisfaction of owner any loss of and any damage to all structures and properties belonging to owner or being executed or procured or being procured by owner or of other agencies within the premises of all work of owner, if such loss or damage is due to fault and / or the negligence of willful act or omission of Contractor, his employees, agent, representatives or sub-Contractor s.
- Contractor shall indemnify and keep owner harmless of all claims for damage to properties other than property arising under by reasons of this agreement, such claims result from the fault and / or negligence or willful act or omission of Contractor, his employees, agents representative or sub-contractor.

### GC-91 CONTRACTOR TO INDEMNIFY OWNER:

- The Contractor shall indemnify and keep indemnified the owner and every member, officer and employee of owner from and against all actions, claims, demands and liabilities whatsoever under the in respect of the breach of any of the above clauses and / or against any claim, action or demand by any workman / employee of the Contractor or any subcontractor under any laws, rules or regulations having force of laws, including but not limited to claims against the owner under the workman compensation Act, 1923, the Employee's Provident Funds Act, 1952 and / or the contract labour (Abolition and Regulations) Act, 1970.
- 2. <u>PAYMENTS OF CLAIMS AND DAMAGES</u>: If owner has to pay any money in respect of such claims or demands aforesaid, the amount so paid and the cost incurred by the owner shall be charged to and paid by Contractor without any dispute not withstanding the same may have been paid without the consent or authority of the Contractor.
- 3. In every case in which by virtue of any provision applicable in the workman's Compensation Act, 1923 or any other Act, owner be obliged to pay compensation to workmen employed by Contractor the amount of compensation so paid, and without prejudice to the rights of owner under Section-(12) Sub-section-(2) of the said Act, owner shall be at liberty to recover such amount from any surplus due to on to become due to the Contractor or from the security deposit. Owner will not be bound to contest any claim made under Section-(12) Sub-section-(2) of the said act

except on written request of Contractor and giving full security for all costs consequent upon the contesting of such claim.

The Contractor shall protect adjoining sites against structural, decorative and other damages that could be cased to adjoining premises by the execution of these works and make good at his cost, any such damage, so caused.

### GC-92 <u>IMPLEMENTATION OF APPRENTICE ACT 1954</u>:

Contractor shall comply with the provisions of the apprentice Act 1954 and the orders issued there under from time to time. If he fails to do so, it will be a breach of contract.

### GC-93 <u>HEALTH AND SANITARY ARRANGEMENTS FOR WORKERS</u>:

Contractor shall comply with all the rules and regulations of the local Sanitary Authorities or as framed by owner from time to time for the protection of health and provide sanitary arrangements of all labour directly or indirectly employed on the work of this contract.

### GC-94 <u>SAFETY CODE</u>:

### General:

Contractor shall adhere to safe construction practice and guard against hazardous and unsafe working conditions and shall comply with owner's rules as set forth herein.

### 1.0 First Aid and Industrial Injuries :

- 1.1 Contractor shall maintain First-Aid facilities for its employees and those of his sub-contractors.
- 1.2 Contractor shall make outside arrangements for ambulance service and for the treatment of industrial injuries. Name of those providing these services shall be furnished to Engineer-In-Charge prior to start of construction, and their telephone numbers shall be prominently posted in Contractor's field office.
- All injuries shall be reported promptly to Engineer-In-Charge and a copy of Contractor's report covering each personal injury requiring the attention of a physician shall be furnished to owner.

### 2.0 General Rules:

Carrying and striking, matches, lighters inside the project area and smoking within the job site is strictly prohibited. Violators of smoking rules shall be discharged immediately. Within the operation area, no hot work shall be permitted, without valid gas, safety, fire permits. The Contractor shall also be held liable and responsible for all lapses of his sub-Contractors / employees in this regard.

### 3.0 Contractor's Barricades:

- Contractor shall erect and maintain barricades without any extra cost, required in connection with his operation to guard or protect during the entire phase of the operation of this contract for
  - i) Excavation
  - ii) Hoisting areas
  - iii) Areas adjudged hazardous by Contractor's OR Owner's inspectors.
  - iv) Owner's existing property liable to be damaged by Contractor's operations, in the opinion of Engineer-In-Charge / Site Engineer.

- **3.2** Contractor's employees and those of his sub-contractors shall become acquainted with owner's barricading practices and shall respect the provisions thereof.
- **3.3** Barricades and hazardous areas adjacent to but not located in normal routes of travel shall be marked by red lantern at night.

### 4.0 Scaffolding:

- **4.1** Suitable scaffolding shall be provided for workman for all works that cannot safely be done from ladders. When a ladder is used, an extra mazdoor shall be engaged for holding the ladder and if the ladder is used for carrying materials as well suitable footholds and handholds shall be provided on the ladder and the same shall be given an inclination not steeper that 1 in 4 (1 horizontal and 4 vertical).
- Scaffolding or staging, more than 3.6 M. (12') above the ground or floor, swing or suspended from an overhead support or erected with stationary support shall have a guard rail properly attached, bolted, braced and otherwise fixed at least 1.0 M (3') high above the floor or platform or scaffolding or staging and extending along the entire length of the outside ends thereof with only such openings as may be necessary for the delivery of materials. Such scaffolding or staging shall be so fastened as to prevent it from swaying from the building or structure.
- Working platforms, gangways, and stairways should be so constructed that they should not sag unduly or inadequately and if the height of the platform or the gangway of the stairway is more than 3.6 (12') above ground level or floor level, they should be closely boarded, should have adequate width and should be suitably fastened as described in 4.2 above.
- Every opening in the floor of a building or in a working platform be provided with suitable means to prevent the fail of persons or materials by providing suitable fencing or railing whose minimum height shall be 1.0 M (3'.0").
- 4.5 Safe means of access shall be provided to all working platforms and other working places. Every ladder shall be securely fixed. No portable single ladder shall be over 9.0 M. (30') in length while the width between the side rails in rung ladder shall in no case be less than 30 cms (12 inches) for ladder up to and including 3.0 M. (10'), in longer ladders this width would be increased at least 6 mm (1/4") for each addition 30 c.m. (1.0) of length. Uniform step spacing shall not exceed 30 cms. (12"). Adequate precaution shall be taken to prevent danger from electrical equipment. No materials on any of the side of work shall be so stacked or placed as to cause danger or inconvenience to any person or public. The Contractor shall also provide all necessary all necessary fencing and lights to protect the workers and staff from accidents, and shall be bound to bear the expenses of defence of every suit action or other proceedings at law that may be brought by any persons for injury sustained owning to neglect of the above precautions and to pay damages and costs which may be awarded in any such suit or action or proceedings to any such person, or which, may be with the consent of the Contractor be paid to compromise any claim by any such person.

### 5.0 Excavation:

- **5.1** All trenches 1.2 M (4') or more in depth, shall at all time be supplied with at least one ladder.
- Ladder shall be extended bottom of the trench to at least 3" above the surface of the ground. The side of the trench which are 1.5 M (5') or more in depth shall be stopped back to give suitable slope, or securely held by timber bracing, so as to avoid the danger of sides to collapse. The excavated materials shall not be placed within 1.5 M (5') of the trench of half of the trench depth whichever is more. Cutting shall be done from top to bottom. Under no circumstances, undermining or under cutting be done.

### 6.0 Demolition:

- Before any demolition work is commenced and also during the progress of the work all roads and open area adjacent to the work site shall either be closed or suitably protected.
- No electric cable or apparatus which is liable to be a source of danger shall remain electricity charged.
- 6.3 All practical steps shall be taken to prevent danger to persons employed from risk of fire or explosion of flooding. No floor or other part of the building shall be so over loaded with debris or materials as to render it unsafe.

### 7.0 Safety Equipment:

- All necessary personal safety equipment as considered necessary by the Engineer-In-Charge should be made available for the use of persons employed on the site and maintained in a condition suitable for immediate use, and the Contractor should take adequate steps to ensure proper use of equipment by those concerned.
- **7.2** Workers employed on mixing asphaltic materials, cement and line mortars shall be provided with protective footwear and protective gloves.

### 8.0 Risky Place:

When the work is done near any place where there is a risk of drowning, all necessary safety equipment shall be provided and kept ready for use and all necessary steps taken for prompt rescue of any person in danger and adequate provision should be made for prompt first-aid treatment of all injuries likely to be sustained during the course of the work.

### 9.0 Hoisting Equipment:

- **9.1** Use of hoisting machines and tackles including their attachments, and storage and supports shall conform to the following standards or conditions.
- **9.2** These shall be of good mechanical construction, sound material and adequate strength and free from patent defect and shall be kept in good condition and in good working order.
- **9.3** Every rope used in hoisting or lowering materials or as a means of suspension shall be of durable quality and adequate strength and free from patent defects.
- **9.4** Every crane driver or hoisting appliance operator shall be properly qualified and no person under the age of 21 Years should be in-charge of any hoisting machine including any scaffolding.

- In case of every hoisting machine and of every chain ring hook, shackle, swivel and pulley block used in hoisting or lowering or as means of suspension, the safe working load shall be ascertained by adequate means. Every hoisting machine and all gear referred to above shall be plainly marked with the safe working load and the conditions under which it is applicable shall be clearly indicated. No part of any machine or any gear referred to above in this paragraph shall be loaded beyond the safe working load except for the purpose of testing.
- In case of departmental machine, the safe work load shall be notified by the Engineer-In-Charge, as regards Contractor s machine, the Contractor shall, notify, the safety working load of the machine to the Engineer-In-Charge. Whenever the Contractor brings any machinery to site of work he should get it verified by the Engineer-In-Charge concerned.

### 10.0 Electrical Equipment:

Motors, gears, transmission, electric wiring and other dangerous parts of hoisting appliances shall be provided with efficient safeguards, hoisting appliances should be provided with such means when will reduce to the minimum the risk of accidental descent of the load, adequate precautions shall be taken to reduce to the minimum the risk of any part or a suspended load becoming accidentally displaced. When workers are employed on electrical installations which are already energized, insulating mats, wearing apparel such as gloves, and booths as may be necessary shall be provided. The workers shall not wear any rings, watches and carry keys or other materials which are good conductors of electricity.

### 11.0 Maintenance of Safety Devices :

All scaffolds, ladders and other safety devices as mentioned or described herein shall be maintained in sound condition and no scaffold, ladder or equipment shall be altered or removed while it is in use. Adequate washing facilities should be provided at or near place of work.

### 12.0 Display of Safety Instructions :

The safety provisions should be brought to the notice of all concerned by display on a Notice Board at a prominent place at the work spot. The persons responsible for compliance of the safety code shall be named therein by the Contractor.

### 13.0 Enforcement of Safety Regulations :

To ensure effective enforcement of the rules and regulations relating to safety precautions, the arrangement made by the Contractor shall be open to inspection by the Welfare Officer, Engineer-In-Charge or Safety Engineer of the owner or their representatives.

### 14.0 No Exemption:

- Notwithstanding the above clause 1.0 to 13.0 there is nothing to exempt the Contractor from the operations of any other Act or Rules in force in the Republic of India.
- In addition to the above, the Contractor shall abide by the safety code provisions as per C.P.W.D. safety code framed from time to time.

### GC-95 ACCIDENTS:

It shall be Contractor's responsibility to protect against accidents on the works. He shall indemnify the owner against any claim for damage or for injury to person or property resulting from, and in the course of work and also under the provisions of the workman's compensation Act. On the occurrence of an accident arising out of the works which results in death

or which is so serious as to be likely to result in death, the Contractor shall within twenty-four hours of such accident, report in writing to the Engineer-In-Charge, the facts stating clearly and in sufficient details the circumstances of such accident and the subsequent action. All other accidents on the works involving injuries to person or damage to property other than that of the Contractor shall be promptly reported to the Engineer-In-Charge, stating clearly and in sufficient details the facts and circumstances of the accidents and the action taken. In all cases, the Contractor shall indemnity the owner against all loss or damage resulting directly or indirectly from the Contractor's failure to report in the manner aforesaid. This includes penalties or fines, if any, payable by the owner as a consequence of failure to give notice under the Workman's Compensation Act, or failure to conform to the provisions of the said act in regard to such accidents.

In the event of an accident in respect of which compensation may become payable under the Workman's Compensation Act VIII of 1923 including all modification thereof, the Engineer-In-Charge may retain out of money due and payable to the Contractor such sum of sums of money as may in the opinion of Engineer-In-Charge be sufficient to meet such liability. On receipt of award from the Labour Commissioner in regard to quantum of compensation, the difference in amount will be adjusted.

Addl/Asst. Engineer R.M.C.

Dy.Ex.Engineer R.M.C.

CITY ENGINEER R.M.C.

Signature of Contractor with Seal

# PART-II SECTION - 3

## TECHNICAL SPECIFICATIONS

### PART-II SECTION - 3 TECHNICAL SPECIFICATIONS

### **CONTENT**

| SR NO | PARTICULARS   |
|-------|---|
| A     | GENERAL   |
| 1     | Scope of Contract   |
| 2     | e-TENDER Price  |
| 3     | Completion Schedule   |
| 4     | General Technical Guideline                                   |
| 5     | Classification of Strata                                      |
| В     | DETAILED TECHNICAL SPECIFICATION                              |
| B1    | Material specification  |
| 1     | Providing and testing of SWG pipe                             |
| 2     | Providing and supplying precast M.H. & H.C.C. frame and cover |
| B2    | Labour specification  |
| 1     | Excavation and Refilling                                      |
| 2     | Providing and laying CC bedding for pipes                     |
| 3     | Providing sand/granular bedding for pipes                     |
| 4     | Lowering ,laying and jointing of SWG and RCC NP3 pipe         |
| 5     | Removing surplus materials                                    |
| 6     | Appurtenances   |
| 7     | Breaking of Asphalt surface and re-instating of road          |
| С     | GENERAL MATERIAL SPECIFICATION                                |
| 1     | Concrete  |
| 2     | Form Work   |
| 3     | Reinforcement   |
| 4     | Brick Masonry   |
| 5     | Definition of Incomplete Work                                 |
| 6     | Contractor to observe all conditions                          |
| D     | ADDITIONAL CONDITIONS   |
| E     | SCHEDULE OF DRAWING   |

### :: TECHNICAL SPECIFICATIONS ::

### A. GENERAL

### 1. SCOPE OF CONTRACT:

The work entitled comprise of excavation of trenches with shoring and strutting wherever required bailing out water wherever necessary, laying of pipes, jointing including supply of material and material required for jointing, testing as per specifications, Construction of appurtenances such as brick Masonry Manholes, house chambers etc. as per the type design specified entirely of the specification of various works stipulated in the e- Tender. The work includes supply of sewer pipes i.e. stone ware pipes of ISI Marked and R.C.C. precast manhole frames & covers which shall have to be supplied at site or Municipal store by the contractor at specified and shown in schedule "B". Other material like cement etc shall have to supplied by the contractor from open market.

### 2. e-TENDER PRICE:

The rates quoted in the bill of quantities shall cover everything necessary for the due and complete execution of the work according to the drawings and other condition and stipulations of the contract including specifications of the evident, intend and meaning of all or either of them or according to customary usage and for periodical and final inspection and test and proof of the work in every respect and for measuring, numbering or weighing the same, including setting out and laying or fixing in position and the provision of all materials, power, tools, rammers, labour, tackle, platforms with impervious lapped joints for scaffolding, ranging roads, straight edged, cantering and boxing, wedges, moulds, templates, posts, straight rods, straight edged, cantering and boxing, wedges, moulds, templates, posts, straight rails, boning staves strutting, barriers, fencing lighting pumping apparatus, temporary arrangement for passage of traffic access to premises and continuance to drainage water supply and lighting (if interrupted by contractor's temporary painting, sheds, varnishing, establishment for efficient supervision and stating arrangements for the efficient protective of life and property and all requisite plant and machinery of every kind.

The contractor shall keep every portion of the work clear of accumulation from time to time and shall leave every portion of the work clean, clear, perfect and at the conclusion of whole, providing at their own cost all such material implement, appliances and labour as the Engineer in charge may require to prove if it to be so.

### 3. COMPLETION SCHEDULE:

The contract period shall be as prescribed in tender document, from the date of notice to proceed. The Contractor shall submit his completion schedule and the program of works together with this e-Tender in conformity with completion schedule given in the documents.

### 4. GENERAL TECHNICAL GUIDELINE:

- 4.1 All the items occurring in the work and as found necessary during actual execution shall be carried out in the best workman like manner as per specifications and the written order of the Engineer in charge
- 4.2 Extra Claim in respect of extra work shall be allowed only if such work is ordered to be carried out in writing by the Engineer in charge
- 4.3 The contractor shall engage a qualified Engineer for the Execution of work who will remain present for all the time on site and will receive instructions and orders from the Engineer in charge or his authorized representative. The instruction and orders given to the contractor representative on site shall be considered as it given to the contractor himself.
- 4.4 The work order book as prescribed shall be maintained on the site of the work by the contactor and the contractor shall sign the orders given by the inspecting offers and shall carry out them properly.
- 4.5 Quantities specified in the e-Tender may vary at the time of actual execution and the contractor shall have no claim for compensation on account of such variation
- 4.6 Unexcavated lengths shall be left wherever required and so directed by the Engineer in charge during the currency of the contract and shall be tackled. If required, before completion of work.
- 4.7 Diversion of road, if necessary, shall be provided and maintained during the currency of the contract by the contractor at his cost.
- 4.8 Figured Dimensions of drawing shall supersede measurements by scale, special dimensions or directions in the specifications shall supersede all other dimensions.
- 4.9 All levels are given on drawings and the contractor shall be responsible to take regular level on the approved alignment before actually starting the work. The levels shall be commence to the G.T.S. levels and shall be got approved from the Engineer in charge

4.10 If the arrangement of temporary drainage is required to be made during any work of this Contract, this shall be made by the Contractor without claiming any extra cost.

### **5. CLASSIFICATION OF STRATA:**

5.1 All materials encountered in excavation will be classified in the following groups irrespective of mode of excavating the materials and the decision of the Engineer in charge in this regard shall be final and binding to the contractor.

### 5.2 Soils:

Soils of all sorts, silt, sand, gravel, soft murrum, stiff clay, kunkar and other soft excavation not covered in the items mentioned hereunder.

### 5.3 Hard Murrum:

Hard Materials comprising of all kinds of disintegrated rock or shale or indurate conglomerate interspersed with boulders, weathered and decomposed rock which could be removed with pick, bar, shove, wedges and hammers, though not without some difficulties.

### 5.4 Soft – Rock:

This shall include all materials which is rock but which does not need blasting and can be removed with a pick bar, wedges, pavement breakers, pneumatic tools etc.

### 5.5 Hard Rock:


This shall include rock accusing in mass or boulders which need blasting, this will also include rock to be removed by chiseling or any other method where blasting is not permissible.

- **6.** The rates are inclusive of dewatering, if required.
- **7.** Regarding water supply for hydro testing, necessary water, power, labour, etc. required for necessary test shall be arranged by the contractor at his own cost.
- **8.** During construction activity, proper care must be taken for labour safety and must follow the provisions of the Labour laws.
- **9.** TMT bars of Fe-500 should be confirming to IS:1786. The approved makes shall be TATA, SAIL, Vizag, Gallent, Electrotherm or other equivalent make as approved by engineer-in-charge.
- 10. Cement shall be ordinary Portland cement 53 Grade conforming to

IS:269, IS:8112 or IS:12269 for all the works as per the instructions of engineer-incharge. The approved makes shall be Ambuja, Ultratect, LOTUS, Hathi or as per IS confirming. Minimum Cement content for the work should be as per attached circular No.RMC/C/Vigi.(Tech)/231 dt. 11/03/2022.

- **11.** Testing of the materials like Brick, Sand, Aggregate, Reinforcement steel, etc. should have to be tested peridiocally as suggested by the Engineer-in-charge at Government approved material testing Laboratory and testing charges for the same has to be borne by the contractor.
- **12.** In case of any ambiguity found in inspections / drawings etc, the decision of engineer-in-charge shall be final and binding to the contractor.

| <b>A.</b> | DETAILED TECHNICAL SPECIFICATIONS |  |
|-----------|-----------------------------------|--|
|           |                                   |  |



### 1. Material:

### M-1 Water:

Water shall not be salty or brackish and shall be clean, reasonably clear and free from objectionable quantities of silt and traces of oil and injuriousalkalis, salts, organic matter and other deleterious material which will either weaken the mortar of concrete or cause efflorescence or attack the steel in RCC container for transport, storage and handling of water shall be clean. Water shall conform to the standards specified in I.S. 456 - Latest edition.

If required by the engineer-in-charge, it shall be tested by comparison with distilled water. Comparison shall be made by means of standard cement tests for soundness, change in time of setting and mortar strength as specified in I.S. 269 (Latest edition). Any indication of unsoundness, change in time of setting by 30 minutes or more or decrease of more than

10 per cint in strength of mortar prepared with water sample when compared with the results obtained with mortar prepared with distilled water shall be sufficient cause for rejection of water under test.

Water for curing mortar, concrete or masonry should not be too acidic or too alkaline. It shall be free of elements which significantly affect the hydration reaction or otherwise interfere with the hardening of mortar or concrete during curing or those which produce objectionable stains or other unsightly deposits on concrete or mortar surface.

Hard and bitter water shall not be used for curing.

Potable water will generally found suitable for curing mortar of concrete.

### M-2 Lime:

Lime shall be hydraulic lime as per I S 712 - Latest Edition. Necessary tests shall be carried out as per I S 6932 9 (Parts I to X) Latest edition.

The following field tests for limes are to be carried out:

- i) A very rough idea can be formed about the type of lime by its visual examination i.e. fat lime bears pure white colour, lime in form of porous lumps of dirty white colour indicates quick lime and solid lumps are the unburnt lime stone.
- ii) Acid tests for determining the carbonate content in lime, lime Excessive amount of impurities and rough determination of lime.

Storage shall comply with I S 712 - Latest Edition. The slaked lime, it stored, shall be kept in a weather proof and damp-proof shed with impervious floor and sides to protect it against rain, moisture, and weather and extraneous materials mixing with it. All lime that has been damaged in any way shall be and all rejected materials shall be removed from site of work.

Field testing shall be done according to I S 269 (latest edition) to show the acceptability of materials.

### M-3 Cement:

Cement shall be ordinary portland cement as per IS:269 or IS:8112 and IS:12669 (All Latest edition).

### M-4 White Cement:

The white cement shall conform to I S 8042-E Latest edition.

### M-5 Colored Cement:

Color cement shall be with white or grey portland cement as specified in the item of the work.

The pigments used for colored cement shall be of approved quality and shall not exceed 10% of cement used in the mix. The mixture of pigment and cement shall be properly ground to have a uniform color and shade. The pigments shall have such properties as to provide for durability under exposure to sunlight and weather.

The pigment shall have the property such that it is neither affected by the cement nor detrimental to it.

### M-6 <u>Sand</u>:

Sand shall be natural sand or silica, clean well graded, hard strong, durable and gritty particles free from injurious amounts of dust, clay, kankar nodules, soft or flaky particles Shale, alkali, salts organic matter, loam, mica or other deleterious substances and shall be got approved from the engineer-in-charge. The sand shall not contain more than 8 percent of silt as determined by field test. If necessary, the sand shall be washed to make it clean.

### **Coarse Sand:**

The fineness modules of coarse sand shall not be less than 2.5 and shall not exceed 3.0. The sieve analysis of coarse shall be as under:

| I.S. Sieve<br>Designation | Percentage by weight passing sieve | IS Sieve percentage<br>Designation | by weight<br>percent-<br>age pass-<br>ing sieve. |
|---------------------------|------------------------------------|------------------------------------|--|
| 4.75 mm                   | 100                                | 600 Micron                         | 30-100   |
| 2.36 mm                   | 90 to 100                          | 300 Micron                         | 5-70   |
| 1.18 mm                   | 70-100                             | 150 Micron                         | 0-50   |

### Fine Sand:

The fineness modules shall not exceed 1.0 The sieve analysis of fine sand shall be as under:

| I.S. Sieve Percentage by weight Designation passing sieve | IS Sieve percentage<br>Designation | by weight percent-age pass-ing sieve. |
|---|------------------------------------|---------------------------------------|
|---|------------------------------------|---------------------------------------|

| 4.75 mm | 100    | 600 Micron | 40-85 |
|---------|--------|------------|-------|
| 2.36 mm | 100    | 300 Micron | 5-50  |
| 1.18 mm | 75-100 | 150 Micron | 0-10  |

### M-7 Stone Dust:

This shall be obtained from crushing hard black trap or equivalent. It shallnot contain more than 8% of silt as determined by field test with measuring cylinder. The method of determining silt contents by fields test is given as under:

A sample of stone dust to be tested shall be placed without drying in 200mm measuring cylinder. The quantity if the sample shall be such that it fills the cylinder upto 100 mm mark, the clean water shall be added upto

150 mm mark. The mixture shall be stirred vigorously and contentallowed to settle for 3 hours.

The height of silt visible as settled layer above the stone dust shall be expressed as percentage of the height of the stone dust below. The stone containing more than 8% silt shall be washed so as to bring the content within the allowable limit.

The fitness nodules of stone dust shall not be less than 1.80

### M-8 Stone Grit:

Grit shall consist of crushed or broken stone and be hard, strong dense durable clean of proper gradation and free from skin or coating likely to prevent proper adhesion of mortar. Grit shall generally be cubical in shapeand as far as possible flaky elongated pieces shall be avoided. It shall generally comply with the provisions of IS 383 (Latest Edition). Unless special stone of particular quarries is mentioned, grit shall be obtained from the best black trap or equivalent hard stone as approved by the engineer-in-charge. The grit shall have no deleterious reaction with cement.

The grit shall conform to the following gradation as per sieve analysis:

| I.S. Sieve  | Percentage passing | IS Sieve    | percentage pass-  |
|-------------|--------------------|-------------|-------------------|
| Designation | through sieve      | Designation | ing through sieve |
| 12.50 mm    | 100%               | 4.75 mm     | 0-20%             |
| 10.00 mm    | 85-100%            | 2.36 mm     | 0-25%             |

The crushing strength will be such as to allow the concrete in which it used to build up the specified strength of concrete.

The necessary tests for grit shall be carried out as per the requirements of IS 2386 (Part I to VIII) Latest edition as per instruction of engineer-in- charge. The necessity of test will be decided by the engineer-in-charge.

### M-9 Cinder:

Cinder is well burnt furnace residue which has been fused or sintered into lumps of varying sizes.

Cinder aggregates shall be well burnt furnaces residue obtained from furnace using coal fuel only. It shall be sound clean and free from clay, dirt, ash or other deleterious matter.

The average grading for cinder aggregate shall be as mentioned below:

| I.S. Sieve  | Percentage passing | IS Sieve    | percentage pass- |
|-------------|--------------------|-------------|------------------|
| Designation |                    | Designation | ing              |
| 20 mm       | 100%               | 4.75 mm     | 70               |
| 10 mm       | 86                 | 2.36 mm     | 52               |

### M-10 Lime Mortar:

**Lime:** Lime shall conform to specification M-2. **Water:** Water shall conform to specification M-1. **Sand:** Sand shall conform to specification M-6.

### **Proportion of Mix:**

Mortar shall consist of such proportions of slaked lime and sand as may be specified in item. the slaked lime and sand shall be measured by volume.

### **Preparation of Mortar:**

Lime mortar shall be prepared by process as per IS 1625 Latest edition. Power drive mill shall be used for preparation of lime mortar. The slaked lime shall be placed in the mill in an even layer and ground for 180 revolutions with a sufficient water. Water shall be added as required during griding (care being taken not to add more water) that will bring the mixed material to a consistency of stiff paste. Thoroughly wetted sand shall then be added evenly and the mixture ground for another 180 revolutions.

### Storage:

Mortar shall always be kept damp, protected from sun and rain till usedup, covering it by tarpaulin or open sheds.

All mortar shall be used as soon as possible after grinding. It should be used on the day on which it prepared. But in no case, mortar made earlierthan 36 hours shall be permitted for use.

### M-11 Cement Mortar:

Water shall conform to specification M-1. Cement: Cement shall conform to specifications M-3. Sand: Sand shall conform to M-6.

### **Proportion of Mix:**

Cement and sand shall be mixed to specified proportion, sand being measured by measuring boxes. The proportion of cement will be by volume on the basis of 50 kg/Bag of cement being equal to 0.342 Cu.M. The mortar may be hand mixed as directed.

### **Proportion of Mortar:**

In hand mixed mortar, cement and sand in the specifications shall be thoroughly mixed dry on a clean impervious platform by turning over at least 3 times or more till a homogeneous mixture of uniform color is obtained. mixing platform shall be so arranged that no deleterious extraneous material shall get mixed with mortar or mortar shall flow out. While mixing, the water shall be gradually added and thoroughly mixed toform a still plastic mass of uniform color so that each particle of sand shall be completely covered with a film of wet cement. the water cement ratio shall be adopted as directed.

The mortar so prepared shall be used within 30 minutes of adding water. Only such quantity of mortar shall be prepared as can used within 30 minutes.

### M-12 Stone Coarse Aggregate for Nominal Mix Concrete.

Coarse aggregate shall be of machine crushed stone of black trap or equivalent and be hard, strong, dense, durable clean and free from skin and coating likely to prevent proper adhesion of mortar.

The aggregate shall generally be cubical in shape. Unless special stones of particular quarries are mentioned, aggregates shall be machine crushed from the best black trap or equivalent hard tone as approved. Aggregate shall have no deleterious reaction with cement. The size of the coarse aggregate for plain cement concrete and ordinary reinforced cement concrete shall generally be as per the table given below, however, in case of reinforced cement concrete the maximum limit may be restricted to 6 mm, less than the minimum lateral clear distance between bars of 6 mm less than the cover whichever is smaller.

| I S<br>Sieve<br>designa- | Percentage passing for single sized aggregates of nominal size |        |       | IS Sieve<br>desig-<br>nation |       | ge passi<br>zed aggreg<br>size |       |
|--------------------------|--|--------|-------|------------------------------|-------|--------------------------------|-------|
| tion                     | 40 mm  | 20 mm  | 16 mm |                              | 40 mm | 20 mm                          | 16 mm |
| 80 mm                    |  |        |       | 12.5<br>mm                   |       |                                |       |
| 63 mm                    | 100  |        |       | 10 mm                        | 0.5   |                                | 0.30  |
| 40 mm                    | 85-100   | 100    |       | 4.75 mm                      |       | 0.20                           | 0.5   |
| 20 mm                    | 0-20   | 85-100 | 100   | 2.35 mm                      |       | 0.50                           |       |
| 16 mm                    |  |        | 8-100 |                              |       |                                |       |

### Note:

This percentage may be the engineer-in-charge when considered necessary for obtaining better density and strength of concrete.

The grading test shall be taken in the beginning and at the change of source of materials. The necessary tests indicated in IS 383 Latest editionand IS 456 Latest edition shall have to be carried out to ensure the acceptability. The aggregates shall be stored separately and handled in such a manner as to prevent the intermixing of different aggregates. If the aggregates are covered with dust, they shall be washed with water tomake them clean.

### M-13 <u>Black Trap or Equivalent Hard Stone Coarse:</u> Aggregate for Design Mix concrete:

Coarse aggregate shall be of machine crushed stone of black trap or equivalent hard stone and be hard strong, dense, durable, clean and free from skin and coating likely to prevent proper adhesion of mortar.

The aggregates shall generally be cubical in shape. Unless special stones of particular quarries are mentioned, aggregates shall be machine crushed from the best, black trap or equivalent hard stones as approved. Aggregate shall have no deleterious reaction with cement.

The necessary tests indicated in IS 383 Latest edition and IS 456 Latest edition shall have to carried out to ensure the acceptability of the material.

If aggregate is covered with dust, it shall be washed with water to make it clean.

### M-14 Brick Bats Aggregate:

Brick bat aggregate shall be broken from well burnt or slightly over burntand dense bricks. It shall be homogeneous in texture, roughly cubical in shape, clean and free from dirt of any other foreign material. The brick bats shall be of 40 mm to 50 mm size unless otherwise specified in the item. The under burnt of over brunt brick bats shall not be allowed.

The brick bats shall be measured by suitable boxes as directed.

### M-15 Bricks:

The bricks shall be hard or machine moulded and made from suitable soilsand burnt. They shall be free from cracks and flaws and nodules of free lime. They shall have smooth rectangular faces with sharp corners and shall be of uniform colors.

The bricks shall be moulded with a frog of  $100 \text{ mm} \times 40 \text{ mm}$  and 10 mm to 20 mm deep on one of it's flat sides. The bricks shall not break when thrown on the ground from a height of 600 mm.

The size of modular bricks shall be 190 mm x 90 mm.

The size of the conventional bricks shall be as under:  $(9" \times 4.3/8" \times 2,3/4") 225 \times 110 \times 75 \text{ mm}$ 

Only bricks of one standard size shall be used in one work. The following tolerances shall be permitted in the conventional size adopted in aparticular work.

Length  $\pm 1/8$ " (3mm) width :  $\pm 1/16$ " (1.5mm) Height:  $\pm 1/16$ " (1.5 mm)

The crushing strength of the brick shall not be less than 35 kg/sq.cm. The average water absorption shall not be more than 20 percent by weight. Necessary tests for crushing strength and water absorption etc., shall be carried out as per IS: 3495 (Part I to IV) - latest edition.

### M-16 Stone:

The stone shall be of the specified variety such as granite / trap stone / quarzite or any other type of good hard stones. The stones shall be obtained only from the approved quarry and shall be hard, sound, durable and free from defects like cavities cracks, sand holes flaws, injurious reins, patches of loose or soft materials etc. and weathered portion and other structural defects or imperfection tending to affected their soundness and strength. The stone with round surface shall not be used. The percentage of water absorption shall not be more than 5% dry or wet. When tested in accordance with I.S.1124 - Latest edition. The minimum crushing strength of the stone be 200 kg/sq.cm unless otherwise specified.

The samples of the stone to be used shall be got approved before the work is started.

The khanki facing stone shall be dressed by chisel as specified in the itemfor khanki facing in required shape and size. The face of the stone shall be so dressed that the bushing on the exposed face shall not project by morethan 40 mm from the general wall surface and on face to be plastered it shall not project by more than 19 mm nor shall it have depressions morethan 10 mm from the average wall surface.

### M-17 Laterite Stone

Laterite stone shall be obtained from the approved quarry. It shall be compacted, in texture, sound, durable and free from soft patchs. Its shall have minimum crushing strength of 10 Kg/sq.cm in its dry condition. It shall not absorb water more than 20 % of its own weight, when immersed for 24 hours in water After quarrying, the stone shall be allowed to weather for some time before using in work. '

The stone shall be dressed into regular rectangular blocks so that all facesare free from waviness and unevenness, and the edges true and square.

Those types of stone in which white cly occurs should not be used.

Special corner stones shall be provided where so directed.

### M-18 Mild Steel Bars:

Mild steel bars reinforcement for RCC work shall confirm to IS 432 (Part- II) Latest edition and shall be of tested quality. It shall also comply with relevant part of IS 456 Latest edition.

All the reinforcement shall be clean and free from dirt, paint, grease, mill scale or loose or thick rust at the time of placing.

For the purpose of payment, the bar shall be measured correct upto 10 mm length and weight payable worked out at the rate specified below:

| 1 | 6 mm | 0.22 Kg/Rmt | 8 | 20 mm | 2.47 Kg/Rmt |
|---|------|-------------|---|-------|-------------|
| 2 | 8 mm | 0.39 Kg/Rmt | 9 | 22 mm | 2.98 Kg/Rmt |

| 3 | 10 mm | 0.62 Kg/Rmt | 10 | 25 mm | 3.85 Kg/Rmt |
|---|-------|-------------|----|-------|-------------|
| 4 | 12 mm | 0.89 Kg/Rmt | 11 | 28 mm | 4.83 Kg/Rmt |
| 5 | 14 mm | 1.21 Kg/Rmt | 12 | 32 mm | 6.31 Kg/Rmt |
| 6 | 16 mm | 1.58 Kg/Rmt | 13 | 36 mm | 7.99 Kg/Rmt |
| 7 | 18 mm | 2.00 Kg/Rmt | 14 | 40 mm | 9.86 Kg/Rmt |

### M-19 High Yield Strength Steel Deformed Bars:

High yield strength steel deformed bars shall be either cold twisted other rolled and shall conform to IS 1786 Latest edition and IS 1139 Latest edition respectively.

Other provisions and requirements shall conform to specification No.M-18for Mild Steel Bars.

### M-20 High Tensile Steel Wires:

The high tensile wires for use in prestressed concrete work shall conform to IS 2090 Latest edition.

The tensile strength of the high tensile steel bars shall be as specified in the item. In absence of the given strength the minimum strength shall be taken as per part 6-1 of the IS 1785 Latest edition. Testing shall be doneas per I S requirements.

The high tensile shall be free from loose mill scale, rust, oil grease, or any other harmful matter. Cleaning of steel bars may be carried out immersion in solvent solution, wire brushing or passing through a pressure box containing carborundum.

The high tensile wire shall be obtained from manufacturer in coil having diameter not less than 350 times the diameter of wire itself, so that wire springs back straight on being uncoiled.

### M-20(A) Plain Carbon Drawn Steel Wires:

The plain carbon drawn steel wires for use in precast concrete work shall be conform to IS 1785 (Part-II) Latest edition.

The tensile strength of the P C steel bars shall be as specified in the item.In absence of the given strength, the minimum strength shall be taken as per IS:1785 Latest edition. Testing shall be done as per IS requirements.

The P C steel bars shall be free from loose mill scale, rust, oil grease, or any other harmful matter. Cleaning of steel bars may be carried out immersion in solvent solution, wire brushing or passing through a pressure box containing carborandum.

### M-21 Mild Steel Binding Wire:

The mild steel wire shall be of 1.63 mm, 22 mm (16 or 18 gauge) diameter and shall conform to I S 280 Latest edition.

The use of black wire will be permitted to binding reinforcement bars. It shall be free rust, oil paint, grease, loose mill scale or any other undesirable coating which may prevent adhesion of cement mortar.

### M-22 Structural Steel:

All structural steel shall confirm to IS 226 Latest edition. The steel shall befree from the defects mentioned in IS 226 Latest edition and shall have a smooth finish. the material shall be free from loose mill scale, rust pits or other defects affecting the strength and durability. River bars shall conform to IS 1148 Latest edition.

When the steel is supplied by the contractor, test certificate of the manufacturer shall be obtained according to IS 226 Latest edition and other relevant Indian Standards.

### M-23 Galvanized Iron Sheets:

The galvanized iron sheets shall be plain or corrugated sheets of guages as specified in item. The G.I. Sheets shall conform to I.S.latest edition. The sheets shall be undamaged in carriage and handling either by rubbing off of zinc coating or otherwise. They shall have clean and bright surface and shall be free from bends, holes, rust or white powdery deposit.

The length and width G.I. sheet shall be as directed as per site condition.

### M-23-A: G.I. Vallevs gutter, ridges:

The G.I. ridges and hips shall be of plain galvanized sheets Class-3 of the thickness as specified in item. These shall be 600 mm in and width and properly bent up to shape without damage to the sheets an in process of bending.

Valleys gutters and flashings shall also be of galvanized sheets of thickness as specified in item. Valleys shall be 900 mm. wide overall and flashing shall be 380 mm. wide overall. They shall be bent to the required shape without damage to the sheet in the process of bending.

### M-24. Asbestos Cement Sheets:

Asbestos cement sheets plain, corrugated or semi-corrugated shall - conform shall conform to I.S. latest edition. The thickness of the sheets shall be as specified in The item. the sheets shall be free from all defects such as cracks, holes, deformities, edges or otherwise damaged.

### Ridge & Hips:

Ridge and hips shall, be of same thickness as that of A.C. sheets. The types of ridges shall be suitable for the type of sheets and location.

Other accessories to be used in roof such as flashing pieces eaves filler pieces, valley gutters, north light and ventilator curves, barge boards etc. shall be of standard manufacture and shall be suitable for the type of sheets and location.

### M-25. Manglore Pattern Roof Tiles:

The mangalore pattern tiles shall conform to I.S. latest edition for Class AA or class A type as specified in item. Sample of the tiles to be provided shall be got approved from the Engineer-in-charge. Necessary tests shall be carried out as directed.

### M-26 Shuttering:

The shuttering shall be either of wooden planking of 30 mm minimum thickness with or without sheet lining or of steel plates stiffened by steel angles. The shuttering shall be supported on battens and beams and props of vertical bullies properly cross braced together so as to make the centering rigid. In places of bullies props, brick pillar of adequate section built in mud mortar may be used.

The form work shall be sufficiently strong and shall have camber, so that it assumes correct shape after deposition of the concrete and shall be able to resist forces caused by vibration of live load of men working over it and other incidental load associated with it. The shuttering shall have smooth and even surface. Its joints shall not permit leakage of cement grout.

If at any stage of work during or after placing concrete in the structure, the form work sags or bulges out beyond the required shape of the structure, the concrete and adequately rigid form work. The complete form work shall be got inspected by and got approved from the engineer-in-charge before the reinforcement bars are placed in position.

The props shall consist of bullies having 100 mm minimum dia. measurement at mid length and 80 mm at thin end and shall be placed asper design requirement. These shall rest squarely on wooden sole plates 40 mm thick and minimum bearing area of 0-10 sq.m laid on sufficiently hard base.

Double wedges shall further be provided between the sole pite and the wooden props so as to facilitate tightening and easing of shuttering without jerking the concrete.

The timber used in shuttering shall not be so dry as too absorbed water from concrete and swell or bulge nor so green or wet as the shrink after erection. The timber shall be properly sawn and planned on the sides and the surface coming in contact with concrete. Wooden form work with metal sheet lining or side plates stiffened by steel angles shall be permitted.

As far as practicable, clamps shall be used to hold the forms together anduse of nails and spikes avoided.

The surface of timber shuttering that would come in contact with concrete shall be well wetted and coated with soap solution before the concreting is done. Alternatively, coat of raw linseed oil or oil of approved manufacturermay be applied in place of soap solution. In case of steel shuttering either soap solution or raw linseed oil shall be applied after thoroughly cleaning the surface. Under no circumstances, black or brunt oil shall be permitted.

The shuttering for beams and slabs shall have camber of 4 mm per meter(1 in 250) or as directed by the engineer-in-charge, so as to offset the subsequent deflection for cantilevers, the camber of free end shall be 1/50 of the projected or as directed by the engineer-in-charge.

### M-27. Expansion joints - Premoulded filler:

The item provides for expansion joints in R.C.C. frame structures for internal joints, as well as exposed joints, with the use of premoulded bituminous joint filler.

Premoulded bituminous joint filler, i.e. performed strip of expansion joint filler shall not got deformed or broken by twisting, bending or other handling when exposed to atmospheric condition. Pieces of joint filler that have been damaged shall be rejected.

Thickness of the pre-moulded joint filler shall be 25 mm. unless otherwise specified.

Premoulded bituminous joint filler shall conform to I.S. Latest edition.

### M-28. Expansion joints Copper strips & hold fasts:

The item provide for expansion joints in R.C.C. frame structure for internal joint as well as for exposed joints with the use of necessary copper strip and holdfasts.

Copper sheet shall be of 1.25 mm thick and of 1.25 mm width and the "U" shape in the middle.

Copper strip shall have holdfast of 3 mm diameter copper rod fixed to the plate soldered on strip at intervals of about 30 cm or as shown in the drawing or as directed. The width of each flange (horizontal side) of the copper plate to be emvidded in the concrete work shall be 25 mm. depth of "U" to be provided in the expansion joint, in the copper plate shall be of 25 mm.

### M-29. <u>Teak wood</u>:

The teak wood shall be of good quality as required for the item to be executed. When the kind of wood is not specifically mentioned, good Indian teak wood as approved shall be used.

Teak wood shall generally be free from large, loose, dead of cluster knots flaws, shakes, warps, twists, bends; or any other defects. It shall generally be uniform in substance and of straight fibres as far as possible. It shall be free from rot, decay, harmful fungi and other defects of harmfulnature, which will affect the strength, durability or its usefulness for the purpose for which it is required. The colour shall be uniform as far as possible. Any effort like paining, using any adhesive resinous materials made to hide the defects shall render the pieces liable to rejection by the Engineer-in-Charge.

All scantlings, planks etc. shall be sawn in straight lines and planes in the direction of grains and of uniform thickness.

The tolerances in the dimensions shall be allowed at the rate of 1.5 mm,per face to be planed.

### First class teak wood:

First class teak wood shall have no individual hard and sound knots, more than 6 sq.cm. in size and the aggregate area of such knots shall hot be than 1 % of area of piece, the timber shall be closed grained.

### **Second Class Teak Wood:**

No individual hard and sound knots shall be more than 15 sq.cm. in size and aggregates area of such - knots shall not exceed 2 % of the area of piece.

### M-29A. Non-teak wood:

The non-teak wood shall be chemically treated, seasoned as per I.S. Specification and of good quality. The type of, wood shall be got approved before collecting the same an site. Fabrication of wooden members shall be started only after approval.

For this purpose wood of Bio, Kalai, Sires, Saded, Behda, Jamun, Sisoo will be used for door where as only Kalai, Halda, Sires, Kalam etc. will be permitted far shutters after proper seasoning and chemical treatment, The non-teak wood shall be free from large, loose dead of cluster knots, flows, shakes, warps, bends or any other defects. It shall be uniform in substance and of straight fibres as far as possible. It shall be free from rots, decay, harmful fungi and other defects of nature which will effect the straight durability or its usefulness for the purpose for which it is required. The colour of wood shall-be uniform as far as possible. The scantalings planks etc. shall be saw in straight lines and planes in the direction of grain and of uniform thickness. The department will use the Agency to produce certificate from Forest Department in event of Dispute and the decision of the Department shall be final and binding to the contractor: The tolerance in the dimension shall be allowed at 1.5 mm. per face to beplaned.

### M-30. Wooden flush door shutters (solid core):

The solid core type flush door shutters shall be of decorative or non-decorative type as specified in the drawing. The size and thickness of the shutter shall be as specified in drawings or as directed. The timber species for core shall be used as per I.S. Latest edition. The timber shall be free from decay and insect attack. Knots and knot holes less than halfthe width of cross-section of the members in which they occur may be permitted. Pitch pockets, pitch streaks and harmless pin holes shall be permissible except in the exposed edges of the care members. The commercial plywood, cross-bands shall conform to I.S: latest edition.

The face panel of the shutters shall be formed by gluing by the hot press process on both faces of the care with either, plywood or cross-bands and face veneers. The lipping, rebating, opening of glazing; venetian etc.shall be provided if specified in the drawing.

All edges of the door shutters shall be square. The shutters shall be free from twist of warp in its plant Both faces of the shutters shall be sand papered to smooth even texture.

The shutters shall be tested for

- (1) **End immersion test:** The test shall be carried out as per I.S. latest edition. There shall be no delamination at the end of the test.
- (2) **Knife test:** The face panel when tested in accordance with I.S. latest edition shall pass the test.
- (3) **Glue adhesion test:** The flush door shall be tested for glue adhesive test in accordance with I.S.: latest edition. The shutters shall be considered to have passed the test if no delamination occurs in the glue lines in the plywood and if no single delamination more than 80 mm in length and more than 3 mm in depth has occured in the assembly glue lines between the plywood face and the style and rail. Delamination at the corner shall be measured continously around the corner. Delamination at the knots, knot holes and other permissible wood defects shall not be considered in assessing the sample.

The tolerance in size of solid care type flush door shall be as under:In Nominal thickness  $\pm$  1.2 mm in Nominal height  $\pm$  3 mm.

The thickness of the shutter shall be uniform throughout with a permissible variation of not more than 0:8 mm: when measured at any two points.

### M-31. <u>Aluminum doors</u>, <u>windows</u>, <u>ventilators</u>:

Aluminum alloy used in the manufacture of extruded window sections shall conform to I.S. designation HEA-WP of LS.: latest edition and also to I.S. Designation WVG-.WP of I.S. latest edition. The section shall be as specified in the drawing and design. The fabrication shall be done as directed.

The hinges shall be cast or extruded aluminum hinges of same type as in window but of larger size.

The hinges shall normally be of 50 mm. projecting type. Non-projecting type of hinges may also be used if directed. The handles of door shall be of specified design. A suitable lock for the door operable from outside or inside shall be provided. In double, shutter door, the first closing shutter shall have concealed aluminum alloy bolt at top and bottom,

### M-32. Rolling Shutters.

The rolling shutters shall conform to I.S. latest edition. Rolling shutters shall be supplied of specified type with accessories. The size of the rollingshutters shill be specified in the drawings. The shutters shall be con- structed with interlocking lath sections formed from cold rolled steel stripsnot less than 0.9 aim. thick and 80 mm. wide for shutters upto 3.5 mm, width not less than 1.25 mm, thick and 80 mm. wide for shutter 3.5 mm in width and above unless otherwise specified,

Hood covers shall be of mild steel deep channel section and of rolled pressed or build up (fabricated) jointless construction. The thickness of sheet used shall not be less than 3.5 mm.

Hood covers shall be made of M S Sheets not less than 0.90 mm. thick. For shutters having width 3.5 Meter and above, the thickness of M.S. sheet for the hood cover shall be not less than 1.25 mm.

The spring shall be of 'best quality and shall be manufactured from tested high tensile spring steel wire or strip of adequate strength to balance the shutters in all position. The spiting pipe shaft etc, shall be supported on strong M.S. or malleable C.I. brackets. The brackets shall be fixed on or under the lintel as specified with rawl plugs and screws bolts etc.

The rolling shutters shall be of self rolling upto 8 Sq. m. clear area withoutball bearing and up to 12 Sq. rn. clear area with ball bearing. If the rollingshutters are of larger, than gear operated type shutters shall be used

The locking arrangement shall be provided at the bottom of shutter at both ends. The shutters shall be opened from outside,

The shutters completed with door suspension shafts, looking arrangements, pulling hooks handles and other accessories.

### M-33. Collapsible Steel Gate:

The collapsible steel gate shall be in one or two leaves and size as per approved drawings or as specified. The gate shall be fabricated from best quality mild steel channels, flates etc. Either steel pulleys or ball - bearings shall be provided in every doubly channel, Unless otherwise specified the particulars of collapsible gate shall be as under:

- (a) **Pickets**: These shall be of 20 mm. M.S. channels of heavy sections unless otherwise shows on drawings. The distance center to center of pickets shall be 12 cms with an opening of 10 Cms.
- (b) Pivoted M.& flats shall be 20 mm x 6 mm.
- (c) Top and bottom guides shall be from tee or flat iron of approved size.
- (d) The fittings like stoppers, fixing hold fasts, locking cleats brass handles and cast iron rollers shall be of approved design and size.

### M-34. Welded Steel Wire Fabric

Welded steel wire fabric for general purpose shall be manufactured from cold drawn steel wire "as drawn" or galvanized steel conforming to LS. Latest edition with longitudinal and transverse wire securely connected at every intersection by a process of electrical resistance welding and conforming to I.S. latest edition. It shall be fabricated and finished in workmanlike manner and shall be free from injurious defects and shall be rust proof. The type of mesh shall be oblong or square as directed. The mesh sizes and size of wire for square as well as oblong welded steel wirefabric shall be as directed. The steel wire fabric in panels shall be in one whole piece in each panel as far as stock sizes permit.

### M-35. Expanded Metal. Sheets:

The expanded metal sheets shall be free from flaws, joints, broken strands, laminations and other harmful surface defects. Expanded metal steel sheet shall conform to I.S. latest edition, except that blank sheets heed not be with guaranteed mechanical properties. The seze of the size of the diamodd mesh of expanded metal and dimensions of strands (width and thickness) shall be as specified. The tolerance on nominal weight of expanded metal sheets shall be of 10 percent.

Expanded metal in panels shall be in one whole piece in each panel as faras stocks sizes permit. the expanded metal sheets shall be coated with suitable protective coating to prevent corrosion,

#### M-36. Mild Steel Wire (Wire Gauze Jali):

Mild steel wire may be galvanized, as indicated. A11 finished steel wire shall be well cleanly drawn to the dimensions, and size of wire as specified in item. The wire shall be sound, free from splits, surface flaws, rough jagged-and imperfect edges and other harmful surface defect and shall conform to I.S. latest edition.

#### M-37. Plywood

The plywood for general purpose shall conform I.S. latest edition.

Plywood is made by cementing together thin boards or sheets of wood into panels. There are always an odd number of layers, 3, 5, 7, 9 ply etc. The plies are placed so that grain of each layer is at right angle to the grain in the adjacent layer.

The chief advantages of plywood over a single board of the same thickness is the more uniform strength of the plywood, along the length and width of the plywood and greater ,resistance, to cracking and splitting with change in moisture content.

Usually synthetic resins are used for gluing, phenolic resions are usually cured in a hot press which compresses and simultaneously heats the plies between hot plates which maintain a temperature of 90 degree C to 140 degree and a pressure of 11 to 14 Kg/Sq. Cm. on the wood. The time of heating may be anything from 2 to 60 minutes depending upon thickness.

When water glue are used the wood absorbs so much water that the finished plywood must be dried carefully When synthetic resigs are used as adhesive the finished plywood must be exposed to an atmosphere of controlled humidity until the proper amount of moisture has been absorbed.

According to I.S. Latest edition, the plywood far general purpose shall be of the grades namely BWR; WWR and CWR, depending upon the adhesives used for bonding the veneers, and it will be further classified into six type namely AA, AB, AC, BB, BC and CC, based on the quality of the two faces, each face being moisture content not less than 8 percent and riot more than 16 percent.

#### 37.A. Thickness of plywood boards

| Board | Thickness | Board | Thickness | Board | Thickness | Board | Thickness |
|-------|-----------|-------|-----------|-------|-----------|-------|-----------|
| 3 ply | 3 mm      | 3 ply | 5 mm      | 3 ply | 9 mm      | 3 ply | 16 mm     |
|       | 4 mm      |       | 6 mm      |       | 13 mm     |       | 19 mm     |
|       | 5 mm      |       | 8 mm      |       | 16 mm     |       | 19 mm     |
|       | 6 mm      |       | 9 mm      |       | 13 mm     |       | 25 mm     |

#### M-38 Glass:

All glass shall be of the bet quality, from specks, bubbles, smokes, veins, air, holes blisters, and other defects. The kind of glass to be used shall be as mentioned in the item or specification or in the special provisions or asshown in detailed drawings. Thickness of glass panes shall be uniform. The specifications for different kinds shall be as under:

#### **Sheet Glass:**

In absence of any specified thickness or weight in the item or detailed specifications of the item of work, sheet glass shall be weighing 7.5 Kg/Sq. m. for panes upto 600 mmx500 mm.

For panes larger than 600 mm.x600 mm. and upto 800 mm.x800 mm. the glass weighing not less than 8.75 Kg Sq. m. shall be used. For biggerpanes upto 900 mm:x900 mm. glass weighing not less than 8.75 Kg/Sq. m. shall be used. For bigger panes upto 900 mm.x900 mm. glass weighing not less than 11.25 Kg/Sq. M. shall be used

Sheet glass shall be patent flattened glass of best quality and of glazing and framing purposes shall conform to I.S. latest edition. Sheet glass of the specked colour used, if so shown on detailed drawings or so specified. For important buildings and for panes with any dimension over 900 mm. plate glass of specified thickness shall be used.

#### Plate Glass :-

When plate glass is specked, it shall be "Polished patent plate glass" of best quality. It shall have both the surface ground late and parallel and polished to obtain clear undisturbed vision and reflection. The plate glass shall be of the thickness mentioned in the item or as shown in the detailed drawing or as specified. In absence of any specified thickness, the, thickness of plate glass to be supplied shall be 6 mm. and a tolerance of 0.20 mm. shall be admissible.

## **Obscured Glass:**

This type of glass transmits light so that vision is partially or almost completely obscured. Glass shall be plain rolled, figured, ribbed or fluted, or frosted glass as may be specked as required. The thickness and type ofglass shall be as per details on drawings or as specified or as directed.

#### Wired Glass:

Glass shall be with wire netting embedded in a sheet of plate glass. Electrically welded 13 mm. Georgian square mesh shall be used.

Thickness of glass shall not be less than 6 mm. Wired glass shall be of type and thickness as specified.

## M-39 Acrylic Sheets:

Acrylic sheet shall be of thickness as specified in the item and of an specked shape size as the case maybe. Panels may be flat or curved. It should be light in weight. It shall be colourless or coloured or opaque as specified in the item. Colourless sheet shall be as transparent as the finest optical glass. Its light transmission rate shall be about 95%. Transparency shall not be affected for the sheets thickness of it shall be extremely resistant to sunlight, weather and temperatures.

It shall not show any significant yellowing or change in physical properties or loss of light transmission over a longer period of use. The sheet shall be impact resistant also. Sheets should be of such quality that they can be cut, bent and jointed, as desired. Solution or the joints shall be used as per the requirement of manufacturer.

#### M-40. Particle board:

The particle boards used for face panels shall of best quality free from any defects. The particle boards shall be made with phenolamaldehyde adhesive. The particle boards shall conform to IS latest edition "Specifi- cation for wood particle board for general purpose" *The size and* the thickness shall be as indicated.

# M-41. Expanded polystyrene or tamed styroper slabs

The expanded polystyrene ceiling boards and tiles shall be of approved make and shall be of size, thickness finish and colour as indicated. It shallbe of high density and suitable for use as insulation material. The insulating material shall be like slab of Thermo Cole etc.

## M-42. Resign bonded fiber glass:

The resign bonded fiber glass tiles or rolls shall be of approved make and shall be followed.

For test of Mineral wool thermal insulation Blanker IS. : latest edition shallbe of sizes, thickness and finish as indicated.

Insulation wood blanket shall be with the following coverings on one or both side as indicated.

- (1) Bituminised hessain Kraft paper for use in position where moisture has to be excluded.
- (2) Hessian cloth or Kraft paper, for keeping out dust
- (3) G. I. wire netting, suitable for surfaces to be plastered over.

## M- 43. Fixtures and fastenings

#### General

The fixtures and fastenings, that is butt, hinges, tee and strap hinges sliding door bolts tower bolts, door latch, bath-room latch, handless doorstoppers, casement window fasteners, casement staysand ventilators

catch shall be made of the metal as specked in the item or its specification.

They shall be of iron, brass, aluminum, chromium plated iron, chromium plated brass, copper oxidized iron, copper oxidized brass or anodized aluminum as specified.

The fixtures shall be heavy, medium or light type. The fixtures and fastenings shall be smooth finished and shall be such as will ensure ease of operations.

The sample of fixture and fastenings shall be got approved as regards, quality and shape before providing them in position.

Brass and anodized aluminum fixtures and fastening shall be brightfinished.

#### **Holdfasts:**

Holdfasts shall be made from mild steel flat 30 cm. length and one of the holdfasts shall be bent at right angle and two nos. of 6 mm- diameter holes, shall be made in it for fixing it to the frame with screws. At the other end, the holdfast shall be forked and bent at right angles in oppositedirections

#### **Butt hinges:**

Railway standard heavy type butt hinges shall be used when so specified. Tee and strap hinges shall be manufactured from M.S. Sheet

# Siding door-bolts (Aldrops):

The aldrops as specified in the item shall be used and shall be tot approved.

## **Tower bolts (Barrel Type):**

Tower bolts as specified in the item shall be used and shall be got approved.

#### **Door Latch**

The size of door latch shall be taken as the length of latch.

#### **Bathroom Latch**

Bathroom latch shall be similar to tower bolt.

#### Handle

The size of the handles shall be determined by the inside grip length of the handles. Handles shall have a base plate of length 50 mm. more thanthe size of the handle.

#### **Door Stoppers**

Door Stoppers shall be either floor door stopper type or door catch type. Floor stopper shall be of overall size as specified and shall have a rubber cushion.

#### **Door Catch**

Door catch shall be fled at a height of about 900 mm. from the floor level such that one part of the catch is fitted on the inside of the shutter and the other part is fixed in the wall with necessary wooden plug arrangements for appropriate fixity. The catch shall be fixed 20 mm. inside the face of the door for easy operation of catch.

## **Wooden Door Stop with hinges**

Wooden door stop of size 100 mm X 60 mm.X 40 mm. shall be fixed on the door frame with a hinge of 75 mm. size and at a height of 900 mm. from the floor level. The wooden door stop shall be provided with 3 coats of approved oil paint.

#### **Casement window Fastener**

Casement window fastener for single leaf window shutter shall be left or right handed as directed.

# Casement stays (Straight Peg Stay):

The stays shall be made from a channel section having three holes at appropriate position so that the window can be opened either fully or partially as directed. Size of the stay shall be 250 mm to 300mm as directed.

#### **Ventilator Catch**

The pattern and, shape of the catch shall be as approved.

#### **Pivot**

The base and socket plate shall be made from minimum 3 mm. thick plate, and projected pivot shall not be less than 12 mm. diameter and 12 mm. length and shall be firmly riveted to the base plate in case of iron and in single piece in the case of brass pivot.

#### M-44. Paints:

Oil paints shall be of the specified colour arid shade, and as approved. The ready mixed paints shall only be used. However, if ready mixed paint of specified shade or tint is not available while ready mixed paint with approved stained will be allowed. In such a case, the contractor shall ensure that the shade of the paint so allowed shall be uniform.

All the paints shall meet with the following general requirements

- (i) Paint shall not show excessive setting in d freshly opened full can and shall easily be redispresed with a paddle to a smooth homogeneous state. The paint shall show no curdling, livering, caking or colour separation and shall be free from lumps and skins.
- (ii) The paints as received shall brush easily, Possess good leveling properties and show no running or sagging tendencies.
- (iii) The paint shall not skin within 48 hour in a three quatereds filled closed container.

(iv) The paint shall dry to the smooth uniform finish free from roughness, grift, unevenness and other imperfections:

#### **Enamel Paints:**

The enamel paint shall satisfy in general requirements in specification of oil paints: Enamel paint shall conform to IS: latest edition.

# M-45 French Polish

The French polish of required tint and shade shall be prepared with the below mentioned ingredients and other necessary materials

(i) Denatured spirit of approved quality (ii) Chandras (iii) Pigment.

The French polish so prepared shall conform to IS: Latest edition.

#### M-46 Marble chips for marble mosaic terrazzo:

The marble chips shall be of approved quality and shades: It shall be hard, sound, dense and homogeneous in texture with crystalline and coarse grains. It shall be uniform in colour and free from stains, cracks, decay and weathering.

The size of various colour of marble chips ranging from the smallest upto 20 mm. shall be used where the thickness of top wearing layer is 6 mm. size. The marble chips of approved quality and colours only as per grading as decided by the Engineer-in-charge shall be used for marble mosaic tiles or works.

The marble chips shall be machine crushed. They shall be free from foreign matter, dust etc, except as above, the chips shall conform to IS latest edition.

#### M-47. Flooring Tiles:

## (A). Plain Cement tiles

The plain cement tiles shall be of general purpose type. These are the tiles in the manufacture of which no pigments are used. Cement used in the manufacture of tiles shall be as per Indian Standards.

The tiles shall be manufactured from a mixture of cement and natural aggregates by pressure process. During manufacture, the tiles shall be subjected to pressure of not less than 140 Kg/Sq. Cm. The proportion of cement to aggregate in the backing of the tiles shall be-not less than 1:3by weight. the wearing face though the tiles are of plain cement, shall be provided with stone chips of 1 to 2 mm. size. The proportions of cement to aggregate in the wearing layer of the tiles shall be three parts of cement to one parts chips by weight. The minimum thickness of wearing layer shall be 3 mm. The colour and texture of wearing layer shall be uniform throughout its face and thickness. On removal from mould, the tiles kept in moist condition continuously at least for seven days and subsequently, if necessary, for such long periods would ensure their conformity to requirements of IS. Latest edition regarding strength resistance to wear and water absorption.

The wearing face of the tiles shall be plane, free from projections, depressions and cracks and shall be reasonably parallel to the back face of the tile. All angles shall be right angle and all edges shall be sharp and true.

The size of tiles shall generally be square shape 24.85 Cm. x 24.85 Cm: or 25 Cm. x 25 Cm. The thickness of tiles shall be 20 mm.

Tolerance of length and breadth shall be plus or minus one millimeter. Tolerance on thickness plus 5 mm.

The tiles shall satisfy the tests as regards transverse strength, resistance to wear and water absorption as per I.S.: Latest edition.

# (B) Plain Coloured Tiles:

These tiles shall have the same specification as for plain cement tiles as per (A) above expect that they shall have a plain wearing surface wherein pigments are used. They shall conform to I.S. Latest edition.

The pigments used for colouring cement shall not exceed 10 percent by weight of cement used in the mix. The pigments, synthetic or otherwise, used for colouring tiles shall have permanent colour and shall not contain materials detrimental to concrete.

The colour of the tiles shall be specified in the item or as directed.

## (C) Marble Mosaic Tiles:

The tiles same specification as per plain cement tiles except the requirements as stated below:

The marble mosaic tiles shall conform to I.S. latest edition. The wearing face of the tiles shall be mechanically ground and filled. The wearing face of tiles shall be free from projections, depressions and cracks and shall bereasonably parallel to the back face of the tiles. All angles shall be right angles and all edges shall be sharp and true.

Chips used in the tiles be from smallest upto 20 mm. size. The minimum thickness of wearing layer of tiles shall be 6 mm. For pattern of chips to be had on the wearing face, a few samples with or without their full size photographs as directed shall be presented to the Engineer-in-charge for approval.

Any particular samples, if found suitable shall be approved by the Engineer-in-charge, or he may ask for a few more samples to be presented. The samples shall have to be made by the contractor till a suitable sample is finally approved for use in the work. The Contractor, shall ensure that the tiles-supplied for the work shall be in conformity with the approved sample only, in terms of its dimensions thickness of backing layer and wearing surface, materials, ingredients, colour. shade chips, distribution etc. required.

The tiles shall be prepared for cement conforming to Indian Standards or coloured portland cement generally depending upon the colour of tiles to be or as directed.

# (D) Chequered Tiles:

Chequered tiles shall be plain cement tiles or marble mosaic tiles. The former shall have the same specification as per (A) above and the latter as per marble mosaic tiles as per (C) except as mentioned below. The tiles shall be of nominal size of 250 mm. X 250 mm. if specified. The centre to centre distance of chequer shall not be less than 25 mm. and not more than 50 mm. The overall thickness of the tiles shall be 22 mm.

The grooves in the chequers shall be uniform and straight. The depth of the grooves shall not be less than 3 mm. The chequered tiles shall be plain, coloured or mosaic as specified. The thickness of the upper layer measured form the top of the chequers shall not be less than 6 mm. The tiles shall be given the first grinding with machine before delivery to site.

Tiles shall conform to relevant IS: latest edition.

# (E) Chequered Tiles For Stair Cases:

The requirements of these tiles shall be the same as chequered tiles as per (D) above except in following respects :

(1) The length of a tile including note shall be 330 mm: (2) The minimum thickness shall be 28 mm: (3) The nosing shall have also the same wearing layer as at the top: (4) The nosing edge shall be rounded. (5) The front portion of the tiles for minimum length of 75 mm. from and including the nosing shall have grooves running parallel to nosing and at centers not exceeding 25 mm. Beyond that the tiles shall have normal chequer pattern.

## M-48. Rough Kotah Stone:

The kotah stones shall be hard, even, sound and regular in shape and generally uniform in colour, The colour of the stone shall generally be green. Brown coloured shall not be use. They shall be without any soft veins, cranks or flaws.

The size of the stones to be used for flooring shall be of size  $600 \text{ mm.} \times 600 \text{ mm.}$  abd / or size  $600 \text{ mm.} \times 450 \text{mm}$  as directed. However smaller sizes will be allowed to be used to the extent of maintaining required pattern. Thickness shall be as specified.

Tolerance of minus 30 mm. on accounts of chisel dressing of edges shall be permitted for length as well as breadth. Tolerance in thickness shall be + 3 mm.

The edges of stones shall be truly chiselled and table rubbed with coarse sand before paving. All angles and edges of the stone of shall be true, square and free from chipping and the surface shall be true and plain.

When machine cut edges are specified, the exposed and the edges at joints shall be machine cut. The thickness of the exposed machine cut edges shall be uniform.

#### M-49. Polished Kotah Stones:

Polished kot4h stone shall have the same specification as per rough kotah stone except as mentioned below:

The stones shall have machine polished surface. When brought an site, the stones shall be single polished or double polished depending upon its use. The stones for paving shall generally be single polished. The stones to be used for dedo, skiri thing sink, veneering, sills, steps, etc, where machine polishing after the stone are fixed in situ is not possible shall be double polished.

#### M-50. Dholpur Stone Stab:

Dholpur stone slab shall be of best quality as approved by the Engineer-incharge: The stone slab shall be without any veins, cracks, and flaws. The stone slab be even, sound and durable regular in shape and of uniform colour.

The size of the stone shall be as specified in the item or detailed drawing of as approved by the Engineer-in-charge. The thickness of the stone shall be as specified in the item of work with the permissible tolerance of plus or minus 2 mm. the provisions in respect of polishing as for polished kotah stone shall apply to polished Dholpur stone also. All angles and edges of the face of the stone slab shall be fine chiselled or polished as specified in the item of work and ai6 the four edges shall be machine out. All angles and edges of the stone slab shall be true and plane.

The sample of stone shall be got approved by the Engineer-in-charge for a particular work. It shall be ensured that the stones to be used in a particular work shall not differ much in shade or tint from the approved sample.

#### M-51. Marble Slab:

Marble slab shall be white or of other and of best quality as approved by the Engineer-in-charge.

Slabs shall be hard close, uniform and homogeneous in texture. They shall have even crystalline grain and free from defects and cracks. the surface shall be machine polished to an even and perfect plane surface and edges machine cut true and square. The rar face shall be rough to provide key for the mortar.

Marble slabs with nature veins, if selected shall have to be laid as per the pattern given by the Engineer-in-charge. Size of the slab minimum 460 mm. X 450 mm: and preferably 600 min. X 600 mm. However smaller sizes will be allowed to be used to the extent of maintaining required pattern.

The slab shall not be thinner than the specified thickness at its thinnest part. A few specimen of finished slab to be used shall be deposited by the Contractor in the office for reference.

Except as above, the marble slabs shall conform to IS: Latest edition.

## M-52. Granite Stone slab:

Granite shall be of approved colour and quality. The stone shall be hard, even sound and regular in shape and generally uniform in colour. It shallbe without any soft veins, cracks of flaws.

The thickness of the stone shall be as specified in item.

All exposed faces shall be double polished tender truly smooth and even reflecting surface. The exposed edges and corners shall be rounded off as directed. The exposed edges shall be machine cut and shall have uniform thickness.

#### M-53. PVC Flooring

PVC sheet for PVC, floor covering shall be of homogenous flexible type, conforming to I.S. Latest edition. The PVC covering shall neither develop any toxic effect while put to use for shall give off any disagreeable odour.

Thickness of flexible type covering Ales shall be as specified in the description of the item.

The flexible shall be backed with hessian or other woven fabric. The following tolerances shall be applicable on the nominal dimensions of the folls or tiles:

- (a) Thickness  $\pm$  15 mm.
- (b) Lengh of Width:
- 1. 300 rnm. square tiles  $\pm$  0.20 mm
- 3. 900 mm, square tiles  $\pm$  0.60 mm,
- 2. 600 mm. Square tiles  $\pm$  0.40 mm. 4. Sheets and roll  $\pm$  0.10 percent.

#### **Adhesive:**

The adhesive for PVC flooring shall be of the type and make, recommended by the manufactures of PVC sheets/tiles.

#### M-54 Facing Tiles

The facing tiles (burnt clay facing bricks) shall be free from cracks and nodules of free lime. They shall be thoroughly burnt and shall have plane rectangular faces with parallel sides and sharps straight right angled faces.. The texture of the finished surface that will be exposed when in place shall conform to an approved sample consisting not less than four stretch brickseach representing the texture desired. The facing tiles shall have apleasing appearance sufficient resistance to penetration by rain and greaterdurability than common bricks. The tiles shall conform to I.S.Latest edition.

Ι

The standard size of facing brick tiles shall be 19 x 9 x 4 cms. The facing brick tiles shall be provided with frog which shall conform to IS: Latest edition.

The permissible tolerance in dimensions specified above shall be asfollows:

| Size | Tolerance for   |                 |  |  |
|------|-----------------|-----------------|--|--|
|      | 1st class brick | 2nd class brick |  |  |
| 19   | ± 6 mm          | ± 10 mm         |  |  |
| 9    | ± 3 mm          | ± 7 mm          |  |  |
| 4    | ± 1.5 mm        | ± 3 mm          |  |  |

The tolerance for distortion or warpage of face or edges of individual brick form a plane surface and from a straight line respectively shall be as follows:

| Ficing dimensions | Permissible tolerance |
|-------------------|-----------------------|
| Max. below 19 cms | Max 2.5 mm            |
| do above 19 mm    | Max 3.0 mm            |

The average compressive strength obtained as a sample of five tiles when tested in accordance with the) procedure laid as per IS: Latest edition shall be not less than 175 Kg/Sq. Cm. The average compressive strength of any individual bricks shall be not less than 160 Kg/Sq. Cm.

The average water absorption for five bricks tiles shall not exceed 12 percent of average weight of brick before testing. The absorption for each individual bricks shall not exceed 25 percent.

The brick tiles when tested in accordance with IS: Latest edition, the rate of efflorescence shall not be more than "Slightly effloresced'

## M-55. White glazed tiles

The tiles shall be of best quaky as approved by the Engineer- in-charge. They shall be foat and true to shape. They shall be free from cracks, crazing spots, chipped edges and corners. The glazing shall be of uniformshade.

Variation from the stated sizes, other than the thickness of tile shall be plus or minus 1.5 mm. The thickness of tile shall be 6 mm. Except as above the tiles shall conform to I.S. Latest edition.

#### M-56. Galvanized Iron Pipes and Fittings:

Galvanized iron pipe shall be of the medium type and of required diameter and shall comply with IS: latest edition. The specified diameter of the pipes shall refer to the inside diameter of the bore. Clamps, screw and all galvanized iron fittings shall be of the standard'R' or equivalent make.

## M-57. Bib cock and stop cock:

A bib cock is a draw off tap with a horizontal inlet and free outlet. A stop cock is a valve with a suitable means of connection for insertion in a pipeline for controlling or stopping the flow.

They shall be of screw down type and or brass chromium plated and of diameter as specified in the description of the item. They shall conform to IS: latest edition and they shall be of best Indian make. They shall be polished bright.

The minimum finished weight of bib cock and stop cock shall be as given below:

| Diameter | Bib cock | Stop cock | Diameter | Bib cock | Stop cock |
|----------|----------|-----------|----------|----------|-----------|
| 8 mm     | 0.25 kg  | 0.25 kg   | 15 mm    | 0.40 kg  | 0.40 kg   |
| 10 mm    | 0.30 kg  | 0.35 kg   | 20 mm    | 0.75 kg  | 0.75 kg   |

# M-58. Gun metal wheel valve:

The gun metal wheel valve shall be of approved quality. These shall be of gun metal fitted with wheel and shall be of gate valve opening fullway and of the size as specified. These shall conform to IS: latest edition.

## M-59. White glazed porcelain wash basin:

Wash basin shall be of white porcelain first quality best Indian makeand it shall conform to IS: latest edition. The size of the wash basinshall be as specified in the item. Wash basin shall be of one piece construction with continued over flow arrangements. All internal angles shall be designed so as to facilitate cleaning. Wash basin shall have single tap hole or two holes as specified. Each basin shall have a circular waste hole which is either revated or beveled internally with 65 mm diameter at top and 10 mm depth to suit the waste fitting. The necessary stud slot to receive the bracket on the under side of the basin shall be provided. Basin shall have an internal soap holder recess which shall fully drain into the bowl.

White glazed pedestal of the quality and color as that of the basin shallbe provided where specified in the item. It shall be completely recessed at the back for reception of supply and wash pipe. It shall be capable of supporting the basin rigidly and adequately and shall be so designed as to make the height from the floor to top of the rim of basin 750 mm to 800 mm as directed.

## M-60. <u>European type water closet with low level flushing</u>:

The European type water closet shall be white glazed porcelain first quality and shall be of wash down type conforming to IS: latest edition.

'S' trap shall be provided as required with water seal not than 50 mm. The solid plastic seal and cover shall be of best Indian make conforming to IS: latest edition. They shall be made of moulded synthetic materials which shall be tough and hard with high resistance to solvents and shall be free from blisters and surface defects and shall have chromium plated brass hinges and rubber buffer of suitable size.

#### M-61. Orissa type water closet:

The specification of Orissa type white glazed water closet of first quality shall conform to IS: latest edition and relevant specification of Indian type water closet except that pan will be with the integral squatting pan of size  $580 \times 440$  mm with raised footrest.

## M-62. Indian type water closet:

The Indian type white glazed water closet of first quality shall be of size as specified in the item and conforming to IS: latest edition. Each pan shall have integral flushing. It shall also have an inlet at back or front for connecting flush pipe as directed. The inside of the bottom of the pan shall have sufficient slope from the front towards the outlet and surface shall be uniform and smooth. Pan shall be provided with 100mm. diameter "P" or "S" trap with approximately 50 mm, Water seal and 50 mm. diameter vent horn.

#### M-62 A Foot Rests

A pair of white glazed ear then ware rectangular foot of minimum size 250 mm, x 130 mm x 20 min shall be provided with the water closet.

#### M-63 Glazed Earthen Ware Sink

The glazed earthen ware sink shall be of specified size, colour and quality. The sink shall conform to I. S. latest edition. The brackets for sinks shall conform to IS: latest edition.

The pipes shall conform to I.S. latest edition for steel and lead pipes respectively. 32 min. brass waste coupling of standard pattern with brass chain and rubber plug shall he provided with sink.

# M-64. Glazed earthen-ware Lipped type flat back urinal / corner type urinal.

The lipped type shall be flat. back or corner type as specified in the item and shall conform to IS: Latest edition. It shall be of best Indian make and size as specified arid approved by the Engineer-in-charge. The flat back or corner type urinal must be of 1st quality free from any defects, cracks etc.

#### M. 65. Low level enamel flushing tank

The low level enamel flushing tank shall be of 15 litres capacity. It shall conform to IS: latest edition. The flushing cistern shall be of best quality and free from any defects. The flushing tank shall have outlet 32 mm. diameter. The outlet shall he connected with WC. Pan by lead pipe or PVC pipe as specified. The flushing cistern shall be provided with inlet and outlet for fixing G.I. inlet pipes and overflow pipes The flushing cistern shall be provided with chromium plated handle for flushing. The flushing tank shall be provided with bracket of cast iron so that it can be fixed on wall at specified height. The, brackets shall conform to I.S. latest edition.

#### M-66. Cast iron flushing cistern.

The cast iron flushing cistern shall be of 15 litres capacity. It conform to IS. latest edition, The flushing cistern shall be of best quality free from any defects, The flushing cistern shall have outlet of 32 mm. diameter. The leadpipe shall conform IS: latest edition. For fixing G.I. inlet pipes and overflowpipe 20 mm dia inlet and outlet shall he got provided. The flushing, cistern shall be provided with galvanized iron chain and pull of sufficient length andshall be got approved from the engineer-in-charge. The cast iron flushing cistern shall be painted with one coat of anti-corrosive paint and two coats

of paints. The flushing cistern shall be fixed on two C.I. brackets. The C.I. bracket shall conform to IS: latest edition.

## M-67 Flush Cock

Half turn flush cock (Heavy weight) shall be of gun metal chromium plated of diameter as specified in the description of the item. The flush cock shall conform to relevant Indian Standard.

# M-68 Cast iron pipes and fittings.

All soil, water, vent and antisyphonage pipe and fitting shall conform to IS: latest edition. The pipe shall have spigot and socket ends with head on spigot end. The pipes and fittings shall be true to shape, smooth, cylindricaltheir inner and outer surfaces being as nearly as practicable concentric. They shall be sound and nicely cast and shall be free from cracks, laps pinholes or other imperfection and shall be neatly dressed and carefully settled.

The end of pipes and fittings shall be, reasonable square to their axis.

The sand cast iron pipes shall be of the diameter as specified in the description and shall be in lengths of 1.5 M, 1.8 M. and 2 M. including socket ends of the pipe unless shorter lengths are either specified or required at junctions etc. The pipes and fittings shall he supplied. without ears unless specified or directed otherwise.

#### **Tolerances**

The standard weights and thickness of pipes shall be as shown in the following table:

| Sr | Nominal      | Thickness | Overall  | Weight of | Excluding |
|----|--------------|-----------|----------|-----------|-----------|
| No | dia. of bore |           |          | pipe      | ears      |
|    |              |           | 1.5 m    | 1.8 m     | 2 m long  |
| 1  | 75 mm        | 5.0 mm    | long     | long      | 18.37 kg  |
|    |              |           | 12.83 kg | 16.52 kg  |           |
|    |              |           |          |           |           |
| 2  | 100 mm       | 5.0 mm    | 18.14 kg | 21.67 kg  | 24.15 kg  |

A tolerance upto minus 15 percent in thickness and 20 mm in length will be allowed. For fittings tolerance in lengths shall be plus 25 mm and minus 10 mm.

The thickness of fittings and their socket and spigot dimensions shall conform to the thickness and dimensions specified for the corresponding sizes of straight pipes. The tolerance in weights and thickness shall be the same as for straight pipes.

# M-69. Nahni Trap:

Nahni trap shall be of cast iron and shall be sound and free from porosity or other defects which affect serviceability. The thickness of the base metal shall not be less than 6.5 mm. The surface shall be smooth and free from craze, chips and other flaws or any other kind of defect which affect

serviceability. The size of nahni trap shall be as specified and shall be of self cleaning design.

The nahni trap shall be of quality approved by the engineer-in-charge and shall generally conform to the relevant Indian Standard.

The nahni provided shall be with deep seal, minimum 50 mm except at places where trap with deep seal cannot be accommodated. The cover shall be cast iron perforated cover shall be provided on the trap of appropriate size.

# M-70. Gully Trap:

The gully trap shall conform to IS: latest edition. It shall be sound, free from defects such as fire cracks or hair cracks. The glaze of the traps shall be free from crazing. They shall give a sharp clear note when struck with light hammer. There shall be no broken blisters.

The size of the gully trap shall be as specified in the item.

Each gully trap shall have one C.I. grating of square size corresponding to the dimensions, of inlet of gully trap. It will also have a water tight C.I. cover with frame inside dimension 300 mm  $\times$  300 mm. The cover with frame inside dimensions 300 mm  $\times$  300 mm the cover weighing not less than 4.53 kg and the frame not less than 2.72 kg. The grating cover and frame shall be of sound and good casting and shall have truly square machined seating faces.

## M-71. Glazed stone ware pipe and fittings:

The pipes and fittings shall be of best quality as approved by engineer-incharge. The pipe shall be of best quality manufactured from stoneware offire clay, salt glazed thoroughly burnt through the whole thickness, of a close even texture, free from air blows, fire blisters, cracks and other imperfections, which affect the serviceability. The inner and outer surfaces shall be smooth and pefectly glazed. the pipe shall be capable to withstand presures of 1.5 m lead without showing sign of leakage. The thickness of the wall shall not be less than 1/12th of the internal dia. the depth of socket not be less than 38 mm. The socket shall be sufficiently large to allow a joint of 6 mm around the pipe.

The pipes shall generally conform to relevant IS latest edition.

## M-72. Wall Peg Rail:

The aluminum wall peg rail shall have three aluminum pegs of approved quality and size. It shall be fixed on teak wood plank of size  $450 \text{ mm} \times 20 \text{ mm}$ . The teakwood shall be french polished or oil painted as specified.

## M-73. <u>G.I.</u> <u>Water Spot</u>:

The G.I. pipes of 40 mm dia shall be of medium quality and specials shall be of 'R' brand or equivalent of the best approved quality.

The pipe shall have length as required for the thickness of wall in which it is fixed, and at outside end tee and bend cut at half the length shall be

provided and at other end, coupling shall be provided to have better fixing. The water spout shall be provided as per detailed drawing or as directed.

# M-74. Asbestos Cement Pipe (A.C. Pipe)

The asbestos cement pipe of diameter as specified in the description of the item shall conform to I.S. latest edition. Special like bends, shoes, cowls etc. shall conform to relevant Indian Standards. The interior of pipe shall have a smooth finish, regular, surface and regular internal diameter. The tolerance in all dimension shall be as per IS: latest edition.

#### M-75. Crvdon Ball valve

Ball valve of screwed type including polythene float and necessary level etc. shall be of the size as mentioned in the description of item and shall conform to IS: latest edition.

# M-76. Bitumen Felt For Water Proofing And Damp Proofing

Bitumen felt shall be on the fiber bases and shall be of type 2, self finished felt grade-2 and shall conform to IS: latest edition.

# M-77. Selected Earth

The selected earth shall be that obtained from excavated material or shall have to be brought from outside as indicated in the item. If item does not indicate anything the selected earth shall have to be brought fromoutside.

The selected earth shall be good -yellow soil and shall begot approved from the Engineer-in-charge. In no case black cotton soil or similar expensive and shrinkable soil shall be used. It shall be clean and free from all rubbish and perishable materials, stones or brick bats. The clods shall be broken to a size of 50 mm. or less. Contractor shall make his own arrangement at his own cost for land for borrowing selected earth. The stacking of material shall be done as directed by the Engineer-in-charge insuch a way as not to interfere with any constructional activities and in proper stacks.

When excavated material is to be used, only selected stuff got approved from the Engineer-in-charge shall be used. It shall lie stacked separately and shall comply with all the requirements of selected earth mentioned above.

### M-78. Barbed Wire.

The barbed wire shall be of galvanized steel and it shall generally conform to IS: latest edition. The barbed wire shall be of type-I whose nominal diameter for line wire shall be 2.5 mm and point wire 2.24 mm. The nominal distance between two barbs shall be 75 mm, unless otherwise specified in the item. The barbed wire shall be formed by twisting together two line wires, one containing the barbs. The size of the line and point wires and barb spacing shall be as specified above. The permissible deviation from the nominal diameter of the line wire and point wire shall not exceed 0.08 mm.

The barbs shall carry four points and shall be formed by twisting two point wires, each two turns, lightly round one line wire, making altogether four complete turns. The barbs shall be so finished that the tour points are setand locked at right angles to each other. The barbs shall have a length ofnot less than 13 mm. and not more than 18 mm. The point shall be sharpand cut at an angle not greater than 35 degree of the axis of the wire forming the barbs.

The line and point wires shall be circular section, free from scale and other defects and shall be uniformly galvanized. The line wire shall be in continuous length and shall not contain any welds other than those in the rod before it is drawn. The distance between two successive splices shall not be less than 15 meters.

The lengths per 100 Kg. of bar bed wire IS: type I shall be as under: Nominal 1000 meters. Minimum 934 Meter. Maximum 1066 Meter.

#### M-79 Admixture for mass concrete and mortar:

#### M-79A) Joint Sealant

The sealant shall be best quality and from manufacturer like CICO, Fosroc MC-BAUCHEMIE, PIDILITE, HMP or equivalent as approved by engineer- in-charge. The prior approval for the source shall be taken from the engineer-in-charge. It shall be conformed to the relevant I.S. Code.

It shall be two component polysulphide rubber joint sealant, based on a low molecular weight polymer. It should not contain chloride or other corrosive substances.

It shall be used for sealing joints in water retaining structure, roofs, external wall, cladding, floors, partition, sealing, pavement surface etc. It shall have excellent property to adhere most of building material like aluminum, stainless steel, glass, concrete, marble, stone, brick, masonry block, plaster, ceramic, quarry tiles, timber etc. The modulus of elasticity of the sealant shall be less than 0.16 MPa,  $\pm 10\%$  at 100% elongation. The shore "A" hardness of the sealant shall be 22 $\pm 3$  @ 250C.

The operating temperature range for the sealant shall be 250C to 800C. The permanent dynamic movement capability of the sealant shall be  $\pm 25\%$ . The tensile strength of the sealant shall not be less than 0.4 MPa. The optimum width / depth ratio shall be 2:1. The specific gravity of the sealant shall be 1.6 kg/Lit. The sealant should be capable to resist to attack of water, sunlight, oxidation, corrosive fumes, oils, petrol, diluted acids and alkalies, salt spray, aliphatic and aromatic solvent and shall not contain tar or bituminous ingredients.

It shall possess the properties like 550% elongation at break, non-toxicity when fully cured, no staining and shrinkage less than 1%. The trafficable strength shall be achieved within 24 hours and full at 7 days (at 250C and 250% RH). It shall posses excellent coverage capacity and more strength at low dry temperature.

#### M-79B) Abrasion Resistant Industrial Flooring Aggregate:

The flooring aggregate shall be of best quality and from manufacturer like CICO, Fosroc or equivalent, as approved by the engineer-in-charge. The prior approval for the source shall be taken from the engineer-in- charge. It shall beconformed to the relevant I.S. Code.

The flooring aggregate shall be factory processed and specially graded non-oxidized, non-magnetic and chemically inert metallic flooring aggregate, free from oil and grease.

It shall be used as a surface hardener to concrete floors. It is recommended forfactory floors, warehouses, hangers, car parks and such other areas subjected to heavy vehicular traffic. It shall also be used on open and continuously wet surfaces. The flooring aggregate shall build in wearing resistance and shall produce high abrasion resistant floor surfaces. It shall impart extreme surface density and shall offer resistance to oil and water penetration. It shall provide a non-rusting floor surface which is easy to maintain.

It shall be used with cement in the ratio, as per manufacturer's instruction and spread evenly on the surface to be treated, at the rate depending on the type of floor. The flooring aggregate shall be spread when the surface of the concrete floor is still fresh, i.e. as soon as the surface water has evaporated and then trawled, in stage, to bring about an uniform and smooth finish.

#### M-79C Concrete Hardener and Dust Proofer:

The concrete hardener and dust proofer, shall be of the best quality and from manufacturer like CICO, Fosroc or equivalent, as approved by the engineer-incharge. The prior approval for the source shall be taken from the engineer-incharge. It shall be conformed to the relevant I.S. Code.

It shall have a specific gravity of 1.18 and shall be applied on concrete floors, at the ate of at least 25 liter/100 m2/coat. A total of 3 coats shall be applied for permanently hardened concrete floor, with increased abrasion resistance, increased surface density, increased resistance to chemical attack and to eliminate dust accumulation. Drying time of 4 to 6 hours for each coat shall be allowed before the flooring is put to use or is applied with another coat of the product. Precautions shall be taken while using the product, to avoid contact with eye and open wounds and to work in good ventilation. After application, the affected part shall be washed copiously. It shall not be stored for the period of more than two months before use.

#### M-79D Water Repellent Coating:

The water repellent coating shall be of the best quality and from manufacturerlike CICO, Fosroc or equivalent, as approved by the engineer-in- charge. The prior approval for the source shall be taken from the engineer-in-charge. It shall be conformed to the relevant I.S. Code.

Water repellent coatings for exterior exposed surfaces shall be acrylic resin based, having a Flash point of approx. 40°C and specific gravity of 0.95.

It shall be suitably used for concrete, brick, stone and plastered surfaces preventing moisture penetration and thus any damage to the interiors. It shallbe quick acting, long lasting, invisible i.e. colourless so as to maintain theoriginal colour of the surface treated. It shall impart sealing characteristics sothat the treated surface becomes stain and dust free. The coating itself shall not darken or turn yellow with age.

# M-79E Accelerating, Water Reducing Admixture and Plasticiser:

The Accelerating, Water reducing admixture and plasticiser, shall be of best quality and from manufacturer like CICO, Fosroc or equivalent, as approved by the Engineer. The prior approval for the source shall be taken from the Engineer. It shall conform to the relevant IS Code.

It shall be in liquid state with a specific gravity of 1.30 and complying with- ASTM C-494 Type E, IS: 9103 & IS: 2645. It shall accelerate the setting and hardening of the concrete mix, thereby achieving higher early age strength. It shall reduce the water content of the concrete without affecting its workability. It is useful for pre-cast/pre-stressed works, structural concrete works, floors, roads, runways, paving etc. It shall be used at the rate instructed by the manufacturer, with cement, depending on the amount of acceleration of hardening required, it should be compatible

to all types of cement.

## M-79F Retarding, Water Reducing Admixture and Plasticiser:

The Retarding, water reducing admixture and plasticiser, shall be of best quality and from - manufacturer like CICO, Fosroc, Feb Roffe or equivalent, as approved by the Engineer. The prior approval for the source shall be taken from the Engineer. It shall conform to the relevant IS Code.

It shall be in liquid state with a specific gravity of 1.22 and complying with ASTM C-494 Type B & D, IS 9103, CRD-C87 Type B & D, BS 5075 Part 1. It shall be added to the concrete mix during the mixing process, at the same time as the water or the aggregates. No extension of normal mixing time is necessary. It shall extend the period of time as to placing the concrete and compacting, i.e. delay the initial and final setting time. It shall help to spread the heat of hydration over a longer period of time. It shall give a highly workable concrete with a low W/C ratio. It shall

be used at the rate instructed by the manufacturer, with cement, depending on he amount of acceleration of hardening required. It should be compatible to all types of cement.

#### M-79G Water & Weather Proof Compound:

The water & weather proof integral cement admixture shall be of best quality and from manufacturer like Feb Roffe's Roff Hyseal, Roff hyproof, Algiproof or equivalent, as approved by the Engineer. The prior approval for the source shall be taken from the Engineer. It shall conform to the relevant IS Code.

It shall be used as an excellent cement admixture in all types of concrete/plaster mortars, pointing mortars, masonry works, guniting works and pressure grouting works. It shall improve resistance of concrete surfaces to weathering and chemical attack. It shall be non-toxic so as to use for water proofing water tanks, reservoirs, bio-gas tank, leaking ceiling, basements,

tunnels, lift wells etc.

It shall be mixed to concrete or plaster mortar, while mixing. First, water is added and then the admixture, at the rate instructed by the manufacturer. Foruse of the admixture, precaution shall be taken to use clean materials for preparation of mortar.

#### M-79H Plaster Admixture:

An admixture which gives the plaster workability, durability and quality at aneconomical rate shall be of best quality from manufacturer like Feb Roffe (product name - Roff plaster master) or equivalent, as approved by the Engineer. It shall comply to the relevant IS Codes.

It shall keep the plastering mortar plastic for a longer time, giving higher strength on prolonged curing. It shall provide cohesiveness, workability and eliminate efflorescence. It shall reduce shrinkage, cracking and crazing to the minimum.

## M-80 Fly Ash:

Fly Ash of grade-I as per IS: 3812-1981 shall be from Sikka Thermal Power Station Only. Contractor has to manage for required size containers at site work for storing the Fly ash.

#### M-81 Anti-Corrosive Paints: M-81A Ferroshield:

It shall be from STP Limited or equivalent, as approved by the Engineer.

It shall be a high build bituminous emulsion, specially formulated for protection against corrosion. It shall form a dry film, 2 mm. thick, which shall not crack at low temperatures nor crocodile at-very high temperatures. It shall also be used as waterproofing material on flat, sloped and steeped roofs. It shall be applied by brush and by heavy duty airless spraying. ..

#### M-81B Tankmastic:

It shall be from STP Limited or equivalent, as approved by the Engineer. It shall conform to IS: 158-9862.

It shall be special bituminous paint, which shall have no harmful reaction on drinking water. It shall be used to protect the inside of water tanks and pipe connections, against corrosion. It shall be applicable on steel, wood, concrete, iron etc. It shall have a covering capacity of  $12 \, \mathrm{m}^2/\mathrm{lit}$ .

## M-81C Pipekote:

It shall from STP Limited or equivalent, as approved by the Engineer. It shall conform to IS: 158.

It shall be a heavy duty bituminous paint, which shall not impart any odour or taste to water, carried in the steel water pipelines, tanks and pen-stocks. It shall be applied on the inside surface of the water pipe line, tanks and pen- stocks. It shall be resistant to mild acids, alkalis and shall withstand heat upto

 $150\,^{\circ}$ C. It shall render a heavy body protective film. If zinc-rich, epoxyprimer shall be used, better results of pipekote shall be obtained.

#### M-81D Silver Shield:

It shall be from STP Limited or equivalent, as approved by the Engineer.

It shall be a bituminous aluminum-finish paint formulated for application over anti-corrosive paints. It shall have a covering capacity of  $10 \text{ m}^2/\text{lit.}$ .

#### M-81E Shalimastic HD:

It shall be from STP Limited or equivalent, as approved by the Engineer. It shall comply with the US Dept. of interior bureau of reclamation specification CA- 50.

It shall be a viscous, heavy-duty, anti-corrosive waterproof coal tar paint. It shall offer resistance to acids and alkalis. It shall be used for protection of all types of iron and steel structures.

#### M-82 Galvanized Iron Pipe:

Galvanised iron pipe shall be of the medium type and of required diameter and shall comply with IS 1239-1975. The specified diameter of the pipes shall referto all inside diameter of the bore, clamps, screw and all galvanised iron fittings shall be of standard 'R' or equivalent make as approved by the Engineer.

# M-83 Acoustical Wall & Ceiling material:-

#### M-83a Glass wool:-

- I. Glass wool shall be conform as per relevant I.S. standard & specification.
- II. Density, & thickness shall be used as per specified in item specification.
- III. It shall be pure without dust & any foreign matter and shall be uniform in color, density & weight.

## M-83b Aluminum foil or percolated sheet:-

- I. Aluminum alloy used in the manufacture of extruded & sheet or section shall conform to I.S. designation HEA-WP of I.S. 733- 1975 and also to I.S. designation WVG-WP of I.S. 1285- 1975. & it shall be specified in the item specification. The fabrication shall be done as directed.
- II. Aluminum shall be conform to I.S.733-1825, & relevant I.S. standard & specification.
- III. Density, Grade & thickness shall be used as per specified in item specification.

#### M-83c Wood wool board :-

- I. Acoustical Insulation shall be conforming to I.S. 8225-1987, and equivalent to ISO: 354 & ASTM. 423-90 A.
- II. Thermal insulation shall be conform to B.S.: 874 1965.
- III. Board shall be fire resistant conform to B.S. 476- part-5 Class-P, part-6 I-4.11, Part-7 Class-1, & size, thickness and other special requirement shall be as per specified in item specification.

# M-83d Acoustical Board & Gypsum board

| Humidity resistant  | 99 % RH.                       |
|---|--------------------------------|
| Material fire performance   | Class- 0/ Class-1 ( B.S. 476 ) |
| Sound Absorption (NRC.)   | 0.50                           |
| Frequency Hz  | 125 – 4000                     |
| Sound insulation  | 40dB.                          |
| CAC.  | 90%                            |
| Light reflection.   | >85%                           |
| Thermal resistant.  | R=0.28 m <sup>2</sup> k/W      |
| Weight / Piece (600mm X 600mm.<br>X 15mm. thick board without<br>Grid.) | 2.35 Kg.                       |

| Surface finish    | Crisp subtly textured matt appearance with visible perforation finished with vinyl emulsion paint |
|-------------------|---|
| Material          | Hydro synthesized Bio soluble long fiber with purified starch as binder.                          |
| Bending strength  | ≥ 250N ( JIS A 6301 )   |
| Sagging resistant | <u>&lt;</u> 5/1000.   |

# **Testing Method**

| Fire Propagation Test | Class - 0                    | B.S. 476 PART- 6                |
|-----------------------|------------------------------|---------------------------------|
|                       | Class 1 (0-25)               | ASTM - E84                      |
| Flame spread          | Class-A                      | U.S. Federal Spec.<br>SSS-118-b |
| ,                     | 20                           | Underwriters Laboratories Inc.  |
|                       | Class-1                      | BS. 476 Part-7                  |
| Thermal conductivity  | 0.045 Kcal/mh <sup>0</sup> C | JIS A 1412                      |
| Light reflectance     | LR-1 (Over 80%)              | ASTM. C 523                     |
| NRC                   | 0.55-0.70                    | ASTM. C 423                     |
| CAC                   | 36                           | ASTM. E 413                     |

I. Size, thickness and other special requirement shall be specified in the item specification. The fabrication shall be done as directed.

**Signature of Contractor** 

#### **DETAILED TECHNICAL SPECIFICATIONS**

#### Item No.1:

Painting two coats (including priming coat) on new steel and other metal surfaces with enamel paint, brushing, interior to give an even shade including cleaning the surface of all dirt, dust and other foreign matter.

#### 1.0. Materials:

**1.1.** The ready mixed paint, brushing, wood primer pink shall confirm to I. S. 3536-1966 (Latest edition).

# 2.0. Workmanship:

- **2.1.** Preparation of Surfaces :
- 2.2.1. All wood work shall be dry and free from any foreign matter incidental to building operations. Nails shall be punched well below the surface to provide a firm key for stopping. Mouldings shall be carefully smoothened with abrasive paper and projecting fibres shall be removed. Flat portion shall be smoothened off with abrasive paper used across the grain prior to staining and with the grain prior to staining or if the wood isto be left in its natural colour, wood work which is to be stained may be smoothened to scraping instead of by glass papering if so required.
- 2.2.2. Any knots, resinous or stricaks or blueish sap wood that are not large enough to justify cutting out shall be treated with two coats of pure shellac knotting applied thinly and extended about 25 mm. beyond the actual area requiring treatment.
- 2.2.3. Application of primer:
- 2.1.1. The relevant specifications of item No. 19.12 (A) shall be followed for application of primer.
- 1.0. Materials: The enamel paint shall confirm to M-44 B.

# 2.0 Workmanship:

- **2.1.** General:
- 2.1.1. The materials required for work of painting work shall be obtained directly from approved manufacturers or approved dealer and brought to the site in maker's drums, kegs etc. with seal unbroken.
- 2 1.2. All materials not in actual use, shall be kept properly protected, lids of containers shall be kept closed and surface of paint in open or partially open containers covered with a thin layer of turpentine to prevent formation of skin. The materials which have become stale or flat due to improper and long storage shall not be used. The paint shall be stirred thoroughly in its container before pouring into small containers. While applying also the paint shall be continuously stirred in smaller container. No left over paint shall be put back into stock tins. When not in use, the containers shall be kept properly closed.
- 2.1.3. If for any seasons, thinning is necessary, the brand of thinner recommended by the manufacturer shall be used.
- 2.1.4. The surface to be painted shall be thoroughly cleaned am.' dusted. All rust, dirt and grease shall be thoroughly removed before painting is started. No painting on exterior or other exposed parts of the work shall be carried out in wet, damp or otherwise unfavorable weather and all

the surfaces shall be thoroughly dry before painting work is started.

#### 2.2. Application:

- 2.2.1. Brushing operations arc to be adjusted to the spreading capacity advised by the manufacture of particular paint. The paint shall be applied evenly and smoothly by means of crossing and laying off. The crossing and laying off consists of covering the area over with paint, brushing the surface hard for the first lime over and then brushing alternately in opposite directions two or three times and then finally brushing lightly in direction at right angles to the same. In this process, no brush marks shall be left after the laying off is finished. The full process of crossing and laying off will constitute one coat.
- 2.2.2. Each coat shall be allowed to dry completely and lightly rubbed with very fine grade of sand paper and loose particles brushed off before next coat is applied. Each coat shall vary slightly in shade and shall be got approved from Engineer-incharge before next coat is started.
- 2.2.3. Each coat except the last cost shall be lightly rubbed down with sand paper of fine pumice stone and cleaned of dust before the next coat is applied. No hair marks from the brush or clogging of paint puddles in the corners of panels angles of mouldings etc. shall be left on the work.
- 2.2.4. Special care shall be taken while painting over bolts, nuts, rivets, overlaps etc. Approved best quality brushes shall be used.

# 3.0. Mode of measurements & payment:

**3.1.** The relevant specifications of item shall be followed for mode of measurements and payment. The rate is excluding priming coat.

The rate shall be for a unit of one sq. meter.

#### Item No. 2:

20 mm. thick sand face cement plaster on walls and RCC structure up to height of 10 mt. and above ground level consisting of 12 mm thick backing coating of C.M. 1:3 (1 cement : 3 sand) and 8 mm thick finishing coat in C.M. 1:2 (1 cement: 2 sand) etc. complete

#### Material:

Water shall conform to M-1. Cement Mortar shall conform to M-11

#### **Workmanship:**

The work shall be carried out in the coats. The backing coat (base coat) shall be12 mm thick in C.M. 1:3. The relevant specification is below:

# **Scaffolding:**

Wooden bullies, bamboos, planks, treatles and other scaffolding shall be sound. These shall be proper examined before erection and use. Stage scaffolding shall be provided for ceiling plaster which shall be independent of the walls.

## **Preparation of background:**

The surface shall be cleaned of all dust, loose mortar, droppings, traces of algar, efflorescence and other foreign matter by water or by brushing if it is not hard and by hacking if it is hard. In case of concrete surface, if a chemical retarder has been applied to the form work, the shall be roughed by wire brushing and allthe resulting dust and loose particle cleared off and care shall be taken that noneof the retarders is left on the surface. Trimming of projections on brick / concrete surfaces where

necessary shall be carried out to get on even surface. Raking of joints in case of masonry where necessary shall be allowed to dry out for sufficient period before carrying out the plaster work.

The work shall not be soaked but only damped evenly before applying the plaster. If the surface becomes dry, such are shall be moistened again.

For external plaster, the plastering operation shall be started from top floor and carried downwards for internal plaster, the plastering operations may be started whenever the building frame and cladding work are ready and the temporary supports of the ceilings on the wall of the floor have been removed. Ceiling plaster shall be completed before starting plaster to walls.

The plaster about 15 x 15 cms shall be first applied horizontally and vertically atnot more than 2 meters intervals over the entire surface to serve as gauge. The surfaces of these gauges shall be truly in plane of the finished plastered surface the mortar shall than be applied in uniform surface slightly more than the specified thickness, then brought to a true surface by marking a wooden straightedge reaching across the gauges with small upward and sideways movements at a time finally the surface shall be finished off true with a trowel or wooden floataccording as a smooth or a sandy granular texture is required. Excessive troweling or over working the float shall be avoided. All corners, arises angles and junctions shall be truly vertical or horizontal as the case may be and shall be carefully finished. Rounding or chamfering corners, arises junctions etc. shall becarried out with proper templates to the size required.

Cement plaster shall be used half an hour after addition of water, and mortar or plaster which is partially set shall be rejected and removed forthwith from the site.

In suspending the work at the end of the day, the plaster shall be left out clean to the line both horizontally and vertically. When recommencing the plaster, the edges of the old work shall be scrapped clean and wetted with cement putty before plaster is applied to the adjacent areas to enable the two to properly jointogether. Plastering work shall be closed at the end of the day on the body of features such as plaster bonds and cornices nor at the corners or arises. Horizontal joints in plaster work shall not also occur on parapet tops and copings as these invariably lead to leakage. No portion of the surface shall be left out initially be packed up later on the outside of the plaster and keeping them wet.

The thickness of back coat shall be 12 mm average. Before the first coat hardensits surface shall be beaten up by edges of wooden tapers and close dents shall be made on the surface. The subsequent coat shall be applied after this coat hasbeen allowed to set for 3 to 5 days depending upon the weather conditions. The surface shall not be allowed to dry during this period.

the second coat be started over right after finishing of plaster. The plaster shall be kept wet for a period of 7 days. During this period, it shall be protected from all damages.

#### **Mode of measurements & Payments:**

The rate shall include the cost of all materials labour and scaffolding etc. involved in the operations described under workmanship.

All plaster shall be measured in square meter unless otherwise specified length, breadth or height shall be measured correct to a centimeter.

Thickness of the plaster shall be exclusive of the thickness of the key i.e. grooves or open joints in brick work, stone work etc. or space between laths. Thickness of plaster shall be average thickness with minimum 10 mm at any point on this surface.

This item includes plastering upto floor two level.

The measurement of wall plastering shall be taken between the walls or partition (dimensions before plastering being taken) for length and from the top of floor or skirting to ceiling for height, depth of cover of cornices, if any, shall be deducted.

Soffits of stairs shall be measured as plastering on ceilings. Elowigns soffits shall be measured separately.

For jambs, soffits, sides, etc. for openings not exceeding 0.5 sq.mt. each in area for ends of joints, beams, posts girders, steps etc. not exceeding 0.5 sq.mt. each in area and for openings exceeding 0.5 sq.mt. and not exceeding 3.00 sq.mt. in each area deductions and additions shall be made in the following manner:

- a) No deductions shall be made for ends of joints, beams, posts etc. and openings not exceeding 0.5 sq.mt. each and no addition shall be made for reverse, jambs, soffits, side etc. of these openings, for finish to plaster around ends of joints, beams, posts etc.
- b) Deductions for openings exceeding 0.5 sq.mt. but not exceeding 3.00 sq.mt. each shall be made as following and no addition shall be made for reverse, joints, soffits, sides, etc. of these openings.
  - i) When both faces of all walls are plastered with same plaster. Deductions shall be made for one face only.

ii)

- For openings having door squares equal to or projecting beyond the thickness of wall. Full deduction for opening shall be made from each plastered face of the wall.
- In case of openings of area above 3 dq.mt. each deduction shall be made for opening but Jambs, soffits and slits shall be measured.
- The rate shall be for a unit of square meter.

#### Item No.3:

## <u>Cement Plaster With Neeru + Cement Finish</u>

#### Material:

Water shall confirm to M-1. Cement Mortar shall confirm to M-11

#### **Workmanship:**

12 mm thick cement plaster in single coat in CM 1:3 (1-cement : 3-sand) witha floating coat of neat cement slurry.

## Scaffolding:

Wooden bullies, bamboos, planks, treatles and other scaffolding shall be sound. These shall be proper examined before erection and use. Stage scaffolding shall be provided for ceiling plaster which shall be independent of the walls.

This kind of Plaster is normally for interior side or as specified location by Consultant to be applied as above. NORMAL CEMENT PLASTER and the surface shall be rubbed smooth after coating it with a thick coat of pure Portland cement slurry while the base coat is still fresh. If Neeru plus cement finish is specified floating with neat cement will not be required.

#### **Mode of Measurement & Payment:**

The rate shall include the cost of all materials labour and scaffolding etc. involved in the operations described under workmanship.

All plaster shall be measured in square meter unless otherwise specified length,

breadth or height shall be measured correct to a centimeter.

Thickness of the plaster shall be exclusive of the thickness of the key i.e. grooves or open joints in brick work, stone work etc. or space between laths. Thickness of plaster shall be average thickness with minimum 10 mm at any point on this surface.

This item includes plastering up to floor two level.

The measurement of wall plastering shall be taken between the walls or partition (dimensions before plastering being taken) for length and from the top of floor or skirting to ceiling for height, depth of cover of cornices, if any, shall be deducted.

Soffits of stairs shall be measured as plastering on ceilings. Elowigns soffits shall be measured separately.

For jambs, soffits, sides, etc. for openings not exceeding 0.5 sq.mt. each in area for ends of joints, beams, posts girders, steps etc. not exceeding 0.5 sq.mt. each in area and for openings exceeding 0.5 sq.mt. and not exceeding 3.00 sq.mt. in each area deductions and additions shall be made in the following manner:

- a) No deductions shall be made for ends of joints, beams, posts etc. and openings not exceeding 0.5 sq.mt. each and no addition shall be made for reverse, jambs, soffits, side etc. of these openings, for finish to plaster around ends of joints, beams, posts etc.
- b) Deductions for openings exceeding 0.5 sq.mt. but not exceeding 3.00 sq.mt. each shall be made as following and no addition shall be made for reverse, joints, soffits, sides, etc. of these openings.
  - i) When both faces of all walls are plastered with same plaster. Deductions shall be made for one face only.

ii)

- ✓ For openings having door squares equal to or projecting beyond the thickness of wall. Full deduction for opening shall be made from each plastered face of the wall.
- ✓ In case of openings of area above 3 dq.mt. each deduction shall be made for opening but Jambs, soffits and slits shall be measured.

The rate shall be for a unit of square meter.

#### Item No.4:

# Plastic Emulsion paint (two coats) (Asian Paint, ICI, Dulux, Nerolac, Berger, etc. of approved type (with prime coat):

## **Materials:**

The enamel paint shall satisfy in general requirements in specifications of oil paints. Enamel paint shall confirm to I S Latest edition.

# Workmanship:

The materials required for work of painting work shall be obtained directly from approved manufacturer or approved dealer and brought to the site in maker's drum, bags etc. with seal unbroken.

All materials not in actual use shall be kept properly protected, lids of containers shall be kept closed and surface of paint in open or partially open containers covered with a thin layer of turpentine to prevent formation of skin. The materials which have become state or flat due to improper and long storage shall not be used. The paint shall be stirred thoroughly in its container before pouring into small containers. While applying also, the paint shall be continuously stirred in smaller container. No left over paint shall be

put back into store tins. When not in use, the containers shall be kept properly closed.

If for any reasons, thinning is necessary, the brand of thinner recommended by the manufacturer shall be used.

The surface to be painted shall be thoroughly cleaned and dusted. All rust, dirt and grease shall be thoroughly removed before painting is started. No painting on exterior or other exposed parts of the work shall be carried out in wet, damp or otherwise unfavourable weather and all the surfaces shall be thoroughly dry before painting work is started.

# **Application of paint:**

Brushing operations are to be adjusted to the spreading capacity advised by the manufacturer of particular paint. The paint shall be applied evenly and smoothly by means of crossing and laying off. the crossing and laying of consists of covering the area over with paint, brushing the surface hard for the first time over and then brushing alternately in opposite directions two or three times and then finally brushing lightly in a direction at right angels to the same. In this process, no brush marks shall be left after the laying off is finished. The full process of crossing and laying of will constitute one coat.

Each coat shall be allowed to dry completely and lightly rubbed with very fine grade of san paper and loose particles brushed off before next coat is applied. Each coat shall vary slightly in shade and shall be got approved from the engineer-in-charge before next coat is started.

Each coat except the last coat shall be lightly rubbed down with sand paper of fine pumice stone and cleared of dust before the next coat is applied. No hair marks from the brush or clogging of paint puddles in the corners of panels, angles of moulding etc. shall be left on the work.

Special care shall be taken while painting over bolts, nuts, rivets, overlaps etc. Approved best quality brushes shall be used.

#### Mode of measurement and payment:

The new steel and other metal surface shall be measured under this item. All the work shall be measured net in the decimal system as executed subject to the following limits unless otherwise stated hereinafter.

- a) Dimensions shall be measured to the nearest 0.01 meter.
- b) Areas shall be worked out to the nearest 0.01 meter.

No deductions shall be made for openings not exceeding 0.5 sq.m. each and no addition shall be made for painting to beddings, moulding, edges, jambs, soffits, sills etc of such opening.

In case of fabricated structural steel and iron work, priming coat of paint shall be included with fabrication. In case of trusses, if measured is sq.m compound griders, stanchions, lattices, girder and similar work, actual are shall be measured and no extra shall be paid for painting on bolts heads, nuts, washers etc. No addition shall be made to the weight calculated for the

purpose of measurements of steel and iron works for paint applied on shop or at site.

The different surfaces shall be grouped into one general item, areas of uneven surfaces being converted into equivalent plain areas in accordance with the table given as per Annexure-II for payment.

The rate is including priming coat.

The rate shall be for a unit of one square meter.

#### Item No.5:

# Apex Color work on Outer side of Wall (Two coats) (with Base Coat) FINISHES

#### **EXTENT AND INTENT**

The Contractor shall supply all materials, labour, tools, ladders, scaffolding and other equipment necessary for the completion and protection of all painting / finishing work. Painting & finishing, as herein specified shall be applied to all surfaces requiring painting / finishing throughout the interior and exterior of the buildings as given in the schedule of finishes or elsewhere. The painting / finishing shall be carried out by a specialist workers, approved by the Engineer-in-charge of RMC for this work.

#### **STORAGE**

Storage of materials to be used on the job shall be, only in a single place approved by the Engineer-in-charge of RMC for this work. Such storage place shall not be located within any of the buildings included in the contract.

#### **MATERIALS**

Materials used in the work shall be of manufacture approved by the Engineer-incharge of RMC for this work, Ready mixed paints, varnishes, enamels, lacquers, stains, paste fillers, distempers and other materials mustbe delivered to the job site in the original containers, with the seals unbroken and labels intact. Each container shall give the manufacturer's name, type of paint, color of paint and instructions of reducing. Thinning shall be done only in accordance with directions & manufacturer's specification. Remove rejected materials immediately from the premises.

#### **SHADES**

All shades, as provided in the shade schedule, shall be approved by the Engineer- in-charge of RMC for this work. The Contractor shall as far as possible use pre- mixed manufacturer's shades and shall prepare sample of the shades selected and submit same for approval by the Engineer-in-chargeof RMC for this work. No work is to proceed until the Engineer-in-charge of RMC for this work has given his approval, preferably in writing, of the shadesamples.

#### **COMMENCEMENT OF WORK**

Painting / finishing shall not be started until the surfaces to be painted / finished are in a condition fit to receive painting / finishing and so certified by the Engineer-in-charge of RMC for this work.

Painting / finishing work shall be taken in hand only after all other civil work is completed.

Buildings where painting / finishing work is to commenced shall be thoroughly swept and cleaned up before commencement of painting /finishing.

#### **SCAFFOLDING**

Only double scaffolding having two sets of vertical supports shall be provided for all, painting / finishing work. The supports shall be tied together with horizontal pieces over which the scaffolding planks shall be fixed.

All the vertical and horizontal members of the scaffolding shall be placed sufficiently away from the surfaces to be painted to ensure proper and unit

erupted application.

#### WORKMANSHIP

The workmanship shall be of the very best; all materials evenly spread and smoothly flowed as without running sags, using good quality tools, brushes, etc., as required. Only skilled painters / applicators shall be employed. A properly qualified foreman shall be constantly on the job whilst the work is proceeding. All surfaces to be painted / finished shall be cleaned free of all loose dirt and dust before painting / finishing is started. AII work where a coat of material has been applied must be inspected and approved before application of the succeeding specified coat. Each undercoat shall be distinctshade of the approved color.

Before painting / finishing, remove hardware, accessories, plates and similar items or provide portion to all such items. Upon completion of each space, replace all fixtures removed. Remove doors if necessary to paint bottom edge. Use only skilled mechanics for the removal and replacement of above items.

#### CONCEALED SURFACES

All interior and exterior trim, door frames, doors, shelving, cabinet work shall be thoroughly and carefully back painted as all surfaces and edges which will be concealed when installed. Such surfaces shall be clean, dry, sanded and properly prepared to receive the paint. Tops, bottom and edges of doors shall be finished same as the rest of the door.

#### **PROTECT AND CLEAN**

The agency shall protect not only his own work at all times, but shall also protect all adjacent work and materials by suitable covering during progressof his work. Upon completion of his work, he shall remove all paint and varnish spots from floors, glass and other surfaces. Any defaced surfaces shall be cleaned and the original finish restored. He shall remove from the premises all rubbish and accumulated material and shall leave the work in clean, orderly and acceptable conditions.

#### PREPARATION OF SURFACES

<u>PLASTER WORK</u>: Fill all holes, cracks and abrasions with plaster of parish / cement slurry as directed, properly prepared and applied and smoothed off to match adjoining surfaces. Do not use sand paper on plaster surfaces. Plaster shall be allowed to dry for at least 12 (twelve) weeks before the application of paint / finishes.

STEEL AND IRON: All surfaces shall be washed with mineral spirits to removeany dirt or grease before applying paint. Where rust or scale is present, it shall be wire brushed and sand papered clean. All cleaned surfaces shall be given one coat of approved phosphate before prime coat in accordance with the manufacturers, Instructions. Shop coats of paint that have become marred shall be cleaned off, wire brushed, and spot primed over the affectedareas.

#### **APPLICATION**

The paint shall be continuously stirred in the container so that its consistency is kept uniform throughout.

The painting / finishing shall be laid on evenly and smoothly by means of crossing and laying off, the latter in the direction of the grain of the wood. The crossing and laying off consists of covering the area with paint, brushing the surface hard for the first time and then brushing alternatively in opposite directions, two or three times and then finally brushing lightly in a direction at right angles to the same. In this process no brush marks shall be left after the laying off is finished. The full process of crossing and laying off will constitute one coat.

Where so stipulated, the painting / finishing shall be carried out using spray machines suited for the nature and location of the work to be carried out. Only skilled and experienced workmen shall be employed for this class of work. Paints used shall be brought to the requisite consistency by adding a suitable thinner. Spraying shall be carried out only in dry conditions. No exterior painting / finishing shall be done in damp foggy or rainy weather.

Surface to be painted shall be clean, dry, smooth and adequately protected from dampness. Each coat shall be applied in sufficient quantity to obtain complete coverage, shall be well brushed and evenly worked out over the entire surface and into all corners, angles and crevices allowed to thoroughly dry. Second coat shall be of suitable shade to match final color, and shall be approved by the Engineer-in-charge of RMC for this work before final coat isstarted. Allow at least 48 hours drying time between coats for interior and 7days for exterior work, and if in the judgment of the Engineer-in-charge of RMC for this work more time is requested it shall be allowed. Finished surfaces shall be protected from dampness and dust until completely dry. Finished work shall be uniform of approved color, smooth and free from runs, sags, defective brushing and clogging. Make edges of paints adjoining materials of colors sharp and clean, without overlapping.

In order to achieve a superior finished surface, putty paste fillers shall be used on, all surfaces to be painted. To fill pores, dents, etc. The putty / paste fillers shall be approved quality and manufacture and shall be applied to the surface with a knife or other sharp edged tools after the priming coat as well as after each undercoat. The surface, after filling with putty / paste tiller, shall be rubbed down with fine sand paper and dusted off before the application of the subsequent coat.

Paste wood filler when set shall be wiped across the grains of the wood and then with the grain to secure a clean surface. Surface to be stained shall be covered with uniform coat of stain wiped off if required.

FINISH: The painted surfaces shall be finished to require texture. Matt finishshall be achieved by use of sponge rollers or stippling brushes as called for.

The rate shall be paid for a unit of one square meter basis.

### Item No.6:

# Painting of Traffic Strip Foothpath / Circle & divider block size $0.38 \times 0.30 \times 0.30$ in two coats using enamle paint in different colors

In this work the color work to road divider blocks except flooring including top the portion outside the road (from ground) is to be carried out with the oil paintof approved quality. The shade of various colors shall be used as approved by the engineer-in-charge. The work is to be carried out as per the instructions of engineer-in-charge.

For this color work, first of all primer is to be applied to old road divider blocks thereafter one coat is to be applied for whole work and shall have to be got checked from the engineer-in-charge and thereafter only the second coat is to be applied. The liquid between the two colors shall be done with due care and in line level.

The rate for this work shall be for running meter basis.

# Item No. 7: making of wall pictures in different wards

For making of wall pictures in different shades agency have to consult architect with minimum 5 years internal/mural/art in wall paint experience and RMC not bound for extra payment.

In Diff. wall painting agency have submitted diff mural art or any other concept and put to RMC for prior permission.

The rate for this work will be paid per square meter basis.

Addl/Asst. Engineer R.M.C.

R.M.C.

Dy.Ex.Engineer CITY ENGINEER (I/C) R.M.C.

Signature of Contractor with Seal

|     |  | LISTOFAPPRO   | OVED MAKE(CivilWork)   |   |                |
|-----|--|---|--|---|----------------|
| NO. | SPACE  | PARTICULAR  |  | COMP  |                |
| 1   | Ready mixed Concrete   |   | Lafarge/Bhanu/ultra tech/RJ/Krishna  |   |                |
| 2   | Ordinary Portland Cement<br>(Minimum 53 Grade)   |   | UltraTech /Birla/ ACC /Ambuja/Hathi/Sanghi   |   |                |
| 3   | Flush doors  |   | BIS approved brand (IS   | 51 Mark)  |                |
| 4   | FRP Doors  |   | Fibrevent, Techno skill<br>Engineer Incharge)  | ls or Equivalent (or as app                             | roved by       |
| 5   | PVC Doors with Frame   |   | ISI and approved by E  | ngineer Incharge  |                |
| 6   | Hydraulic floor Spring/ Door   |   | Everite, Garnish, Hard   |   |                |
| 7   | White Cement   |   | JK White   | Birla white   | Nihon<br>White |
| 8   | Reinforcement/Structural<br>Steel (Each LOT shall<br>accompany manufacturer's<br>Test Certificate) |   | (TMT BARS Fe-500) Gallent/ET/ASR/Friend or BIS approved manufacturers                        |   |                |
| 9   | Dining, Drawing, Bed Room,<br>Kitchen, Toilet/Bath/Wash<br>etc,                                    | Vitrified/ Ceramic /Glaze Tiles/Wall Tiles/ Parking Floor Tiles | Somani/Nitco/Kajaria/<br>Euro/Vermora  | RAK/Jhonson/Simpolo/Bel                                 | I/Asian/       |
| 10  | Toilet/Bath/Wash   | PVC/UPVC<br>pipes &<br>Fittings                                 |  | e/finolex /Simco/Plumber<br>e of outer side of Building |                |
| 11  |  | Sanitary<br>ware  | Jaquar/cera/Hindware/Jhonson and any other standard brandh as approved by engineer-in-charge |   |                |
| 12  | Teak Wood  |   | Bulsar   | C.P.Teak  |                |
| 13  | Inter locking Paver blocks   |   | ISI Mark – Balaji,Rege   | ncy,Supreme   | 1              |
| 14  | Plywood Products Commercial Block Board Commercial PlyTeak Ply                                     |   | ISI Mark as approved b   | by engineer-in-charge                                   |                |
| 15  | Glass/Float/Sheet  |   | Saint Gobain   | Modi/HNG  | Asahi          |
| 16  |  | Laminates   | Neolux/Formica/Sunm  | nica/Merino or as per IS                                |                |
| 17  | Aluminum sections  |   | Jindal   | Indal   | Banco          |

A) The contractor shall produce samples of the materials for approval of the RMC/PMC. The materials of the makes out of the above as approved by the RMC/PMC shall be used on the work. RMC/PMC member has not bide to give any reason for rejection of any brand from the above list and its decision will be consider as final.

- B) In respect of materials for which approved makes are not specified above, these will be of makes to be decided by the RMC / PMC.
- C) Contractor can use for any material of equivalent make of the above specified company after taking prior permission of RMC/PMC.

The agency has to use item/material mentioned in the list above. In no case other item/material shall be allowed except those mentioned in the list unless and until the unavailability of the above said item/material noticed that too, prior approved of RMC/PMC

| D. | ADDITIONAL CONDITIONS |  |
|----|-----------------------|--|
|    |                       |  |
|    |                       |  |

#### D. ADDITIONAL CONDITIONS:

- 1. The contractor shall have to provide his own level instrument for this work.
- 2. The safety of the traffic and surrounding properties is the prime important factor. As it is the renovation work in existing residential and commercial area the fencing, lighting, covering etc., requires to be provided as per clause 1.1.15. and as per the site requirement. Sign Board shall have to be provided at required locations, so that there will not be any fatal accident.
- 3. In case of any ambiguity found in inspections / drawings, specifications, etc, the decision of engineer-in-charge shall be final and binding to the contractor.
- 4. Rates quoted in Bill of Quantities to cover everything necessary for complete Execution of work :

The rates quoted will be held to cover everything necessary of the due and complete execution of the work according to the drawings and the several conditions and the stipulations of the contract, including specification, or the evident intent and meaning of all or either of them or according to customary usage and for the periodical and final inspection and test and proof of the work in every respect and for measuring, numbering or weighing the same including setting out and laying or fixing in position and the provision of all materials,

Power, tool rammers, beaters, labour, tackle platforms with impervious lapped joints for scaffolding ranging rods, straight edges, centering and boxes, wedges, moulds, templates, post straight rails, boning-staves, measuring rods, page boards, shores, barriers, fencing, lighting, pumping apparatus, temporary arrangements of passage of traffic, access to premises and continuance of drainage, water supply and lighting (if interrupted by the work) lard temporary sheds and buildings nahanis roofed in or otherwise haulage, painting, varnishing, polishing, establishments for efficient supervision and watching arrangements for the efficient protection of life and property and all requisite plant, implements and appliances every kind, except only such matter and things as it may be distinctly stated here in are to be supplied by the contractors. A rate for anyone description of work is to be held to include such items of other classes of and for these on separate specific charge will be admitted. The contractors shall keep every portion of the work clear of accumulation from time to time and shall leave every portion of the work clean, clear, perfect and at the

- conclusion of whole, providing at their own cost all such material implement appliances and labour as the Engineer may require to prove if it is to be so.
- 5. The contractors are particularly directed to observe from the Articles of Agreement and the specifications, what is to be included in their rates for the several portions of the work and also under what conditions payments are to be made.
- 6. The contractor shall have to avail P F Code as per the prevailing Circular of Government for the employees on work. The process for preparation of bill will be taken up only after submission of the Challan for the amount of P.F. deposited every month for the employees on work, which will binding to the contractor. The required documents shall have to be submitted every month by the contractor to the competent authority.
- 7. The contractor shall have to get registered under ESI (Employer's State Insurance) Act and obtain ESI Registration number if the number of workers are 10 Nos. or more. Also, the agency shall have to give all the benefits to the workers as available under the ESI Act. The agency should follow all the rules and regulations of ESI Act as per prevailing norms.
- 8. This office Circular bearing No.RMC/C/329 dated 22-12-2012 and Order No.RMC/C/132 dated 10-06-2013 are uploaded separately as a part of tender document. The Contractors/Consultants quoting their rates shall have to read, implement, and submit the same duly signed along with the documents to be submitted during physical submission.
- 9. In reference to the above Circular and Order cited para above, the Contractors/Consultant who have quoted their rates for this work will be called in person for verification of original documents. The date and time for verification of original documents will be as prescribed in the tender document.
- 10. After issuance of work order for this tender, if the work falls under any kind of dispute then Rajkot Municipal Corporation reserves the right to terminate the contract for this work awarded to the contractor or execute part work. The decision of Rajkot Municipal Corporation in this regard will be final and binding to the contractor.
- 11. Till the Completion Certificate is issued by Rajkot Municipal Corporation, the agency will be the sole responsible for security of material and structure at site.

- 12. The quantities given in the Schedules are provisional. The Rajkot Municipal Corporation reserves the right to increase or decrease the quantity of work or totally omit any item work and the contractor shall not be entitled to claim any extras or damages on these grounds & he is bound to execute the work as per the instruction of the Engineer-in-charge. Rajkot Municipal Corporation will not entertain any dispute in this regard.
- 13. It is further clarified that Performance Guarantee (SD) for extra work will also be recovered @ 10% from the bill of extra work i.e. works beyond tender amount.
- 14. The bidder must understand clearly that the prices quoted are for the totally works or the part of the total works quoted for and include all costs due to materials, labour, equipments, supervision, other services, royalties, taxes, duties, etc., and to include all extra to cover the cost. No claim for additional payment beyond the prices quoted will be entertained and the bidder will not be entitled subsequently to make any claim on any ground.
- 15. Qualified engineer must be deployed on site and at Plant. The details of qualified engineers are to be given to RMC at the time of bidding of this tender.
- 16. If any irregularities found during the work then penalty will be imposed by Engineer-in-charge or any higher officer. If any disputes arises regarding penalty imposed by Engineer-in-charge then decision of Municipal Commissioner will be final and binding to agency.
- 17. The time limit will remain same as mentioned in the tender document and the work is to be completed accordingly.
- 18. Tender of such Contractor not having registration in appropriate Class and Category, will be treated as non-responsive. In case of any conflicting provisions between registration of appropriate category and Pre-qualification criteria, the later shall govern the process of bid evaluation.
- 19. The agency shall have to quote their rates only after visiting the site and looking to the site conditions.
- 20. DEFECTS: Date of completion for start of defect liability period for the entire work will be considered as the last date mentioned in the completion of work recorded in Measurement Book. The contractor shall be required to make good all the damages/ defects identified and conveyed to him, during the entire defect liability period. The

method and time limit of rectification will be decided by the Engineer in charge. If the contractor fails to carry out rectification as per the instructions, the same will be carried out at his cost and the cost will be recovered from the amount retained.

- 21. Joint venture shall not be allowed under this tender.
- 22. After the completion of work, at the interval of every three months, joint inspection must be done by the agency and RMC staff and then agency has to submit the report stating the condition of work to Rajkot Municipal Corporation. The final checking report stating the condition of work is also to be submitted by the agency before one month of the expiry of defect liability period to the competent authority.
- 23. The Royalty of each and every material, required to be paid is to be borne by the contractor.
- 24. Testing of each material as and when required by Rajkot Municipal Corporation, is to be carried out in Government approved laboratory by the contractor at his own cost. Schedule of testing of material will be as per R&B, State Government Manual and I S Code provision.
- 25. Necessary tests for material quality, soil tests etc. shall be carried out as per the instructions of engineer-in-charge by contractor at his own cost and reports to be submitted to the engineer-in-charge.
- 26. As this work is to be done in existing structure and also keeping in mind surrounding properties, all due precautions should be taken so that no damage occurs to any of the services like; water connection, drainage connection, water pipeline, drainage line or any other services. However, if any damage occurs to any of such service(s) then the contractor shall have to carry out necessary repairs immediately and satisfactorily, at his own cost.
- 27. Wherever the rolling with the road roller is not possible on metalling work and murrum work, the compaction with hand roller or by any other means at such places shall have to be carried out by the contractor satisfactorily as per instructions of engineer-in-charge.
- 28. The Contractor shall carry out modifications in the procedure of work, if found necessary, as directed by the Engineer during inspection. Works falling short of quality shall be rectified / redone by the Contractor at his own cost, and defective work shall also be removed from the site of works by the Contractor at his own cost.

- 29. Defective Materials: All materials which the Engineer / his representative has determined as not confirming to the requirements of the Contract shall be rejected whether in place or not; they shall be removed immediately from the site as directed. Materials, which have been subsequently corrected, shall not be used in the work unless approval is accorded in writing by the Engineer. Upon failure of the Contractor to comply with any order of the Engineer / his representative given under this clause, the Engineer-in-charge shall have authority to cause the removal of rejected material and to deduct the removal cost thereof from any payments due to the contractor.
- 30. The Defect Liability period for this work is 12 Months. After completion of work, a report at the interval of every six months by way of joint inspection shall have to be submitted to the competent authority. The portion which is observed defective / damaged by normal cause during the joint inspection shall have to be repaired/rectified and necessary evidence along with photographs shall also have to be submitted to the competent authority.
- 31. The agency shall have to get interior done from the approved Architect / Engineer and also to get approved from engineer-in-charge. The agency shall have to get the approval within a period of 7 (Seevn) days.
- 32. The Plans got prepared by the agency shall have to be get the design done from the Structural Engineer, the cost of which also is to be borne by the agency.
- 33. The work order will be given only after getting the preliminary approval from Town Planning Department.
- 34. Providing and fixing of precast RCC slab and column shall have to be carried out in line and level.
- 35. For excavation of trench, use of JCB machine will not be permitted directly on the top surface of the road. After excavation up to minimum 1.00 mt. depth from road surface or existing ground level, same shall have to be carried out manually or by using Breaker and after locating underground services like; water supply pipeline, water connection lines, pipe gutters, telephone cables, electric cables etc., and thereafter upon taking the prior approval of the Engineer-In-Charge, the excavation can be carried out by using JCB machine.
- 36. Rajkot Municipal Corporation shall recommend to the competent authority to give Controlled Blasting License to the contractor for

carrying out excavation in hard rock. In case of blasting license not permissible from the competent authority in some places then excavation is to be done by using wedges and hammers, chiseling, breakers, pneumatic tools, etc. Also in case where blasting license is permitted but even then if there is no possibility of carrying out the blasting for whatsoever reason, the excavation is to be done by using Wedges and hammers, chiseling, breakers, pneumatic tools etc. No extra payment shall be made for excavation to be carried out in any of the above mentioned both the situations.

- 37. Excavation in soft rock and hard rock shall have to be carried out only by Chiseling, Breaker (pneumatic tools) etc., as far as possible. If excavation is not possible in terms of above and if excavation is required to be carried out with the help of blasting then the same shall have to be carried out only after taking prior approval and necessary license for blasting from the competent authority.
- 38. In case of excavation not possible manually or by chiseling in certain place(s) as well as if blasting is also not possible due to various reasons i.e. to avoid damage to nearby water pipeline, pipe gutter, telephone cables / Duct, Raw houses / week buildings / narrow street etc., then the excavation by blasting will not be permitted. Under these circumstances, excavation shall have to be carried out only by Breaker (pneumatic tools) as per the instructions of the Engineer-In-Charge. No extra payment will be made for such type of excavation done by using Breaker. The rate for excavation shall be paid as per the rate of related item mentioned in Schedule-B.
- 39. Regarding the width of excavation, as (a) it is difficult to carry out the vertical trench excavation, (b) possibility of sliding the soil, and (c) uneven excavation trench width in case of blasting. In this connection, for every 1.5 mt lift if there is less width up to 5 cm at the bottom then the top width of excavated trench, it shall be considered as per the specified trench width or actual trench width carried out at the ground level by the contractor whichever is less. If excavation is carried out more than the specified width then the payment will be made only for the specified width of excavation.
- 40. After entering into an agreement, the agency shall have to finalize the agency for supply of the material like Precast RCC slab and column and the name of manufacturer / supplier should immediately be informed to Rajkot Municipal Corporation so that Rajkot Municipal Corporation can also expedite the manufacturer / supplier for the material. If necessary, Rajkot Municipal Corporation will visit and inspect the factory. During the inspection, if Rajkot Municipal Corporation is not satisfied then the contractor shall have

- to procure the material from other manufacturer(s).
- 41. During construction activity, proper care must be taken for labor safety and all the provisions of the labor laws must be followed by the contractor.
- 42. The G.A. Drawings and other Drawings as provided at present with the tender document are indicative, however, there is possibility of any change or modification in the said drawing and as such the contractor shall have to carry out the work accordingly at the approved rates without any extra cost.
- 43. The contracting Agency then has to prepare bar bending schedule as per Structural Drawings and submit it to RMC after then RMC shall permit to work to start. Structure design is in the scope of work of contractor and its cost is to be borne by the contractor. The structure designer should be RMC license holder. The proof check of the structure design should be done by one of the structure designers, as suggested by RMC. (If the structure designer is suggested by RMC, then the proof check is not needed.) Bar Bending Schedule, register shall be maintained on site with the details of cut length of bar. The certificate for same shall be denoted in Pour Card.
- 44. Contract Agency has to provide a Site Office Room, a separate Laboratory included with necessary lab instruments for slump test, sieve analysis, etc. whatever suggested by Site Engineer in charge on site premises. There shall be provision of minimum 24 cube mould of 15 x 15 x 15 cm size and 12 mould of 7.5 x 7.5 x 7.5 cm. There shall be a provision of necessary stationary & Furniture. The periodical calibration of instruments like weigh batch Plant, Electronic Balance etc. shall be carried out as per instruction of Engineer in Charge. Without satisfactory report for the same the work may not be continued.
- 45. The Mix Design of Cement Concrete shall be revised submitted with respect to changes in Materials like Cement, Sand, Aggregate
- 46. The Final Completion Drawings shall be submitted in hard copy and as Auto Cad format by Agency. If the same is not submitted, the permanent deposit 0.25 % of Final Bill amount will be deducted from Final bill.
- 47. After the drawings for the proposed work are finalized by RMC, the agency has to submit the same to qualified & experienced structure engineer.
- 48. The agency has to submit the approved & signed copies of structure

- design 3 sets to Rajkot Municipal Corporation
- 49. Additional alternation changes during the work shall has to be incorporated in the structure drawing & shall be re submitted to Rajkot Municipal Corporation accordingly.
- 50. The contracting Agency then has to prepare bar bending schedule, submit it to Rajkot Municipal Corporation. & After checking the bar bending schedule, then Rajkot Municipal Corporation shall permit to work to start.
- 51. Approval to the samples of various materials given by the Engineer-in-charge shall not absolve the contractor from the responsibility of replacing defective material brought on site of materials used in the work found defective at a later date. The contractor shall have no claim to any payment of compensation whatsoever on account of any such materials being rejected by the Engineer-in-charge.
- 52. The agency has to facilitate the Town Planning department in all respective terms and has to provide all the required items as instructed by a surveyor of Town planning Dept. The items which are required for demarcation are colors, Tags, Nails, labors and agency will also be responsible for cleaning of the plot without any extra cost.
- 53. The agency has to create the passage/access to the plot where the work is supposed to start. If in case the access to plot is restricted by any farming land, then the agency has to take a proper arrangement for passage and whatever the cost occurred in the construction of the passage, the agency has to pay the cost of its own.
- 54. The compound wall has to be constructed with the proper guidance by the Engineer- in- charge, such as if the land has difference in the level (irregular topography), then the agency has to construct the compound wall in the step pattern form.
- 55. The top of the precast wall will be either in Semi-circular or triangular whichever instructed by the Engineer-in-charge. The Measurement of the Semi-circular or triangular item of the precast wall will be taken from the middle of the section of the item.
- 56. If in case the Semi-circular or triangular item of the precast wall will not be fixed, then the agency has to keep the top section of precast pole empty, without any curtailment in the height of the pole. But the measurement will be counted only for the constructed slabs.

- 57. In the precast wall, either the cement mortar in the ratio of 1:1 or Standard chemical mortar to be filled in Groove i.e. the area between two precast slabs and the area between the slabs and pole, whichever instructed by the Engineer- in- charge.
- 58. The restoration work for the excavation done is to be carried out immediately as per the instructions of engineer in charge. The excess material shall have to be disposed with no extra cost at the site specified by engineer-in-charge.

The word "Arbitration" or "Arbitration Clause" wherever mentioned in this tender document, is now to be treated as "Deleted". In this context, an Order bearing No.RMC/Legal/1858 dated 18-02-2017 of Legal Department of Rajkot Municipal Corporation is uploaded separately along with this tender, which Order, will hereafter be referred and taken into consideration for Arbitration related purpose for the tenders of Rajkot Municipal Corporation.

CITY ENGINEER
Rajkot Municipal Corporation

Signature of Contractor with Seal

#### **Raikot Municipal Corporation**


#### :: SPECIAL CONDITIONS ::

- 1. The Royalty of each and every material, required to be paid is to be borne by the contractor.
- 2. Testing of each material as and when required by Rajkot Municipal Corporation, is to be carried out by the contractor at his own cost. Schedule of testing of material will be as per R&B, State Government Manual and I S Code provision.
- 3. The whole work shall be executed by qualified Site Engineer. The required L- Section and Cross section is to be prepared by contractor at his own cost. The work should be done by levelling instrument. The Drawings shall be submitted accordingly in advance before starting the work. No extra payment will be made for the above work. Contractor has to submit Bill form with hard copy and soft copy of cross section and L-section of work completed. No bill will be accepted without above drawings.
- 4. Necessary tests for material quality, Paving Blocks, soil tests etc. shall be carried out as per the instructions of engineer-in-charge by contractor at his own cost and reports to be submitted to the engineer-in-charge.
- 5. The contractor shall have to get registered under ESI (Employer's State Insurance) Act and obtain ESI Registration number if the number of workers are 10 Nos. or more. Also, the agency shall have to give all the benefits to the workers as available under the ESI Act. The agency should follow all the rules and regulations of ESI Act as per prevailing norms.
- 6. The testing of metal and the design as per IRC shall have to be carried out by the contractor at his own cost.
- 7. Structure design is to be prepared by contractor and after approval of engineer-in-charge the work can be started.
- 8. Agency intending to carry out excavation will be able to carry out excavation / digging only after prior intimation through "Call before U Dig" mobile application.

CITY ENGINEER
Rajkot Municipal Corporation

Signature of Contractor with Seal

# PART-III BILL OF QUANTITIES (Attached in Separate Folder)



CONTRACT No: RMC/ENGG/EZ/24-25/155

Bidders are required to fill up all blank spaces in this Bid Form

The Commissioner
Rajkot Municipal Corporation
Dr. Ambedkar Bhavan
Dhebar Road
Rajkot

Dear Sir,

SUB : વોર્ડ નં.૦૧ માં એસ.આર.પી.(ઘંટેશ્વર)પ્રાથમિક શાળામાં કલર કરવાનું તેમજ પરચુરણ સિવિલ કામ રીટેન્ડર

(in words) below / above than the rates given in Price Schedule.

2. I / We agree that

(a) if we fail to provide required facilities to the Employer's representative or any other person/agency by the employer to perform on his behalf for carrying out the inspection and testing of materials and workmanship

OR

(b) if we incorporate into the Works, materials before they are tested and approved by the Engineer's representative

<u>OR</u>

(c) if we fail to deliver raw water of required quantity according to the conditions/stipulations of the Contract, the Engineer will be at liberty to take any action including termination of Contract and impose at his absolute discretion any penalties, and/or reject the work.

- 3. We undertake, if our Bid is accepted, to complete and deliver the Works in accordance with the Contract within **3 Months** of construction period from the date of Work Order issued to us by you.
- 4. We agree to abide by this Bid for a period of 120 days from the date of opening of technical bid and it shall remain binding upon us and may be accepted at any time before the expiry of that period.
- 5. In the event of our Bid being accepted, we agree to enter into a formal Contract Agreement with you incorporating the conditions of Contract thereto annexed but until such agreement is prepared this Bid together with your written acceptance thereof shall constitute a binding Contract between us.
- 6. We agree, if our Bid is accepted, to furnish Performance Bond/Security in the forms and of value specified in the Conditions of Contract of a sum equivalent to 5% of the Contract price for due performance of the Contract.
- 7. We have independently considered the amounts of liquidated damages shown in Appendix to Bid and agree that they represent a fair estimate of the damages likely to be suffered by you in the event of the Work not being completed by us in time.
- 8. We understand that you are not bound to accept the lowest or any Bid you may receive.

| Dated thisday of   | 20 <u>.</u>          |
|--|----------------------|
| Company Seal   | (Signature)          |
|  | (Name of the person) |
| (Name of firm) Duly authorised to sign Bid for and on behalf of (Fill in block capitals) | (In the capacity of) |
| Witness Signature  |                      |
| NameAddress  |                      |

# PREAMBLE TO PRICE SCHEDULES

#### Note on Schedule:

The bid is percentage rate bid for વોર્ડ નં.૦૧ માં એસ.આર.પી.(ઘંટેશ્વર)પ્રાથમિક શાળામાં કલર કરવાનું તેમજ પરયુરણ સિવિલ કામ રીટેન્ડર

- 1. The bid is percentage rate bid.
- The rates and prices shall be submitted in the formats given in the online Price Schedules. Rates and prices received in any other formats will be rejected and the Bids will be disqualified.
- It will be entirely at the discretion of the Employer to accept or reject the bidder's proposal, without giving any reasons whatsoever.
- 4. In Price Schedule, bidder shall quote his percentage Equal/Above/Below for items listed in the schedule. Prices quoted in Schedule only will be considered for price evaluation & shall form a part of the Contract Agreement.
- 5. The Only Price Schedule will be considered for financial evaluation of the bid with the successful bidder.
- 6. The bidder shall be deemed to have allowed in his price for provision, maintenance and final removal of all temporary works of whatsoever nature required for construction including temporary bunds, diverting water, pumping, dewatering etc. for the proper execution of works. The rates shall also be deemed to include any works and setting out that may be required to be carried out for laying out of all the works involved.
- 7. Where there is a discrepancy between the unit rates and the amount entered, the latter shall govern.
- 8. The Price Schedules are to be read in conjunction with the Conditions of Contract, the Specifications and other sections of these bid documents and these documents are to be taken as mutually explanatory of one another.
- 9. Prices quoted by the bidder shall be firm for the entire period of Contract without any escalation.
- The bidder shall interpret the data furnished and carry out any additional survey work, or investigative work required at his own cost.

- 11. The prices quoted shall also include the cost of materials utilized for testing.
- 12. The bidder should acquaint himself with the site conditions including the access to Worksite. The successful bidder shall have to make suitable access to worksites at his own cost. These accesses will be used by the other contractors working for RMC.
- 13. The material shall be inspected Departmentally, the cost of which, if any, is to be borne by contractor.
- 14. **Bidder has to quote their rates without GST** and including other taxes. The invoice should be submitted by contractor showing the breakup of GST in the bill. GST will be paid extra at the prevailing rate at the time of execution.

The contractor shall have to purchase the material required for this tender work, only from the supplier having registered GST Number. RMC will not be responsible to pay any amount towards GST if the material is purchased from the unregistered supplier not having GST Number.

- 15. In case of extra item work if quoted and approved tender price is above Percentage Rate then no above percentage rate will be given, only the rates as per S.O.R. will be paid for such extra item. But, if the quoted and approved tender price is below percentage rate then that below percentage rate will be considered for paying of any extra item.
- 16. The whole work is to be done under the supervision of RMC.
- 17. The rates and prices shall be submitted in the formats given in the enclosed Price Schedules. Rates and prices received in any other formats will be rejected and the Bids will be disqualified.
- 18. It will be entirely at the discretion of the Employer to accept or reject the bidder's proposal, without giving any reasons whatsoever.
- 19. In Price Schedule, bidder shall quote his percentage Equal/Above/Below for items listed in the schedule. Prices quoted in Schedule only will be considered for price evaluation & shall form a part of the Contract Agreement.
- 20. Only Price Schedule will be considered for financial evaluation of the bid with the successful bidder.
- 21. The Price Schedules are to be read in conjunction with the Conditions of Contract, the Specifications and other sections of

- these bid documents and these documents are to be taken as mutually explanatory of one another.
- 22. Prices quoted by the bidder shall be firm for the entire period of Contract without any escalation.
- The bidder shall interpret the data furnished and carry out any additional survey work, or investigation work required at his own cost.
- 24. The prices quoted shall also include the cost of materials utilized for testing.
- 25. The bidder should acquaint himself with the site conditions including the access to Worksite. The successful bidder shall have to make suitable access to worksites at his own cost. These accesses will be used by the other contractors working for RMC.
- 26. From each Running Account Bill, labour cess will be deducted as per norms.
- 27. In Every running bill 0.25% amount shall be retained as extra security deposit if Drawings of work done are not submitted by agency.
- 28. The quoted rates should be inclusive of all taxes and duties.
- 29. The prices shall have to be quoted firm & fix including all the taxes & duties without any statutory variation. RMC will not consider any statutory variation as well as the price rise in the market and if any, those shall be on account of contractor.
- 30. The work contract tax will be borne by the agency.
- 31. While considering experience of ongoing sewer/storm water pipeline works, part work completed in all respect will be considered for evaluation of bid. In this regard contractor shall be required to submit part completion certificate along with bid document from competent authority.

- 32. Use of ready mix concrete may be permitted if it fulfils tender specifications.
- 33. No extra item or extra width will be paid due to excavating method or type of machinery.
- 34. For any type of license regarding labour, etc. has to be achieved by agency.
- 35. This office Circular bearing No. RMC/C/329 dated 22-12-2012 and Order No. RMC/C/132 dated 10-06-2013 are uploaded in tender document.
- 36. In reference to the above Circular and Order cited at above, the Contractor firm who have quoted their rates for this work will be called in person for verification of original documents. The date and time for verification of original documents will be intimated to the Contractors.
- 37. If the progress of work is found slow then Extra security Deposit may be recovered from any running bill as decided by Engineer in charge up to maximum 5% amount of concerned R.A. Bill amount.
- 38. In case of Extra Item, No "**On**" %age i.e. +ve % age Rate will be given but if there is Down %age i.e, -ve % age Rate that will be applied to that rate of that Extra Item.

CITY ENGINEER (I/C)
Rajkot Municipal Corporation

Signature of Contractor with Seal

| Check List for submission of Documents   |          |
|--|----------|
| Tender Fee submitted as per Tender   | Yes / No |
| Tender Earnest Money Deposit submitted as per<br>Tender  | Yes / No |
| Registration documents submitted as per tender requirement   | Yes / No |
| Financial Details:   |          |
| Turnover details submitted as per requirement  | Yes / No |
| Working Capital as per requirement of tender is submitted  | Yes / No |
| Valid Bank Solvency submitted  | Yes / No |
| Validity of Bank Solvency  | Date:    |
| Experience Details:  |          |
| Details of Technical Staff and details of machineries submitted  | Yes / No |
| Address proof submitted  | Yes / No |
| Identity proof submitted   | Yes / No |
| Fresh Declaration on Non-Judicial Stamp Paper regarding not black listed or Terminated or Debarred, is submitted | Yes / No |
| Professional Tax Receipt of current year   | Yes / No |

#### Note:

Over and above, the agency shall also have to submit all other necessary documents as may be required for pre-qualification, failing which, the agency will be treated as Non-responsive and will be DISQUALIFIED and also the online price bid of such agency will not be opened.

Signature of Contractor with seal



#### **Rajkot Municipal Corporation Price Schedule - B**

#### Name of work:

વોર્ડ નં.૦૧ માં એસ.આર.પી.(ઘંટેશ્વર)પ્રાથમિક શાળામાં કલર કરવાનું તેમજ પરયુરણ સિવિલ કામ રીટેન્ડર

| Enemal painting on door/window, iron door, iron grill or woodwork two coat with Primer  20mm thick Sand Face Cement Plaster              | 125.00  | Sq.Mt.   |   |
|--|---|--|---|
| 20mm thick Sand Face Cement Plaster  |   |  | 27500.00  |
| Work in which 1 paster in proportion of 1:3 and 2nd plaster inteh proportion of 1:2 using Cement Mortar with spong                       | 263.00  | Sq.Mt.   | 13150.00  |
| Cement Plaster 12 mm thick using Cement:Mortar in proportion 1:3 with Niru Finishing curing, etc. complete                               | 223.00  | Sq.Mt.   | 11150.00  |
| Plastic Imulsion Paint (Two coats) (Asian Paint, ICI, Dulux,Nerolac, Berger etc. of approved type) (with Prime Coat)                     | 145.00  | Sq.Mt.   | 339300.00   |
| Apex Color work on Outer side of Wall (Two coats) (with Base Coat)   | 115.00  | Sq.Mt.   | 322000.00   |
| Painting of Traffic Strip Foothpath / Circle & divider block size 0.38 x 0.30 x 0.30 in two coats using enamle paint in different colors | 54.00   | R.Mt.  | 13500.00  |
| making of wall pictures in different wards   | 594.00  | Sq.Mt.   | 504900.00   |
|  |   | Total  | 1231500.00  |
|  |   |  | 221670.00   |
|  | I otal  |  | 1453170.00<br>14,54,000   |
| 000000000000000000000000000000000000000  | 1:3 and 2nd plaster inteh proportion of 1:2 using Cement:Mortar with spong finishing etc. complete (Note: Before carringout Plaster work on RCC, required tipping work should be carried out as instructed)  Cement Plaster 12 mm thick using Cement:Mortar in proportion 1:3 with Niru Finishing curing, etc. complete  Plastic Imulsion Paint (Two coats) (Asian Paint, ICI, Dulux,Nerolac, Berger etc. of approved type) (with Prime Coat) Apex Color work on Outer side of Wall (Two coats) (with Base Coat)  Painting of Traffic Strip Foothpath / Circle & divider block size 0.38 x 0.30 x 0.30 in two coats using enamle paint in different colors making of wall pictures in different | Work in which 1 paster in proportion of 1:3 and 2nd plaster inteh proportion of 1:2 using Cement:Mortar with spong finishing etc. complete (Note: Before carringout Plaster work on RCC, required tipping work should be carried out as instructed)  Cement Plaster 12 mm thick using Cement:Mortar in proportion 1:3 with Niru Finishing curing, etc. complete  Plastic Imulsion Paint (Two coats) (Asian Paint, ICI, Dulux,Nerolac, Berger etc. of approved type) (with Prime Coat)  Apex Color work on Outer side of Wall (Two coats) (with Base Coat)  Painting of Traffic Strip Foothpath / Circle & divider block size 0.38 x 0.30 x 0.30 in two coats using enamle paint in different colors  making of wall pictures in different wards  Add o | Work in which 1 paster in proportion of 1:3 and 2nd plaster inteh proportion of 1:2 using Cement:Mortar with spong finishing etc. complete (Note: Before carringout Plaster work on RCC, required tipping work should be carried out as instructed)  Cement Plaster 12 mm thick using Cement:Mortar in proportion 1:3 with Niru Finishing curing, etc. complete  Plastic Imulsion Paint (Two coats) (Asian Paint, ICI, Dulux,Nerolac, Berger etc. of approved type) (with Prime Coat)  Apex Color work on Outer side of Wall (Two coats) (with Base Coat)  Painting of Traffic Strip Foothpath / Circle & divider block size 0.38 x 0.30 x 0.30 in two coats using enamle paint in different colors  making of wall pictures in different wards  263.00  Sq.Mt.  263.00  Sq.Mt. |

R.M.C.

R.M.C.

Addl/Asst. Engineer Dy.Ex.Engineer CITY ENGINEER (SPL) R.M.C.

I/We agree to carry out the above said work at \_(to be quoted online) % Equal / above / below on the tendered rates shown in Schedule.

Signature of Contractor with Seal



#### રાજકોટ મહાનગરપાલિકા સોલિડ વેસ્ટ મેનેજમેન્ટ શાખા wow cell

A298075 स्वच्छ के India सर्वेद्या सर्वेद्वाण (Nex State), Nex Todalu 2,024

'ડો. આંબેડકર લવન, હેબરભાઇ રોડ, રાજકોટ

રા.મ.ન.પા./સો.વે.મે./જા.નં.-6445

rtl.30-03-2024

**§**84:

#### સંદર્ભ: સ.મ.ન.પા./સો.વે.મે./જા.નં ૮૬૬, તા. ૦૪-૦૬-૨૦૧૯

રાજકોટ મહાનગરપાલિકા વિસ્તારમાં વિકાસ કામો અને બાંધકામ પ્રવૃત્તિનો ખૂબ જ ઝડપથી વિકાસ શઈ રહેલ છે. જેના પરિણામે શહેરમાં કન્સ્ટ્રક્શન એન્ઠ ડિમોલિશન વેસ્ટ પણ ખૂબ બહેળા પ્રમાણમાં ઉત્પન્ન થાય છે. આથી તેના કલેક્શન તથા યોગ્ય પદ્ધતિથી નિકાલની ખૂબ જ વિકટ સમસ્યા ઊભી શાય છે. કન્સ્ટ્રક્શન એન્ઠ ડિમોલિશન (સી & ડી) વેસ્ટ કલ્સ -2016 પ્રમાણે આ વેસ્ટનું કલેક્શન, સ્ટોરેજ તથા પ્રોસેસિંગ કરી યોગ્ય નિકાલ કરવો જરૂરી છે. જે અન્વયે આ અગાઉ ઉપરોક્ત સંદર્ભિત ફુકમથી શફેરમાં ઉત્પન્ન થતા સી & ડી વેસ્ટના નિકાલ અન્વયેની માર્ગદર્શિકા નિયત કરવામાં આવેલ. જેની વધુ અસરકારકતા તથા કાર્યક્ષમતા સાથે પરિણામલક્ષી કામગીરી થઇ શકે તે માટે ફવે પછીથી નીયે જણાવ્યા મુજબની વિગતે અમલવારી કરવા ફકમ કરવામાં આવે છે.

(૧) રાજકોટ મહાનગરપાલિકાની ટાઉન પ્લાનિંગ શાખા દ્વારા શહેરમાં આવેલ ફ્યાત/જુના બાંધકામ ધરાવતી ઈમારતોને સ્થાને નવું બાંધકામ કરવા માટેની બાંધકામ પરવાનગી ઇસ્યુ કરતા પહેલા હાલની વ્યવસ્થા મુજબ જે ડિમોલિશન ચાર્જ લેવામાં આવે છે તેની સાથે શહેરમાં આવેલ આવી જૂની ઈમારતોનું બાંધકામ માલિક/કબજેદાર/ડેવલપર દ્વારા દૂર કરવાથી કેટલો સી & ડી વેસ્ટ ઉત્પન્ન (Generate) થશે તે બાંધકામ પરવાનગી અર્થે પ્લાન સફીતની વિગતો રજૂ કરનાર પરવાનેદાર એક્જિનિયરશ્રી/આર્કિટેકટશ્રી મારફત પ્રમાણિત કરાવી તેના જથ્થા મુજબ અને બાંધકામની પરવાનગીના પ્રકાર મુજબ આ ઉત્પન્ન થનાર સી & ડી વેસ્ટને નાકરાવાડી ખાતે આવેલ સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતે નિકાલ કરવા માટેની ડિપોઝિટની રકમ પેટે રૂપિયા ૫૦૦૦/- (અંકે રૂપિયા પાંચ ફજાર પુરા) વસુલવાની રહેશે. આ પ્રકારના તમામ કિસ્સાઓમાં ડીપોઝીટની રકમ જમા થથા બાદ જ ટાઉન પ્લાનિંગ શાખા દ્વારા શરતી બાંધકામ પરવાનગીમાં સંલગ્ન જૂની ઈમારતના સી & ડી વેસ્ટને ટ્રાન્સપોર્ટ કરી સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતે મોકલી આપવામાં આવ્યાનું પ્રમાણિત થયા બાદ જ ટાઉન પ્લાનીંગ શાખા દ્વારા બાંધકામ પરવાનગી આપવામાં આવશે અને ત્યારબાદ જ અરજદારશ્રી દ્વારા નવું બાંધકામ શરૂ કરવાનું રહેશે તેવો ઉલ્લેખ કરવાનો રહેશે.

શરતી બાંધકામ પરવાનગી મેળવ્યા બાદ અરજદારશ્રી દ્વારા તેઓના જુના મકાન/ઈમારતના ડીમોલીશનને કારણે નીકળેલ સી & ડી વેસ્ટને રાજકોટ મહાનગરપાલિકાના નાકરાવાડી ખાતે આવેલ સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ પર મોકલવાની વ્યવસ્થા કરી નિકાલ કરવાનો રહેશે, તથા સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતેથી આ અંગેની પહોંચ (રીસીપ્ટ)/પ્રમાણપત્ર મેળવી લેવાનું રહેશે.

સી. & ડી. વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતે શહેરમાંથી સી & ડી વેસ્ટના નિકાલ અર્થે આવેલ મટીરીયલ અંગેનું રજીસ્ટર નિભાવવાનું રહેશે. તથા પ્લાન્ટ ખાતે સી & ડી વેસ્ટ લઇને આવેલ તમામ વાહન તથા તેના સી & ડી વેસ્ટના જથ્થાની નોંધ ઓનલાઇન નિયત એપ્લીકેશનમાં કરવાની રહેશે. પ્લાન્ટ ખાતે મેળવવામાં આવેલ સી & ડી વેસ્ટ મટીરીયલની પહોંચ (રીસીપ્ટ)/પ્રમાણપત્ર આપવા અંગેની જરૂરી તમામ વ્યવસ્થા સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટની એજન્સી દ્વારા કરવાની રહેશે.

ટાઉન પ્લાનિંગ શાખા દ્વારા ઉપરોક્ત જણાવ્યા મુજબ જુના બંધકામ/ઈમારતના ડીમોલીશનને કારણે ઉત્પન્ન થયેલ સી & ડી વેસ્ટને અરજદારશ્રી દ્વારા નાકરાવાડી ખાતેના સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતે

- મોકલ્યાની ખરાઈ (Confirmation) કર્યા બાદ જ અરજદારશ્રી દ્વારા જમા કરવામાં આવેલ ડીપોઝીટની રકમ્ રૂ.૫૦૦૦/- (અંકે રૂપિયા પાંચ કજાર પુરા) પરત કરી બાંધકામ પરવાનગી ઇસ્યુ કરવાની રહેશે.
- (૨) ટાઉન પ્લાર્ભેગ શાખા દ્વારા કન્સ્ટ્રક્શન એન્ડ ડીમોલિશન વેસ્ટ રૂલ્સ 2016 ની માર્ગદર્શિકા મુજબ શહેરમાં જૂનો ઇમલો દ્વર કરનાર એજન્સીઓ કોન્ટ્રાક્ટરો દ્વારા સી & ડી વેસ્ટનું કલેક્શન તથા તેનું જરૂરી સેગ્રીગેશન કરી રાજકોટ મહાનગરપાલિકાના નાકરાવાડી ખાતે આવેલ સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતે નિકાલ કરવાનું કરજીયાત હોવાની બાબતની સમજ આપી તેઓનું રજીસ્ટ્રેશન કરાવી રાજકોટ મહાનગરપાલિકાની વેબસાઈટ પર શહેરમાં ઈમલો દ્વર કરવાની કામગીરી કરતી આવી તમામ એજન્સીઓ કોન્ટ્રાક્ટરોની યાદી મૂકવાની રહેશે.
- (3) સોલિડ વેસ્ટ મેનેજમેન્ટ વિભાગ દ્વારા ફાલ રાજકોટ મहાનગરપાલિકાના ત્રણેય ઝોનના જુદા જુદા વોર્ડ વિસ્તારના પ્લોટ તથા રસ્તાઓની સાઈડમાં પડેલ સી & ડી વેસ્ટને કલેકટ કરી નાકરાવાડી ખાતે આવેલ સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટની જરૂરીયાત મુજબ પ્લાન્ટ ખાતે પહોંચાડવા (Transportation) ની વ્યવસ્થા કરવાની રહેશે, તથા શહેરના જાહેર રસ્તાઓ કે રાજકોટ મહાનગરપાલિકાના પ્લોટ પર અનઅધિકૃત રીતે સી & ડી વેસ્ટ ડિપ્પેંગ ન થાય તે અંગેની તકેદારી રાખવા માટેની જરૂરી વ્યવસ્થા ઉભી કરવાની રહેશે.
- (૪) રાજકોટ મહાનગરપાલિકાની તમામ તાંત્રિક શાખા દ્વારા તેમના કાર્યક્ષેત્ર ફેઠળ સિવિલ કામ કરતી તમામ એજન્સીઓ (ઝ્રોનલ તથા ટેન્ડર કામ) ને સોંપવામાં આવેલ સિવિલ કામગીરી અંતર્ગત ઉત્પન્ન થનાર સી & ડી વેસ્ટના સંપૂર્ણ જથ્થાનો નિકાલ રાજકોટ મહાનગરપાલિકાની નાકરાવાડી ખાતે આવેલ સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતે કરાવવાનો રહેશે.

આ માટે ઉત્પન્ન થયેલ સી & ડી વેસ્ટના જથ્થાને સંલગ્ન તાંત્રિક કામગીરી સંભાળતા એ.એ.ઈ.શ્રી તથા એ.ઈ.શ્રી દ્વારા તેમના નાયબ કાર્યપાલક ઇજનેરશ્રી મારફતે પ્રમાણિત કરાવી તે સી & ડી વેસ્ટના જથ્થાને સિવિલ કામની સંલગ્ન એજન્સી દ્વારા ટ્રાન્સપોર્ટેશનની વ્યવસ્થા કરી શહેરમાં અન્ય કોઈપણ જગ્યાએ નિકાલ ન કરી માત્ર નાકરાવાડી ખાતે આવેલ સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતે જ જમા કરાવવાનો રહેશે, તથા પ્લાન્ટ ખાતેથી તે અંગેની પહોંચ (રીસીપ્ટ)/પ્રમાણપત્ર મેળવવાનું રહેશે. જે પહોંચ (રીસીપ્ટ)/પ્રમાણપત્ર સંલગ્ન તાંત્રિક શાખામાં રજુ થયા બાદ તેને સંલગ્ન તાંત્રિક સ્ટાફ દ્વારા ચકાસણી કર્યા બાદ જ સંલગ્ન નાયબ કાર્યપાલક ઇજનેરશ્રી દ્વારા એજન્સીએ કરેલ કામની રકમનું ચૂકવણું કરવા માટેની બીલ અંગેની કાર્યવાહી હાથ ધરવાની રહેશે.

(૫) રાજકોટ શહેરમાં ઉત્પન્ન થનાર સી & ડી વેસ્ટનો મહત્તમ રીયુઝ તથા રિસાયકલ થાય તે માટે કઈ કઈ બાંધકામ ઉપયોગી વસ્તુઓ (મટીરીયલ) બનાવી શકાય તથા તે તમામ મટીરીયલનો રાજકોટ મહાનગરપાલિકાના વિવિધ તાંત્રિક કામોમાં ઉપયોગ થાય તેવા મટીરીયલનો રાજકોટ મહાનગરપાલિકાના શેડ્યુલ એફ રેઈટસ (S.O.R.) માં સમાવેશ કરવા તથા રાજકોટ મહાનગરપાલિકાના વિવિધ સિવિલ કામમાં તેનો ઉપયોગ થાય તે સુનિશ્ચિત કરવા માટેની જરૂરી કાર્યવાહી હાથ ધરવાની રહેશે.

ઉપરોક્ત વિગતે સોંપવામાં આવેલ કામગીરીનો રિપોર્ટ નાયબ કમિશનરશ્રી (ઈસ્ટ ઝોન)ને કરવો. સદરફ ફકમનો અમલ તાત્કાલિક અસરથી યુસ્તપણે કરવાનો રહેશે.

રાજકોટ મહાનગરપાલિકા

## સ.સ.લ.પા./ય.ગો./સો.વે.તે./જા.લં. ૧૪૭૬ કા.સ.લ.પા./ય.ગો./સો.વે.તે./જા.લં. ૧૬૬૧

#### જાહેરનામું

આશી હું અમિત અરોરા (IAS), મ્યુનિસીપલ કમિશનર, રાજકોટ મહનગરપાલિકા, રાજકોટ ગુજરાત પ્રોવિન્સીયલ મ્યુનિસીપલ કોર્પોરેશન એકટ-૧૯૪૯ની જોગવાઇ અનુસંધાને મળેલ સતા મુજબ, જાહેર હિતને ધ્યાને લઇ, રાજકોટ મહનગરપાલિકા વિસ્તારમાં ઇમારત તોડવા, સમારકામ અથવા તો નવા બાંધકામ દરમ્યાન ઉપસ્થિત થતા બાંધકામએ લગત કચરા (Construction and Demolition Waste) નો રાજકોટ મહનગરપાલિકા ઘરા નિયત કરાયેલ જગ્યા સિવાય નિકાલ કરવા પ્રતિબંધ કરમાવું છું.

એવું ધ્યાનમાં આવેલ છે જે, રાજકોટ મહ્મનગરપાલિકા વિસ્તારમાં ઇમારત, ઇમારતોના બાંધકામ દરમ્યાન નળીયા, પશ્ચરા, ઇટો, ઇમારત બાંધવાના માલ સામાન અને એવા માલ સામાનનો કાટમાળ ગમે તે જગ્યાએ નિકાલ / એકઠો કરવામાં આવે છે. જેનાથી એવી જગ્યાએ ઉંદરો અથવા અન્ય જીવ જંતુઓનું આશ્ચય સ્થાન અથવા ઉત્પતિ સ્થાન બને છે. તેમજ સદરઠું જગ્યાનો ભોગવટો કરનારાઓને અથવા પડોશમાં રહેતી વ્યક્તિઓના ભય અને ઉપદ્રવનું કારણ બને છે. તેના કારણે રોગયાળો ફેલાવવાનો ભય અને લોકોના આરોગ્ય તથા જાનમાલને નુકસાન થાય તેવી સ્થિતી ઉત્પન્ન થાય છે. તેમજ તે કચરો (construction and Demolition Waste) દુર કરવા રાજકોટ મહ્મનગરપાલિકાને ખુબજ મોટો ખર્ચ થાય છે, તેમજ માનવ સમય બગડે છે. આમ. લોકોના જાનમાલના અને આરોગ્યના નુકસાનના ભોગે આવી ગેરકાયદેસર પ્રવૃતિ યાલી રહેલ છે, આવી કોઇપણ પ્રવૃતિ જન આરોગ્ય માટે બિન સલામતી નોતરે તેમ હોય, ગુજરાત પ્રોવિન્સીયલ મ્યુનિસીપલ કોર્પોરેશન એકટ અનુસુચી-ક ના પ્રકરણ-૧૪ ની જોગવાઇઓ અનુસંધાને આવી તમામ પ્રવૃતિ કરવાનો અગાઉના જાહેરનામા નં.સ.મ.ન.પા./મ.ઝો./સો.વે.મે./જા.નં.૧૯૪૧, તા.૦૬/૦૮/૨૦૧૯ થી પ્રતિષેધ કરમાવવામાં આવેલ અને આવા કચરા (Construction and Demolition Waste)ના નિકાલ માટે રાજકોટ મહનગરપાલિકાએ નીચે દર્શાવેલ સ્થળો નિયત કરવામાં આવેલ.

- ૧. ક્રેઠારીયા પોલીસ ચોકીની બાજુમાં પથ્થરની ખાણ પાસે,
- ર. રૈયા સ્માર્ટ સીટીના તમામ ખાણ વિસ્તાર,

6

- 3. ટી.પી.સ્ક્રીય નં.૧૦, એફ.પી.-૮૭, ઢેબર રોડ, સાઉથ અટીકા વિસ્તાર, પી.જી.વી.સી.એલ. ઓફિસ પાસે.
- ૪. ટી.પી.સ્ક્રીમ નં.૨૩, એફ.પી.-૨૩, મોરબી રોડ,પોપટપરા આઇ.ઓ.સી. ગોડાઉન પાસે.
- ૫. સમ્રાટ ઇન્ક. એરિયા, એસ.ટી. વર્કશોપ પાછળ, અનામત પ્લોટ,
- s. ટી.પી.સ્ક્રીમ નં.૯, એફ.પી.-૫, રૈયાધાર ગાર્બેજ ટ્રાન્સફર સ્ટેશન પાસે,
- ૭. ટી.પી.સ્ક્રીમ નં.૨૦, એફ.પી.-૩૫, પ્રધ્યુમન ગ્રીન પાછળ

ઉપરોક્ત સ્થળો ઉપરાંત નીચે મુજબના સ્થળો Construction and Demolition Waste ના નિકાલ માટે નિયત કરવામાં આવે છે.

- ૧. જેટક્રે ચોકડી, ટી.પી.સ્ક્રીમ નં.૨૮, મવડી, એફ.પી.-૪૬/એ,
- ર. ટી.પી.સ્ક્રીમ નં.૧૨, કોહરીયા નેશનલ કાઇવે, લીજજત પાપડ પાસે, એફ.પી.-૩૮/એ, ૩૯/બી.

ઉપરોક્ત નિયત કરેલ સ્થળો સિવાય અન્ય કોઇપણ જગ્યાએ કોઇપણ ઇસમ/ઇસમો છકડો, ટ્રેક્ટર અથવા ડમ્પર દ્વારા (Construction and Demolition Waste) નો નિકાલ કરતાં પકડાશે તો પ્રથમ વખત છકડો/ટ્રેક્ટર દીઠ રૂ!.૭,૫૦૦/- તથા ડમ્પર દીઠ રૂ!.૧૫,૦૦૦/-, બીજી વખત છકડો/ટ્રેક્ટર દીઠ રૂ!.૧૫,૦૦૦/- તથા ડમ્પર દીઠ રૂ!.૩૦.૦૦૦/- અને ત્રીજી વખત છકડો/ટ્રેક્ટર દીઠ રૂ!.૫૦,૦૦૦/- તથા ડમ્પર દીઠ રૂ!.૧.૦૦.૦૦૦/-લેખે વર્શવટી યાર્જ વસુલ કરવામાં આવશે. તેમજ વાદન જપ્ત કરવા સુધીની કાર્યવાહી કરવામાં આવશે.

શહેરમાં વસતાં નાગરીકો દ્વારા ઉપરોક્ત Construction and Demolition Waste ના નિકાલ માટે રાજકોટ મહાનગરપાલિકા દ્વારા ઝોન વાઇઝ કામગીરી માટે Construction and Demolition Waste સેલની રચના કરવામાં આવેલ છે. શહેરના નાગરિકો રાજકોટ મહાનગરપાલિકાના કોલ સેન્ટર – ૦૨૮૧-૨૪૫૦૦૭૭ પર ફોન કરી તેમની મિલ્કતનાં રીપેરીંગ કે કાટમાળનો નિકાલ નીચે મુજબનાં નિયત થયેલ યાર્જીસ ભરપાઇ કરી નિકાલ કરવાની વ્યવસ્થાનો લાભ મેળવી શકશે.

- (00E. | \$ 1/2 \$522 3|.300/-
- ટ્રેક્ટર જેટલો જથ્થો રૂા.૫૦૦/-
- ट्र**५ / ५३**५२ श्रेटली श्रथ्यो ३।.१,०००/-

ઉપરોક્ત નિયત કરાયેલ સ્થળોએથી ખાનગી માલિકો, જુનો એકત્રિત થયેલ બાંધકામનો કાટમાળ પોતાના ઉપયોગ માટે સ્વખર્ચે ઉપાડી લઇ જઇ શકશે.

ઉકત જાહેરનામાનો યુસ્તપણે અમલ કરવો.

રાજકોટ. તા.∤/*b*/२०२२

રાજકોટ મહાનગરપાલિકા



# राष्ड्रीट महानगर सेवासहन

ડો. આંબેડકર ભવન, ઢેબરભાઈ રોડ, રાજકોટ – 350 00૧.

ni.vog.smr.www. : 5011605

રા.મ્યુ.કો./વીજી.ટેક./જા. નં. ૧૦ & 26/2/26 n. 20/ do26

#### પરિપત્ર:-

> રાજકોટ મહાનગરપાલિકામાં ત્રણ ઝોન (ઇસ્ટ, સેન્ટ્રલ, વેસ્ટ) માં ઝોનલ કામમાં કે ટેન્ડરથી થતા કામમાં પેવર બ્લોકની કામગીરી કરવામાં આવે છે. જેથી, ક્વોલીટી કન્ટ્રોલ માટે પેવર બ્લોકની કામગીરીમાં વપરાશ કરવામાં આવતા પેવર બ્લોકનું ટેસ્ટીંગ કરવું જરૂરી હોય, વોર્ડમાં ઝોનલ કામ, ટેન્કર કામ તેમજ વિવિધ શાખા હસ્તક યાલતા પ્રોજેક્ટ કામમાં વપરાશ કરવામાં આવતા તમામ પ્રકારના પેવર બ્લોકના કામમાં કામ કરાવનાર RMC ટેકનીકલ ટીમ દ્વારા IS 15658:2006 મુજબ Government લેબોરેટરી કે Government માન્ય લેબોરેટરીમાં હાજરીમાં

કરજીયાતપણે ટેસ્ટીંગ કરાવવાનું રહેશે.

🛩 આ ઉપરાંત, રાજકોટ મહાનગરપાલિકાની, વિવિધ શાખા હસ્તક યાલતાં બાંધકામ તથા રસ્તાકામને લગત, દરેક મહત્વના પ્રોજેક્ટના અગત્યનાં તબક્કે કામગીરી કરાવનાર પ્રોજેક્ટ એક્ઝીક્યુશન ટેકનીકલ ટીમ દ્રારા આગળના દિવસે વિજીલન્સ (ટેક.) ટીમને SMS/Whatsapp થી જાણ કરવામાં આવે છે. તે જ રીતે પેવર બ્લોક બાબતે RMC એક્ઝીક્યુશન ટેકનીકલ ટીમ દ્રારા ફાલ ચાલુ હોય તેમજ હવે પછી થનાર તમામ પેવર બ્લોકના કામો માટે આગળના દિવસે વિજીલન્સ (ટેક.) ટીમને SMS/Whatsapp થી જાણ કરવાની રફેશે. જે અન્વયે વીજીલન્સ શાખા (ટેક.) દ્વારા રેન્ડમ સેમ્પલીંગ કરી, IS 15658:2006 મુજબ Government લેબોરેટરી કે Government માન્ય લેબોરેટરીમાં ફાજરીમાં કરજીયાતપણે ટેસ્ટીંગ કરાવી, અત્રે રીપોર્ટ કરવાનો રહેશે.

ઉપરોક્ત બાબતની અમલવારી તાત્કાલિક અસરથી યુસ્તપણે કરવાની રહેશે.

રાજકોટ મહાનગરપાલિકા

નકલ રવાના (જાણ તથા અમલવારી અર્થે) - નાયબ કમિરનરશ્રી (ઇસ્ટ, સેન્ટ્રલ, વેસ્ટ-ઝોન)

નકલ રવાના (અમલવારી અર્થે)-

- તમામ સીટી એન્જીનીયરશ્રી, એડી. સીટી એન્જીનીયરશ્રી, એક્ઝીક્યુટીવ એન્જીનીયરશ્રી 2018-8-29 12:55



### રાજકોટ મहાનગરપાલિકા

ડો. આંબેડકર ભવન, હેબર રોડ, રાજકોટ - ૩૬૦૧૧૦.

ni.vag.smr.www. = Sussiss

આર.એમ.સી./સી./

master learn

परीपत्र-:

Vog 1, 100 / m d 9 CO

- રાજકોટ મફાનગરપાલિકામાં ત્રણ ઝોન (ઇસ્ટ, સેન્ટ્રલ, વેસ્ટ) માં ઝોનલ કામમાં કે ટેન્ડરથી થતા કામમાં પેવર બ્લોકની કામગીરી કરવામાં આવે છે. જેથી, ક્વોલીટી કન્ટ્રોલ માટે પેવર બ્લોકની કામગીરીમાં વપરાશ કરવામાં આવતા પેવર બ્લોકનું ટેસ્ટીંગ કરવું જરૂરી ફોય, રા.મ્યુ.કો./વીજી. (ટેક.)/જા.નં.૧૦૨, તા.૨૯/૦૮/૨૦૧૮ થી વોર્ડમાં ઝોનલ કામ, ટેન્ડર કામ તેમજ વિવિધ શાળા કસ્તક યાલતા પ્રોજેક્ટ કામમાં વપરાશ કરવામાં આવતા તમામ પ્રકારના પેવર બ્લોકના કામમાં કરજીયાતપણે ટેસ્ટીગ કરાવવા માટે પરીપત્ર કરવામાં આવેલ છે.
- » જે પરીપત્ર અન્વરો આ પરીપત્રથી હવે પછી કરવાનાં થતા તમામ ટેન્કર કામ તેમજ નવા ઝોનલ કોન્ટ્રાક્ટના કામોમાં નીચે પ્રમાણે યુસ્ત અમલવારી કરવાની રહેશે.
- > આ પરીપત્ર પહેલાના કોઇપણ ઝોનલ કે ટેન્ડર કામ માટે જે તે Grade ની સાપેક્ષ પરિણામ ન મળે તો જે તે મળેલ પરિણામ પ્રમાણે Rate Reduce કરવાનાં રહેશે.
- > કોઇપણ Grade ના પેવર બ્લોક માટે Compressive Strength નું સરેરાશ પરિણામ 10% કરતા વધારે ઓછું (દા.ત. M-30 Grade માટે Compressive Strength 27 N/mm' થી ઓછી) મળશે તો તે પેવરબ્લોક Reject કરવામાં આવશે એટલે કે તેમનું Payment કરવામાં આવશે નહિ.
- > કોઇપાઇ Grade ના પેવર બ્લોક માટે Compressive Strength નું સરેરાશ પરિણામ 10 x ની મર્ટાદામાં ઓણું (દા.ત. M-30 Grade માટે Average Compressive Strength 27 જાજાના થી 29.99 N/mm' ની વચ્ચે) મળશે તો તે પેવરબ્લોક માટે Minimum 5 X તેમજ Maximum 10 x મળેલ Average Compressive Strength પ્રમાણે જાજાન વિલ્લેલ્ડ કરવાના રહેશે.
- होशपड़ Grade ना पेतर अलोड माटे Weter Absorption नु सदेशश परिवाम ६४ की वधारे अववे तो ते पेपरअलोड सक्का डरवामां आवशे जेटले डे तेमनु स्थानकार डरवानुं वसे नहि.

- Compressive Strength માટે કલ ૮ પેવર બ્લોકનું ટેસ્ટીંગ કરવાનું રહેશે જે ૮ પેવર બ્લોક (ગ્રેંડ મુજબ સરેરાશ પરિણામ મળશે તો પણ) પૈકી જો ૧ થી ૨ Individual Sample નું પરિણામ 85% કરતા ઓછું મળશે તો 10% Rate Reduce કરવામાં આવશે તેમજ ૮ પેવર બ્લોક પૈકી જો ૨ થી વધારે Individual Sample નું પરિણામ 85% કરતા ઓછું મળશે તો તે પેવરબ્લોક Reject કરવામાં આવશે એટલે કે તેમનું Payment કરવામાં આવશે નહિ.
- > ૧૨.૦૦ મી. કે તેથી મોટા રોડના Side Shoulder માટે M-30 Grade (ISI Mark)
  Rubber Mould Paving Block વાપરવાના રહેશે. ૧૨.૦૦ મી. થી નાની પહેળાઈના રસ્તાઓ પર Side Shoulder માં M-30 Grade (ISI Mark) Non Rubber Mould Paving Block વાપરવાના રહેશે.
- પહોળાઈમાં ૫.00 મી. કે તેથી ઓછી પહોળાઈ વાળી શેરી હ્રેય ત્યાં જ આખી શેરીમાં Paving Block ની કામગીરી કરી શકાશે.જનભાગીદારી ચોજના હ્રેય ત્યાં ૫.00 મી. કે તેથી વધુ પહોળાઈ વાળી શેરીમાં Rubber Mould Paving Block ની કામગીરી કરી શકાશે.
- આ પરીપત્રને ટેન્ડરના એક ભાગ તરીકે રાખવાનો રહેશે.
  ઉપરોક્ત બાબતની અમલવારી તાત્કાલિક અસરથી યુસ્તપણે કરવાની રહેશે.

કમિશ્વર રાજકોટ મહાનગરપાલિકા

lud P.

નકલ રવાના (જાણ તથા અમલવારી અર્થે) - નાયબ કમિશ્વરશ્રી (ઇસ્ટ, સેન્ટ્રલ, વેસ્ટ ઝોન)

નકલ રવાના (અમલવારી અર્થે)

તમામ સીટી એન્જીનીચરશ્રી, એડી. સીટી એન્જીનીચરશ્રી, એક્ઝીક્યુટીવ એન્જીનીચરશ્રી, એન્વાચરમેન્ટ એન્જીનીચરશ્રી (S.W.M.) ડી.ઇ.ઇ.શ્રી (વીજીલન્સ શાખા – ઢેક.)

# રાજકોટ મહાનગરપાલિકા



ડો. આંબેડકર ભવન, ઢેબર રોડ, રાજકોટ – ૩૬૦૧૧૦.

downes , www.rmc.gov.in

આર.એમ.સી./સી./

11.14.51./195./m.d. .. (5)

11.95 05 1809G

સંદર્ભ:- પરીપત્ર રા. હ્યુ કો. /વીજી /જા.નં. ૧૮૦, તા. ૨૭/૧૨/૨૦૧૮.

# સુધારા પરીપત્ર-:

- રાજકોટ મહાનગરપાલિકામાં ત્રણ ઝોન (ઇસ્ટ, સેન્ટ્રલ, વેસ્ટ) માં ઝોનલ કામમાં કે ટેન્ડરથી થતા કામમાં પેવર બ્લોકની કામગીરી કરવામાં આવે છે. જેથી, ક્વોલીટી જળવાય તે માટે પેવર બ્લોક માટે સંદર્ભથી પરીપત્ર કરવામાં આવેલ. જેના બદલે નીચે પ્રમાણે સુધારા પરીપત્ર કરવામાં આવે છે.
- મંદર્ભમાં દર્શાવેલ પરીપત્ર પહેલાના કોઇપણ ઝોનલ કે ટેન્ડર કામ માટે પરિણામ ન મળે તો જે તે મળેલ પરિણામ પ્રમાણે Rate Reduce કરવાનાં રહેશે.
- મંદર્ભમાં દર્શાવેલ પરીપત્ર પછીના તમામ નવા ટેન્કર કામ તેમજ નવા ઝોનલ કોન્ટ્રાક્ટના કામોમાં નીચે પ્રમાણે યુસ્ત અમલવારી કરવાની રહેશે.
- > કોઇપણ Grade ના પેવર બ્લોક માટે Compressive Strength નું સરેરાશ પરિણામ 10% કરતા વધારે ઓછું (દા.ત. M-30 Grade માટે Compressive Strength 27 N/mm² થી ઓછી) મળશે તો તે પેવરબ્લોક Reject કરવામાં આવશે એટલે કે તેમનું Payment કરવામાં આવશે નહિ.
- > કોઇપણ Grade ના પેવર બ્લોક માટે Compressive Strength નું સરેરાશ પરિણામ 10% ની મર્યાદામાં ઓછું (દા.ત. M-30 Grade માટે Average Compressive Strength 27 N/mm² થી 29.99 N/mm² ની વચ્ચે) મળશે તો તે પેવરબ્લોક માટે Minimum 5 % તેમજ Maximum 10% મળેલ Average Compressive Strength પ્રમાણે Rate Reduce કરવાનાં રહેશે.
- > કોઇપણ Grade ના પેવર બ્લોક માટે Water Absorption નું સરેરાશ પરિણામ 6% વધુ 7% સુધી મળે તો 10% Rate Reduce કરવા, તેમજ Water Absorption નું પરિણામ 7% થી વધુ 8% સુધી મળે તો 25% Rate Reduce કરવા, તેમજ 8% થી વધુ Water Absorption નું પરિણામ મળે તો તે પેવરબ્લોક Reject કરવામાં આવશે એટલે કે તેમનું Payment કરવાનું થશે નહિ. 2019-7-23 16:43

- Compressive Strength માટે કુલ ૮ પેવર બ્લોકનું ટેસ્ટીંગ કરવાનું રહેશે જે ૮ પેવર બ્લોક (ગેડ મુજબ સરેરાશ પરિણામ મળશે તો પણ) પૈકી જો ૧ થી ૨ Individual Sample નું પરિણામ 85% કરતા ઓછું મળશે તો 10% Rate Reduce કરવામાં આવશે તેમજ ૮ પેવર બ્લોક પૈકી જો ૨ થી વધારે Individual Sample નું પરિણામ 85% કરતા ઓછું મળશે તો તે પેવરબ્લોક Reject કરવામાં આવશે એટલે કે તેમનું Payment કરવામાં આવશે નહિ.
- આ ઉપરાંત ભવિષ્યમાં પેવીંગ બ્લોકના કામોમાં 15:15658 (2006) મુજબ વધુ પ્રમાણમાં જરૂર કરતા ઓછા પરિણામ મળતા હોવાનું જાણમાં આવશે, ક્વોલીટી જળવાતી નહિ જણાય તો, સંદર્ભના પરીપત્ર પ્રમાણેની જોગવાઈ ફરીથી લાગુ પાડવામાં આવશે.
- responded to the state of the
- પહોળાઈમાં ૫.00 મી. કે તેથી ઓછી પહોળાઈ વાળી શેરી હોય ત્યાં જ આખી શેરીમાં Paving Block ની કામગીરી કરી શકાશે.જનભાગીદારી યોજના હોય ત્યાં ૫.00 મી. કે તેથી વધુ પહોળાઈ વાળી શેરીમાં Rubber Mould Paving Block ની કામગીરી કરી શકાશે.
- > આ પરીપત્રને ટેન્ડરના એક ભાગ તરીકે રાખવાનો રહેશે.

ઉપરોક્ત બાબતની અમલવારી તાત્કાલિક અસરથી યુસ્તપણે કરવાની રહેશે.

કમિશ્વર કમિશ્વર રાજકોટ મહાનગરપાલિકા 0

નકલ રવાના (જાણ તથા અમલવારી અર્થે) - નાયબ કમિશ્નરશ્રી (ઇસ્ટ, સેન્ટ્રલ, વેસ્ટ ઝોન)

# નકલ રવાના (અમલવારી અર્થે)

- તમામ સીટી એન્જીનીયરશ્રી, એડી. સીટી એન્જીનીયરશ્રી, એક્ઝીક્યુટીવ એન્જીનીયરશ્રી, એન્વાયરમેન્ટ એન્જીનીયરશ્રી (S.W.M.)
- ડી.ઈ.કી (વીજીલન્સ શાખા ટેક.)

# રાજકોટ મहાનગરપાલિકા



ડો. આંબેડકર ભવન, ઢેબરભાઈ રોડ, રાજકોટ – 350 009.

વેબસાઈટ : www.rmc.gov.in

આર.એમ.સી./સી./વીજી. (ટેક) /જા. નં. - 230

dl. 99/03/2092

#### પરીપત્ર-:

રાજકોટ મહાનગરપાલિકા અને RSCDL ખાતે ટેન્કરથી થતા કામમાં સિમેન્ટ કોન્કીટની કામગીરી કરવામાં આવે છે. આ કામોમાં ક્વોલીટી કન્ટ્રોલ જળવાઈ રહે તે માટે નીચે દર્શાવેલ દર્શાવ્યા મુજબ જુદા જુદા સિમેન્ટ કોન્કીટ ગ્રેડ વાઈઝ મીનીમમ સિમેન્ટ કન્ટેન્ટના ધોરણો અનુસરવા અને તેનો સમાવેશ ટેન્કર ડોક્યુમેન્ટમાં કરવા આથી ઠકમ કરવામાં આવે છે.

| (આ) | NABL માન્ય લેબ દ્વારા IS, IRC કે MORTH મુજબ તૈયાર કરાયેલ સિમેન્ટ કોન્કીટ મીક્સ ડીઝાઈન રીપોર્ટ |
|-----|---|
|     | મુજબ કિગ્રા સિમેન્ટ કન્ટેન્ટ પ્રતિ ધનમીટર   |
| (બ) | નીચે દશાવેલ ટેબલ મુજબ મીનીમમ કિગ્રા સિમેન્ટ કન્ટેન્ટ પ્રતિ ધનમીટર                             |

| Sr.<br>No. | Cement Concrete<br>Grade | 28 Days<br>Strength in<br>N/mm <sup>2</sup> | Minimum<br>Cement in Kg |  |
|------------|--------------------------|---|-------------------------|--|
| 1          | M-7.5 for PCC Work       | 7.5 N/mm <sup>2</sup>                       | 160 Kg                  |  |
| 2          | M-10 for PCC Work        | 10 N/mm <sup>2</sup>                        | 220 Kg                  |  |
| 3          | M-15 for PCC Work        | 15 N/mm <sup>2</sup>                        | 290 Kg                  |  |
| 4          | M-20 for RCC Work        | 20 N/mm <sup>2</sup>                        | 360 Kg                  |  |
| 5          | M-25 for RCC Work        | 25 N/mm <sup>2</sup>                        | 380 Kg                  |  |
| 6          | M-30 for RCC Work        | 30 N/mm <sup>2</sup>                        | 410 Kg                  |  |
| 7          | M-35 for RCC Work        | 35 N/mm <sup>2</sup>                        | 425 Kg                  |  |
| 8          | M-40 for RCC Work        | 40 N/mm <sup>2</sup>                        | 440 Kg                  |  |
| 9          | M-45 for RCC Work        | 45 N/mm <sup>2</sup>                        | 450 Kg                  |  |

ઉપરોક્ત (અ) અને (બ) પૈકી જે વધુ હોય, તે સિમેન્ટ કન્ટેન્ટ ને ફાઈનલ મીનીમમ સિમેન્ટ કન્ટેન્ટ પ્રતિ ધનમીટર ગણવા હુકમ કરવામાં આવે છે.

ઉપરોક્ત બાબતની અમલવારી તાત્કાલિક અસરથી યુસ્તપણે કરવાની રહેશે.

રાજકોટ મહાનગરપાલિકા

नंडल रवाना (ऋष् तथा अमलवारी अर्थे)

- નાયબ કમિરનરશ્રી (ઝોન-વેસ્ટ ,સેન્ટ્રલ ,ઇસ્ટ)

નકલ રવાના -(અમલવારી અર્થે)

- તમામ સીટી એન્જીનીયરશ્રી, એડી. સીટી એન્જીનીયરશ્રી, એક્ઝીક્યુટીવ એન્જીનીયરશ્રી, એન્વાયરમેન્ટ એન્જીનીયરશ્રી (S.W.M.) R.M.C./C./832

કમિશ્નર વિભાગ, રાજકોટ મહાનગર સેવાસદન તા. *9015) ન*ઇદ 3

हुडमः :-

વિષય:- ઈ-ટેન્ડર / ઓપન ટેન્ડર પધ્ધતિથી મંગાવવામાં આવતી તમામ પ્રકારની ઓફરો સાથે બિનઅધિકૃત રજુ થતાં ડોક્યુમેન્ટસ સામે કડક કાર્યવાકી હાથ ધરવા બાબત. સંદર્ભ :- આ અગાઉનો પરીપત્ર ને, આર.એમ.સી./સી./સેટલ. તા.૨૨/૧૨/૨૦૧૨.

રાજકોટ મહાનગર સેવાસદનના ત્રણ ઝોનનાં તમામ વોર્ડમાં શહેરનાં વિકાસ તથા જાળવલી માટે વિવિધ કામગીરી કરાવવા ઈ–ટેન્ડર / ઓપન ટેન્ડર પધ્ધતિથી અલગ અલગ એજન્સીઓ પાસેથી સ્પર્ધાત્મક ધોરણે ઋખબારી પ્રસિધ્ધિથી ભાવો ટુંબીડ સીસ્ટમ (૧) ટેકનીકલ બીડ (૨) પ્રાઈઝ બીડ થી મંગાવવામાં આવે છે.

સંદર્ભના પ્રસિધ્ધ કરેલ પરીપત્ર મુજબ તમામ ઈ—ટેન્ડર / ઓપન ટેન્ડરથી મંગાવવામાં આવતાં ભાવો સાથે ભાવ ભરનાર એજન્સીઓ / બીડરો દ્વારા ટેન્ડર બીડ માટે રજૂ કરવાનાં થતો તમાન ડોક્યુમેન્ટસ ફરજીવાતપણે ખરી નકલમાં અથવા સેલ્ફ એટેસ્ટેડ રજુ કરવા આદેશ કરવામાં આવેલ છે. જે સંબંધ નીચે મુજબનાં હુકમની અમલવારી તાત્કાલીક અસરથી કરવા આદેશ કરવામાં આવે છે.

(૧) તમામ ટેન્ડરકામોના, ટેકનીકલ બીડ ઓપન કરતી વખતે જે ટેન્ડર બીડ ભરનાર એજન્સીઓ ઢારા તમામ કોક્યુમેન્ટસ કે તે પૈકી કોઈપણ એક કોક્યુમેન્ટસ ખરી નકલમાં અથવા સેલ્ફ એટેસ્ટેડ રજૂ કરેલ ન હોય તો રજૂ થયેલ ટેકનીકલ બીડ ઓપન કરવાની કાર્યવાહી દરમ્યાન ટેકનીકલ બીડ ઓપન કરનાર સંબંધીત અધિકારીલી / કર્મચારીલીએ Disqualify પ્રકારનો રબ્બર સ્ટેમ્પ બિનઅધિકૃત રજૂ થયેલ ટેન્ડરનાં તમામ પાને લગાવી ટેકનીકલ બીડમાં ટેન્ડર Disqualify કરજીયાતપક્ષે કરવાનું રહેશે.

જે ટેન્ડર ખરી નકલ કે સેલ્ક એટેસ્ટેડ સાથે રજુ થયેલ નથી, તેવું ટેકનીકલ બીડમાં ધ્યાને આવ્યેથી રજુ થયેલ ટેન્ડરને Disqualify ન કરી, તે બીડરનું જો પ્રાઈઝ બીડ ખોલવામાં આવશે તો આવા પ્રાઈઝ બીડ ખોલનાર તમામ સંબંધીત અધિકારીથી / કર્મચારીશી સામે સખત શિક્ષાત્મક પગલાં લેવાની કરજ પડશે.

- (૨) તમામ ટેન્ડરોનાં કિસ્સાઓમાં સંબંધીત ખરી નકલમાં રજુ થયેલ તમામ ડોક્યુમેન્ટસની મુળ (ઓરીજીનલ)નકલ મંગાવી તેની ખરી નકલની ચકાસાશી કરજીધાતપકે સંબંધીત ડી.ઈ.ઈ.શ્રી તથા મ.ઈ.શી / અ.મ.ઈ.શીએ કરવાની રહેશે. જે મુળ નકલ સાથે વેરીફાય કર્યાની સહી ફરજીયાતપજે દરેક ખરી નકલમાં સંબંધીત ડી.ઈ.ઈ.શી/મ.ઈ.શી / અ.મ.ઈ.શીએ કરવાની રહેશે. તે પહેલાં તે ટેન્ડરની પ્રાઈઝ બીડ ઓપન કરી શકાશે નહી. જેમાં કરજચૂક થયેથી સંબંધીત જવાબદાર ડી.ઈ.ઈ.શી / મ.ઈ.શી / અ.મ.ઈ.શી ની સામે કડક ખાતાકીવ પગલાં લેવાની કરજ પડશે.
- (૩) ક્રમ ન (૧) તથા (૨) મુજબની ચકાસલી કરવા છતાં જે કિસ્સામાં ટેકનીકલ બીડ ઓપન કરતાં બીડર દ્વારા કોઈપલ પ્રકારનાં ક્રોડ ડોક્યુમેન્ટસ રજુ કરી કામ મેળવવા માટે પ્રમાસ કર્યાનું સાભિત થશે. તેવા કિસ્સામાં બીડર / એજન્સીને બ્લેકલીસ્ટ કરી, આવા બીડર સામે ફરજીયાતપણે ફોજદારી કાર્યવાહી સંબંધીત શાખાના વડા તથા વીજીલન્સ અધિકારીશ્રી (પ્રીટેકશન) દ્વારા જોઈન્ટલી દિન-૭ માં કરવા આદેશ કરવામાં આવે છે. જેની લેખિતમાં

- જાલ તાત્કાલીક અત્રે કરવાની રહેશે. જેમાં ચૂક થયેથી સંબંધીત તમામ અધિકારીથી / કમેંચારીથી સામે કડક પગલાં લેવા કરજ પડશે.
- (૪) સંદર્ભનો પરીપત્ર તથા આ હુકમ તમામ પ્રકારનાં ટેકનીકલ કામના દરેક ટેન્ડર પ્રસિધ્ધ કરતી વખતે ટેન્ડરનો હિસ્સો ગણી ટેન્ડરના ભાગ તરીકે પ્રસિધ્ધ કરવાનું કરજીયાત રહેશે, તથા બીડર દ્વારા ટેન્ડરમા પ્રસિધ્ધ થતા સંદર્ભના પરીપત્ર તથા આ હુકમનાં દરેક પાને સહી સિક્કા સાથે ભારેલ ટેન્ડરની ટેકનીકલ બીડ કરજીયાત રજુ કરવાની રહેશે.

ઉપરોક્ત હુકમનો તાત્કાલીક અસરથી યુસ્તપક્ષે અમલ કરવા આદેશ કરવામાં આવે છે.

કમિત્રનીર હૈ. રાજકોટ મહાનગર સેવાસદન

<u>નકલ રવાના (જાણ અર્થે):–</u> નાયબ કમિશ્નરશીઓ (તમામ)

નકલ જાણ તથા અમલવારી અર્થે:-(૧) સહાયક કમિશ્નરશ્રીઓ (તમામ) (૨) શાખાધિકારોશ્રીઓ (તમામ) આર.એમ.સી./સી. હર 🗸

રાજકોટ મહાનગરપાલિકા કમિશનર વિભાગ તા.સ્ટે/૧૧/૧૦૧૧

#### પરિપત્ર:-

ઇ-ટેન્ડર પદ્ધતિ / ઓપન ટેન્ડર પદ્ધતિથી માંગવામાં આવતી ઓફરોમાં એજન્સીઓ દ્વારા ટેકનીકલ બીડમાં રજુ કરવામાં આવતા ડોક્યુમેન્ટ્સ જેવા કે ટર્નઓવર, અનુભવના પ્રમાણપત્રો વિગેરે ખરી નકલમાં રજૂ કરવામાં આવતા નથી. આથી હવે પછીથી એજન્સીઓ દ્વારા રજૂ થતાં ટેકનીકલ બીડમાં રજુ કરવામાં આવતા ડોક્યુમેન્ટ્સ ખરી નકલમાં અથવા સેલ્ફ એટેસ્ટેડ ફોવા જરૂરી છે તેમજ જે એજન્સીનું ટેન્ડર ટેકનીકલ બીડમાં ક્વોલીફાય થાય અને ખરી નકલ ગેઝેટેડ ઓફીસર મારફત પ્રમાણિત કરાવેલ ન ફોય તેવા કેસમાં તેના એરીજીનલ ડોક્યુમેન્ટ્સ પ્રાઇસબીડ ખોલતા પફેલા ચકાસી અને ખરી નકલ રજૂ કરાવીને જ ખોલવાના રફેશે તથા આ બાબતનું શાખાધિકારીશ્રીઓએ યુસ્તપણે પાલન કરાવવાનું રફેશે. આમ ન થયેથી પુરતી ચકાસણીને અભાવે જો કોઇ એજન્સીને ખોટા કે અધુરા આધારો સાથે કામ આપવાની ક્ષતિજનક બાબત જાણમાં આવ્યે તે ટેન્ડર ડોક્યુમેન્ટ્સની ચકાસણી કરનાર કર્મચારીશ્રીઓ તેમજ શાખાધિકારીશ્રીની જવાબદારી નક્કી કરવામાં આવશે, જેની સર્વે શાખાધિકારીશ્રીઓએ નોંધ લેવી.

ઉપરોક્ત બાબતનો અમલ તાત્કાલિક અસરથી કરવો.

રાજકોટ મહાનગરપાલિકા

નકલ રવાના :- (જાણ અર્થે)

- નાયબ કમિશનરશ્રીઓ (તમામ)

નકલ જાણ તથા અમલવારી અર્થે :-

- સફાયક કમિશનરશ્રીઓ (તમામ)
- શાખાધિકારીશ્રીઓ (તમામ)

#### ◆中央をかかない1005512中央を中央を

જદા<u>રી કાર્યરીની અમિનીયમ ૧૯૭૩ (૧૯૭૪ના નંગ) ની કલમ ૧૪૪ અન્વચે શહેલ ૬૬મ</u> કમાંક એસ.બી/મ**ફ**જર/જાહેરનામુ/મેડેઉજર૦૧૪,

મજુર/જાકરના છું/ ખેડા-જ સ્વારક પોલીસ કમિશ્રાસીની કપેરી. રાજકોટ શહેર,સજકેટ. તા. સ્કેલ્ડ / સ્વારક

લાઈનારમાં રાજકીટ શકેરમાં ઘરમાંક શેરીના બનાવો વસલા પાસેલ છે ભુતશળનાં રાજકેટ શકેરમાં બનેલ ધરશેડ શેરીના બનાવોની તપાસ કરતા તપાસમાં આવા ગુન્હે કરવાન (લાઇકિંગ) પક્કાયેલ છે. ત્યારે તપાસમાં આવા ગુન્હ વાલ: આરોપીઓ ગુન્હાના બનાવના દિવસો અગાઉ રાજકેટ સ્ટેટમાં નવા બંધાતા ગક્કનોમાં જુદી જુદી. એપોગીક દાનીઓમાં, કોપેરિયનમાં મજુરી કામ અને ટેલીફોન કંપનીઓ આર્ગ ત્યા ગૈસ પાઇપ લાઇન માટે ખેદાતા ખાડાઓની પ્રજુરી ગ્રામ મેળવી અથવા તેના બહાના કેઠળ આવી રોકાલ કરી આપ્યાજની સ્થાનિક પરીચિતીનું સર્વે કરી માકિતલાર શત મિલ્કત વિરૂપ્યાના ગુન્ફઓ આપરતા કેવ છે. મજુરી કાયના મહાના ફેઠળ આતંત્રવાદીઓ પણ આશરો મેળવી લેતા પ્રશ્ન છે કેશી જાફેટ જનતાની જન-માલ (મિલ્કતોની સલામની તથા દ્વારા કાફ શોડા નિયંત્રથી મુકલ જરૂરી જ્યાર છે.

જેશી કું મોઠળ આ (૧.૧.૬.). પોલીસ કમિલર, રાજકોટ શહેર કોજદારી કાર્યકીની અધિનીયમ (સી.આર.પી.સી.) ૧૯૭૬ (૧૯૭૪ ના નંદ) ની કલમ ૧૪૪ મન્વાયે અમેંને પહોલ કહાનાં કહ્યે આવી કું ફુકમ કર છુ કે, રાજકોટ શકેરના પોલીસ કમિલન વિસ્તારમાં લેવર કોન્ટ્રાક્ટર/મુકદમનાઓંએ ખેતાની પાલે જે પજીર કામે સખેલ હોય અને મજુરો કામકાજ માટે સખ્લાય કરતા હોય તેઓએ નીચે જણાએલ કોમે મુજબ દરેદ 'જૂરોના માલઝ-અલગ ક્ષેમે અથે કરજીયાત પાટે સ્થાનીક પોલીસ સ્ટેશનને જણા કરવાની રહેશે તથા મેજુરો જ્યારે મજુરી કામ તથા રાજકોઢ શહેર છોડી જતા રહે ત્યારે લેબર કેન્દ્રાક્ટર/મુક્ડદેવે તે બંગેની જણા નામ/સરનામાં સહિતની લિંગન શાર્ણ સ્થાનીક પી.રેટ.માં કરવાની રહેશે

| į. | લેબર ક્રીન્ટાક્ટર / મુશકર (સપ્લાચર) નુ પુર નામ લરનામું<br>મો.ને., નેબર સર્કિલ | #    |  |
|----|---|------|--|
| ,  | মস্কুল লাম নথ উ.ব.  | 1-1- |  |
|    | મજુરનું હલાનુ સરનામુ દેલીફોન નેલર   | te.  |  |
| v/ | પઝુરનુ પૂળ વતનનું મરનામું ગામ, તાલુકો, જીલ્લો                                 | -    |  |
| 4  | રાભની મજુરીનુ સ્થળ / કંપનીનું નામ   | 120  |  |
| 9  | पकुरन् चलनन् स्थानीड भी स्टे.म् नाम तथा देशीक्रेन नेवर                        | 100  | 111 - 3 102 II - 111 - 1 |
| é  | મજુરના વલતના આગેવાનનું નામ, સરનામું, દેલીઉન નવર                               | 1    |  |
| C  | મજુર અગાઉ કોઇ પોલીસ ગુન્ફામાં પ્રકડાયેલ ટીચ તો તેની                           | 10-1 |  |
|    | Goin  |      |  |
| 0  | क्रमाहरी गुड़ाहरी / केंसाकहरे स्क्रुटी क्रम मार्ट लागेल छ                     | 110  |  |
| 10 | નહેડને બાુપામ પાલની આસરા તૈકે (ક્રુદ્ધા લાઇ વો)                               | 100  |  |
| 17 | राष्ट्रकेट कटेरमां का लारीमधी मधुरी धम करे छे १ अने ३६                        | 188  |  |
|    | તારીપે જવાનો છે ?   |      |  |
| 92 | ગજકોઇ શહેરમાં નજીકના સંબંધી કોઇ ફોંચતો તેનું નામ                              | 10-1 |  |
| 1  | 원린에(작   |      | 20   |

આ ફેક્સ ના ભગભગ ૧૦૧૪ થી ના ૩૦/૦૯/૧૦૦૪ મુદ્દી લમગામ ૧**૪૭**.

માં ફુદમની ભેર કરનાર <del>વ્યક્તિ</del> ભારતીય દંડ સહેતાના કલામ તટદ મુ**જબ શિકાને પાત્ર શકે**.

- The second

- 21/2001-

902

તમાનને વ્યક્તિગત રીતે એકિંગની ખરવાળી કરવી શક્ય ન હ્યા આદી એક્લરફો ફક્મ કરે છું. જાર્કર જનના કરણ સાફ સ્થાનીક વર્તમાન પત્ર આકળવાળ અને દુરદર્શન કેન્દ્ર મારફતે પ્રસિધ્ધી ધ્વારા તાથ મોલીસ લેશનેના પોલિક સન્મોક્ટર, મહદનીશ પોલીસ ક્રમિક્ટ નાવાદ પોલીસ ક્રમિક્ટ તથા પોલીસ કરિક્રાટ કરોરીના એટિશ ભેંડ ઉપર ફુલમાને મહદા વીલાડી પ્રસિધી કરવામાં આવશે તેમાં પ્રદેશાદથી કોઇ શકાય તેની જારૂંત જગ્યામાં ઉપર ફુલમાની મહતા વીલાડી પ્રસિધી કરવામાં આવશે તેમાં પ્રકાર કલાય ૧૯૩ મુજબ પોલીસ અધિકારીએ પણ આ ફુકમાની જાર્ટસાલ અધિકૃત ગાલકે.

આજ તાર્રિકમાટ્ટ પૈયોલ-૨૦૧૪ તા રાજ માટે લઈ અને સિક્કો કરી આવેલ છે.



જમિકન આ પોલીસ કમિલ્ડ રાજકોટ શહેર રાજકોટ

#### 439.2964

- (१) अञ्च स्थितनी, कृड विकास, कांधीलका.
- (e) પોલીસ મહાનિદેશક અને મુખ્ય પોલીસ માંગલારીલી, ગુ. રા. ગાંધીનાગલ
- (૩) અધિક પોલીસ મુકા સિર્દેશકર્યા (ઇપ્લે.) ગુરા ગાંધોનગર.
- (W) पालीस क्षित्रहर्श, अमहादार गाँउर, पार्टीका गाउर, सुरत शहर.
- (प) णाझ मुख्य चेलीस अधिकारीची, राष्ट्रचंड केल्ड, राष्ट्रमेंद्र,
- (4) कुल्ला पोलीस समिलकर्गी, संस्कृत हुए । एक्वीट
- cán slávet llassafia (a)
- (८) म्यूनिशियस हिम्बरकी, संपक्षीर पान-
- (૯) વિશામકર્યા, માર્સનો માતું રોજીવર જ વકાર કરવા મુના સ**વિયાલય ખોક ને**.વ. પ્રીજા મામે.વ.સ. ગાંપીનગર
- (९०) भूद्रकार भश्रमात्री व्यक्तिसभी, श्रेसम्बर पार्ट पाणावाद.
- ુવવા મેનેજરથી, ભલેમેન્ટ પૈસ, રાજકોંડ હોરોડ લાગભ માં, પશ્ચિમ્ધ કરવા માછે.
- (१२) भारतनीक पीलीय अभिवासी एवं, महिल जिल्ला, रास्कीट शहेर.
- (93) with allwash, (672); sevelo discon, econo.
- (૧૪) આરામ પોલીસ અધિકાકમી ત્યાં હતા છે. વસ્ત્રોક જેવે જેશન પી.સે.
- (૧૫) નમામ પૈ.સ્ટે.ઈન્સાર્જમીઓ, રાજકોડ જોડાંગકારી ચીટાડી લાઉક સ્પીકર વારુખ દવારા જાહેરાન કરાવવા શક્
- (१६) नमाम ऋतीर तथा गामा छन्यानंत्रीका, तन्त्रांट सहर.
- (૧૭) ક-ફોલ ઈ-ચાર્જથી, રાજકોટ ગફર લાઇ નકલા વર્તમાનપત્રીને આપલી.
- (१८) विवर कमिन्नशर्मी, ... तमा- भागली सम्प्रकानि भवजात करववा साह

#### नक्षा अविनास श्वाना-

- (૧) રજીસ્ટ્રારમી, કાઈકોર્ટ, ગુ.રા.સીસારોક પ્રગામાના
- (૨) વજારમારથી, દીસ્ટીક્ટ એન્ડ સંશબ્ધ કોઇ, સંજગ્ને
- (૩) વજીસ્ટારથી, શીક જ્યુડીકરલ ચૈલાના ટાન ગયાદીટ.
- (४) क्युक्ट्रावकी, मेडीबाद मेशक्स १९५ केंद्र गांवरीत.
- (પ) એક્ટલેકપૂરીય મેજી.સી. સંપ્રદોર શહેર
- (६) व्येक्टप्रकथ्दीय मेक्टबी, सफ्डोट त लुंडा
- (૭) સર્યુકત માઠીની નિયામાનની, રાજકાર

(સ્થાનીક દાર્તમાનુપત્રો, અહારાવાળી લાગ કરાયેન કેન્દ્રમાં દ્રસિધ્ધ કરવા અને વર્તમાનપત્રોની કાપલીએ મેઠલવર સફ

800



# રાજકોટ મહાનગરપાલિકા

હિસાબી શાખા

ડૉ.આબેડકર ભવન, હેબરભાઇ રોડ, રાજકોટ - 350 001.

सम्बद्धातिकान हरी

AL 951 512010

नीध -

વિષય - Vendor Regi. માં GST No. Update કરવા બાબત

ઉપરોક્ત વિષયે જ્યાવવાનું કે રાજકોટ મકાનગરપાલીકા નાં તમામ વેન્ઠર / કોન્ટ્રાક્ટરો ના Vendor Registration માં GST No. ની જરૂરીયાત હ્યેય તાત્કાલીક અપડેટ કરવા વિનંતિ. Temporary Vendor નાં Regi આપની શાખામાં જ શક જશે જ્યારે Permanent Vendor નાં GST No અપડેટ કરવા શાખા અધિકારીશ્રી નાં જરૂરી સહી સીક્કા સાથે નીચે મુજબ વિગત નું પત્રક બનાવી દિવસ – ૭ માં ઢિસાબી શાખામાં માહિતી મોકલાવી આપવા વિનંતી.

| Vendor Name | Exiting Vendor Regi.<br>No. | PAN | GST NO. |
|-------------|-----------------------------|-----|---------|
|             |                             | -   |         |
|             |                             |     |         |
|             |                             |     |         |

Self of C2)

(જર્મ ચીફ એકાઉન્ટન્ટ રાજકોટ મહાનગરપાલીકા

નોંધ - તમામ વિગતો ચકાસીને અપડેટ કરવી / ચકાસીને મોકલવી અન્યથા સપ્લાયર્સ ને TDS ની

हेडीट मणशे नहीं छेनी नोंध लेवा विनंती

2

नहल अमलवारी थर्थे

' 🖁 1. તમામ શાખા અધિકારીશ્રી ઓ

## नडल सविनय श्राप्त अर्थे

- 1. માન. કમિશ્વર સાફેબશ્રી
- 2. માન. નાયબ કમિશ્નર સાફેબગ્રી

## જાહેરનામ

આથી હું અમિત અરોરા (IAS), મ્યુનિસીપલ કમિશનર, રાજકોટ મહાનગરપાલિકા, રાજકોટ ગુજરાત પ્રોવિન્સીયલ મ્યુનિસીપલ કોર્પોરેશન એકટ-૧૯૪૯ની જોગવાઇ અનુસંધાને મળેલ સતા મુજબ, જાહેર હિતને ધ્યાને લઇ, રાજકોટ મહાનગરપાલિકા વિસ્તારમાં ઇમારત તોડવા, સમારકામ અથવા તો નવા બાંધકામ દરમ્યાન ઉપસ્થિત થતા બાંધકામએ લગત કચરા (Construction and Demolition Waste) નો રાજકોટ મહાનગરપાલિકા હારા નિયત કરાયેલ જગ્યા સિવાય નિકાલ કરવા પ્રતિબંધ ફરમાવું છું.

એવું ધ્યાનમાં આવેલ છે જે, રાજકોટ મહાનગરપાલિકા વિસ્તારમાં ઇમારત, ઇમારતોના બાંધકામ દરમ્યાન નળીયા, પથરા, ઇટો, ઇમારત બાંધવાના માલ સામાન અને એવા માલ સામાનનો કાટમાળ ગમે તે જગ્યાએ નિકાલ / એકઠો કરવામાં આવે છે. જેનાથી એવી જગ્યાએ ઉંદરો અથવા અન્ય જીવ જંતુઓનું આશ્રય સ્થાન અથવા ઉત્પતિ સ્થાન બને છે. તેમજ સદરહું જગ્યાનો ભોગવટો કરનારાઓને અથવા પડોશમાં રહેતી વ્યક્તિઓના ભય અને ઉપદ્રવનું કારણ બને છે. તેના કારણે રોગયાળો ફેલાવવાનો ભય અને લોકોના આરોગ્ય તથા જાનમાલને નુકસાન થાય તેવી સ્થિતી ઉત્પન્ન થાય છે. તેમજ તે કયરો (Construction and Demolition Waste) દ્દર કરવા રાજકોટ મહાનગરપાલિકાને ખુબજ મોટો ખર્ચ થાય છે, તેમજ માનવ સમય બગડે છે. આમ, લોકોના જાનમાલના અને આરોગ્યના નુકસાનના ભોગે આવી ગેરકાયદેસર પ્રવૃતિ ચાલી રહેલ છે, આવી કોઇપણ પ્રવૃતિ જન આરોગ્ય માટે બિન સલામતી નોતરે તેમ હોય, ગુજરાત પ્રોવિન્સીયલ મ્યુનિસીપલ કોર્પોરેશન એકટ અનુસ્યી-ક ના પ્રકરણ-૧૪ ની જોગવાઇઓ અનુસંધાને આવી તમામ પ્રવૃતિ કરવાનો અગાઉના જાહેરનામા નં.રા.મ.ન.પા./મ.ઝો./સો.વે.મે./જા.નં.૧૯૪૧, તા.૦૬/૦૮/૨૦૧૯ થી પ્રતિષેધ કરમાવવામાં આવેલ અને આવા કચરા (Construction and Demolition Waste)ના નિકાલ માટે રાજકોટ મહાનગરપાલિકાએ નીચે દર્શાવેલ સ્થળો નિયત કરવામાં આવેલ.

- ૧. કોઠારીયા પોલીસ યોકીની બાજુમાં પથ્થરની ખાણ પાસે,
- ર. રૈયા સ્માર્ટ સીટીના તમામ ખાણ વિસ્તાર,

6

- 3. ટી.પી.સ્ક્રીમ નં.૧૦, એફ.પી.-૮૭, ઢેબર રોડ, સાઉથ અટીકા વિસ્તાર, પી.જી.વી.સી.એલ. ઓફિસ પાસે,
- ૪. ટી.પી.સ્ક્રીમ નં.૨૩, એફ.પી.-૨૩, મોરબી રોડ,પોપટપરા આઇ.ઓ.સી. ગોડાઉન પાસે,
- ૫. સમાટ ઇન્ડ. એરિયા, એસ.ટી. વર્કશોપ પાછળ, અનામત પ્લોટ,
- ક. ટી.પી.સ્ક્રીમ નં.૯, એફ.પી.-૫, રૈયાધાર ગાર્બેજ ટ્રાન્સફર સ્ટેશન પાસે,
- ૭. ટી.પી.સ્ક્રીમ નં.૨૦, એફ.પી.-૩૫, પ્રધ્યુમન ગ્રીન પાછળ

ઉપરોક્ત સ્થળો ઉપરાંત નીચે મુજબના સ્થળો Construction and Demolition Waste ના નિકાલ માટે નિયત કરવામાં આવે છે.

- ૧. જેટકો ચોકડી, ટી.પી.સ્ક્રીમ નં.૨૮, મવડી, એફ.પી.-૪૬/એ,
- ર. ટી.પી.સ્ક્રીમ નં.૧૨, કોઠારીયા નેશનલ ફાઇવે, લીજજત પાપડ પાસે, એફ.પી.-૩૮/એ, ૩૯/બી.

ઉપરોકત નિયત કરેલ સ્થળો સિવાય અન્ય કોઇપણ જગ્યાએ કોઇપણ ઇસમ/ઇસમો છકડો, ટ્રેકટર અથવા ડમ્પર દ્વારા (Construction and Demolition Waste) નો નિકાલ કરતાં પકડાશે તો પ્રથમ વખત છકડો/ટ્રેકટર દીઠ રૂ!.૭,૫૦૦/- તથા ડમ્પર દીઠ રૂ!.૧૫,૦૦૦/-, બીજી વખત છકડો/ટ્રેકટર દીઠ રૂ!.૧૫,૦૦૦/- તથા ડમ્પર દીઠ રૂ|.30,000/- અને ત્રીજી વખત છકડો/ટ્રેકટર દીઠ રૂ|.૫0,000/- તથા ડમ્પર દીઠ રૂ|.૧,00,000/-લેખે વહીવટી ચાર્જ વસુલ કરવામાં આવશે. તેમજ વાહન જપ્ત કરવા સુધીની કાર્યવાહી કરવામાં આવશે.

શહેરમાં વસતાં નાગરીકો દ્વારા ઉપરોક્ત Construction and Demolition Waste ના નિકાલ માટે રાજકોટ મહાનગરપાલિકા દ્વારા ઝોન વાઇઝ કામગીરી માટે Construction and Demolition Waste સેલની રચના કરવામાં આવેલ છે. શહેરના નાગરિકો રાજકોટ મહાનગરપાલિકાના કોલ સેન્ટર — ૦૨૮૧-૨૪૫૦૦૭૭ પર ફોન કરી તેમની મિલ્કતનાં રીપેરીંગ કે કાટમાળનો નિકાલ નીચે મુજબનાં નિયત થયેલ યાર્જીસ ભરપાઇ કરી નિકાલ કરવાની વ્યવસ્થાનો લાભ મેળવી શકશે.

- रीक्षा डे १/२ ट्रेडटर ३|.300/-
- ટ્રેક્ટર જેટલો જથ્થો રૂા.૫૦૦/-
- ટ્રક / ડમ્પર જેટલો જથ્થો રૂ.૧,૦૦૦/-

ઉપરોક્ત નિયત કરાયેલ સ્થળોએથી ખાનગી માલિકો, જુનો એકત્રિત થયેલ બાંધકામનો કાટમાળ પોતાના ઉપયોગ માટે સ્વખર્ચે ઉપાડી લઇ જઇ શકશે.

ઉકત જાહેરનામાનો યુસ્તપણે અમલ કરવો.

રાજકોટ. તા. **4** / **6**/૨૦૨૨

> ો રાજકોટ મહાનગરપાલિકા

HOW MAIN REG HOOR! X CAC

स्त्रि क्यों के के सिम्बर्ग करेंगे के प्राप्त करें नोधारी करान के के देंगे के के सिम्बर्ग मांधीनगर के के शिक्तकर

- જિલ્લા ઇટલર**માંના કવરા,** <sup>ક્લા</sup>યા સામે **અને મકાન વિભા**મ જિલ્લા

> વિષય: કરારખત પર સ્ટેમ્ગ ક્યુ**ટી વસુવાત ભાગત.** સદર્ભા:– આપની કચેરીનો તા. 30/**૭/૨૦૦૯માં પ**ત્ર

ાપરાંકત વિષય અને સંદર્ભ પત્ર ધ્વારા આપની કવેરી ધ્વારા 'કરાર અને' પર પત્ની ત્રાપ્ય કપુટીના માર્ગદર્શન બાબતે જણાવવાનું કે, અગેની કચેરીના પશ્ચિમ ને સ્ટેપ્ય પત્ર જિલ્લા/હલંહ તા. પાંચ ૧૦૦૭ ના પરિયજ ની નક્ષ્ય પોકલવાયા આવેલે કોના પેસન અને પરીમાં જણાવેલ ક્ટેમ્ય કપુટી વાપરવાની શાય છે.

AUG 2000 Service and Service a

....

- પત્રની નકલ

સુષ્ટ્રિ,ઓફ સ્ટેમ્પસની કચેરી, સ્ટેમ્પ અને નોંધણી ભવન, સેક્ટર-૧૩-સી, ખ રોડ, ગાંધીનગર.


-: KY ] Y

અત્રેની કચેરીનાં ધ્યાન ઉપર આવેલ વિગત મુજબ ગુજરાત રાજ્યમાં આવેલ જીલ્લા પંચાયત, નગર પાલિકાઓ તરફથી કરવાના થતા બોધકામ તથા અન્ય કામો માટે ટેન્ડર બહાર પાડી. કોન્ટ્રાકટરો પાસે કામગીરી કરાવવામાં આવે છે. આવી કામગીરી માટે જે કોન્ટ્રાકટરનું ટેન્ડર મંજુર કરવામાં આવે છે. તે ટેન્ડરની અંદાજીત રકમ પૈકી નિયમોનુસાર અનામતનો (સાકપુરીટો – ડાપોઝાટની ) રક્રમ લેવામાં આવે છે. તે અંગે જીલ્લા પંચાપત / નગરપાલિકા / મહાનગરપાલિકા અને કોન્ટ્રાકટર વચ્ચે કરાર કરવામાં આવે છે. આવા કરારો સ્ટેમ્મ :યુટીના અભિપ્રાય માટે અતે રજુ કરવામાં આવે છે. તેમાં જે ડિપોઝીટની રકમ અનાવન મુકવાની થાય છે. તે રોકડ, ચેક, ડીમાન્ડ ડ્રાકટ બેંક ગેરંટી ફિક્સ ડીપોઝીટ રીસીપ્ટ એન.એસ.સી. બચતપત્ર વિગેરે પૈકીના એક યા વધુ માધ્યમથી આપવામાં આવે છે. તેમાં ટેન્ડર ગન્વયે કેટલી ૨કમ સીકપુરીટી ડીપોઝીટ મેટે મુકવાની છે અને કથા માધ્યમથી મુકવામાં આવે છે. તેની પુરંપુરી વિગત રજુ કરેલ ન હોય તો આવા કેસોમાં પુરેપુરી વિગત રજુ કરવામાં ન આવે ત્યાં સુધી અભિપ્રાય આપી શકાતો નથી અથવા વિલંબ થાય છે. આવી પરિસ્થિતિ નિવારવા અને ટેન્ડરની રકમ અનાયે જે કરાર કરવામાં આવે છે. તેમાં નીચેની વિગતે સંદય્ય ડયુટી લેવાની થાય છે.

(૧) અનામતની જે ૨૬મ રોકડ, ચેક યા ડ્રાક્ટથી લેવામાં આવે અથવા તો બેંક ગેરંટીથી આપવામાં આવે તો કરારનાં લેખ ઉપર મુંબઈ સ્ટેમ્પ અધિનિયમ –૧૯૫૮ની અનુસુચિ–૧ ના આશંકલ –૫ (ઝ) મુજબ કરાર ઉપર રા. ૧૦૦/– સંસ્પ હયુટી વાપરવાની થાય છે.

(૨) ટેન્ડર અન્વયે જે અનામતની ૨૬મ ફિક્સ ડીપોઝીટ રીસીપ્ટ, એન.એસ.સી. યા અન્ય કોઈ બચતપત્રના માધ્યમ થી અનામત મુકવામાં આવે તો તેટલી. અનામતની ૨કમ ઉપર મુખઈ સ્ટેમ્પ અધિનિયમ- ૧૯૫૮ની અનુસુચિ-૧ ના આર્ટીકલ -૩૬ (ક) સાથે આર્ટીકલ ૨૦ (ક) મુજબ આ રીતે આપવામાં આવેલ અનામતની રકમના પ્રત્યેક રૂા. ૧૦૦/– અથવા તેના ભાગ માટે ૪,૨૫% પ્રમાણે સ્ટેમ્પ ડયુટીને પાત્ર બને છે.

આપના તરફથી જે કામો માટે ટેન્ડર બહાર પાડવામાં આવે અને તેમાં ટેન્ડરની રક્ષ્મ અન્વમે જે ૨૬૫ ડિપોઝીટ (અનામત) મુકવામાં આવે છે. તેમાં ઉપર દર્શાવ્યા મુજબ રોલ ડ્યુરીને પાત્ર બને છે. તે મુજબ અમલ કરવા વિનતી છે. સાથોસાથ આપના ધ્યારા



કોન્ટ્રાકટરને વર્ક ઓર્ડર આપવામાં આવે તે સમયે કરારનામાં ઉપર ઉકત વિગતે યોગ્ય સ્ટેમ્પ ડયુટી ભરપાઈ કરેલ છે. કેમ ? તેની પ્રકાસણી કરવા પણ જગાવવામાં આવે છે.

પ્રતિ, એ ૧) લ્લા ક્રિકા કાર કર રહે વિક્રિકિટ (જે) જીલ્લા વિકાસ અધિકારી, જીલ્લા વિકાસ અધિકારીની ક્રયા અધિક સુપ્રિ ઓક રોગ્યા ાજરાત રાજન સામાન

(૩) મ્યુનીતા પલ કમિશ્નરશ્રી, મ્યુ. કમિશ્નરશ્રીની કચેરી

(૪) તોક ઓફિસરાંગી તમામ નગરપાલિકા કચેરી, ...િપાલેટ )..... જી. ૨૧૫૬ો ટ્રે.

्री इतिकारः । स्थानवर्षाः क्षाप्तः



### RAJKOT MUNICIPAL CORPORATION ACCOUNTS DEPARTMENT

Room No. 4, 2<sup>nz</sup> Floor Dr. Ambedkar Bhavan, Debar Road, Rajkot - 360001

# PARTY/VENDOR REGISTRATION FORM

| VENDOR CODE            | j                 | A STATE OF THE STA |
|------------------------|-------------------|--|
| Party Name             | 4                 |  |
| Authorized Person      | ‡                 |  |
| PAN Card No.           | 4                 |  |
| GST No.                |                   |  |
| Address                | *                 |  |
| City                   | 3                 |  |
| Phone No.              | 1                 |  |
| Mobile No.             | 4                 |  |
| eMail ID               | 1                 |  |
| Website                | 1                 |  |
| Area Of Work           | -:                |  |
| Bank Details (attach o | copy of cancelled | d cheque)  |
| Bank Name              |                   |  |
| Branch Name            |                   |  |
| MICR Code              | 3                 | IFSC Code :  |
| Account Type           |                   |  |
| Account No.            | 7                 |  |

- Any vendor while filling a tender shall quote registration details; if he is not registred he
  will give fresh details along with tender.
- (2) Acounts branch will designate a person who will keep the forms and also authorize new registrations or edit existing registrations.

TO,
CHIF ACCOUNTANT,
ACCOUNT DEPARTMENT,
RAJKOT MUNICIPAL CORPORATION

THE ABOVE MENTIONED DETAILS FOR VENDOP, REGISTRATION HAS BEEN VERIFIED BY US & FOUND CORRECT. KINDLY REGISTER ABOVE VENDOP.

SIGN NAME DESIGNATION DEPARTMENT NAME m = 9599

पश्चिपत्र -

विषय - ता. 01/10/2016 थी कु.એस.टी. टी.डी.એस. श्री कपात जाजत संहर्स - (1) Gol. MoF (Department of Revenue) Central Board Indirect Taxes and Customs Notification No. 50/2018-Central Tax

(2) GoG. Finance Department Notification No. 50/2018-State Tax

उपरोक्त विषय समें सहलें गुकरात गुइस केन सविस रक्ष केन्द्र, २०९७ तथा सेन्द्रल गुइस केन्द्र सर्विस रेक्ष केन्द्र, २०९७ मी डलम ५९ जनुसार इ. २,५०,००० थी वधु रङ्मना वैरापात्र बीक्वस्तुओं जरीहे डे वेरापात्र सेवाओं डेन्ट्रान्ट्यी मेणवे तो इल २९ (बे टका) हेक्ष डीडन्सन जेट सोसं (का केसरी टी डी केस) अपवानी थाय छे.

આમ ઉપરાક્ત બાબતો ધ્યાને લઇ વધારાની રજ્ઞ ની વધારાની નિયમો બનુસાર બિલમાંથી તા ૦૧/૧૦/૨૦૧૮ થી જી. ચેસ.ટી. ટી.ડી.એસ. ની કપાત કરવાની થાય છે.

> નાયબ કમિશ્વર સજકોટ મહાનગરપાલિકા

भिडाए - GST FAQ's लड़ल सचिनय श्राष्ट्र अर्थे-

- (૧) માન કમિશ્વર સાહેબશ્રી
- (૨) માન નાયબ કમિક્સ સાદેબશ્રી (વે.ઝોન, ઇ.ઝોન)નકલ અમલવારી અર્થે-
- (૧) તમામ શાખા અધિકારીથી

36187189

શ.મ.ન.પા.લીગલત્કા.નં.15>1


संस्कृतिः भागन्त्रप्रस्थातिकः स्रोजस्य भागत्त्र स्राज्ये- १५-दे १६०५०

# परिपत्र :

विषय: ध्रापी क्षेष्ठ, योश्रमा अंतर्शत आपवानी ध्रती माहिती

રાજકોટ મહાનગરપાલિકાની જુદી-જુદી શાતાઓમાં કરજ બજાવતા કર્મવારી ક લાગ ઇ વો લક ચોજના લાગુ પડે છે. અથવા તો જેઓને એક વખત આ વોજના લાગુ પડી ગયેલ કેવા તે બંબોના ઇ વી લેક. એકાઉન્ટમાં કે વાચ સી (૯,૧૯) ફોર્મમાં આધાર કાર્ડ, પાનકાર્ડ લેક બેકાઉન્ટની લિંદનો હવા લેબાઇલ જલ્દ અપડેટ કરવાના બાકી ફોય તેનું લીસ્ટ ઇ પી એક, કચેરીમાં જે કર્મચારી/એકાઉન્ટ ડેલ્ડરની જરૂરી લિંદનો પૂરી વાડવાની ચાય છે. તથા અઝેશી આ કામગે શિલ્ડ એકાઉન અર્થ નિયુક્ત કરવામાં આવેલ મેનલ એકવોકેટ તરફશી ઇ-મેઇલ મારફતે ચાદી પૂરી પાડલ છે. જે આ લઇ સામેલ છે. સદરફ લિંદના કર્મચારીઓની વિગત સંબંધિત શાળાએ દિનનર માં પેલલ લેડવોકેટ જાલ્લ કન્સલ્ટન્ટ ને અચુકપણે પર્ફોયતી કરવાની શાય છે.

આ ઉપરાંત રાજકોટ મહાનગરપાલિકાની યુદી-જુદી પ્રાપ્તાઓ દ્વારા તમને ૨૦૧૧ થી આજોદ કર્યો કેન્દ્રાકરો મારફતે કાર્ય કરાવેલ કોય જેમાં માનવશ્વમનો ઉપલીગ કર્યો કોય. તે તાલવીલ કિન્દ્રાક કરાવેલ કે કે કે મેં તેની ખરાઇ બાદ જ સામિતિ કેન્દ્રાકરાર સીઓના બીલ પાસ કરવા અગાઉ સુપ્રના આપવામાં આવેલ હતી. જેને કરીની કરક અન્યોન સુપ્રના આપવામાં આવે છે. સંબંધિત કેન્દ્રાક્ટરોની તમા તેઓ કસ્તકના શ્રામિકોની છાંયો વેલ કરેલો નાસ્ત્રી આવેલ પત્રમાં દર્શવેલ વિગતો તાતાલીક અસરથી પેનલ વેલવીકેટશીને દિનવ્ય માં પ્રાપ્તિ કરવા દાવા સામિપ્રીકારીને સુપ્રિત કરવામાં આવે છે.



सर वर्ष विज्ञत निधान सम्बन्धातामां न प्रतिभवाना संकारोंमां क्षस्य ने क्षिण को नेट विज्ञती मीकारण क्षणाने सम्बद्धित सर्वाविक्षरीजी व्यक्तियत स्वावसारी महने क्राव्य क्षणाते. केट विज्ञती मीकारण क्षणाने सम्बद्धित सर्वाविक्षणी व्यक्तियत स्वावसारी महने क्राव्य क्षणाते. केट विज्ञता मिन्द्राकार नथा तेच्ये कस्तवना समितिनो विज्ञते कोष्ट्रा यक्षसारी केट निधान करेट समयमबाहामां पेनान विक्रविक्रेन प्रतिवती करती. तथा तेनी काष्ट्र सीमल सामाने करती

ઉપરાક્ત પરિપત્રના યુસ્તપણ તાલાલિક બલરથી અમલ કરવી

नक्ष्म सचित्रय व्यामा :-- मान अभिक्षत्र अर्थय - नाथज अभिक्षत्र रक्ष और से और।

नमाम शामाधिमही (कामलसाई)

પેનલ એકલોકેટનું લરમામું થયા કોનેલ્ડનો યુવર એકલેટ કરોડ રાગીર શેડ. સાથકલ ગીન ઉપર સમકોઢ, કોન ને, સ્ટક્ટેક્ટ્લ ्र संस्कृत महास्वतंत्रमाहितः स्थाप स्थापम

नीय मजायत क्रीन्यकारी ए पी क्षेत्र क्षेत्र तथा ए क्षेत्र आए केस्ट हेडल २५०२ मा न वर्तेला होत्र तेन्य तथाप क्रेन्यकारीना जीली ओडीट तथा हिमाजी शाजाकी पंत्रुट इटला नहीं

C-38J-

સમસ્યાત્રનીગલાજાતને ૧૯૫૯

રાજકોટ મહાનગરપાલિકા લીગલ શાખા તા*રા*ંગ્ર /૨૦૧૭

4111:

તમાણે : લીગલ ફાઇલ નો.૩૭૧/૨૦૧૬-૧૭

રાજકોટ મહાનગરપાલિકાની કામગીરી માટે જુદી-જુદી શાળાઓ વ્રાસ કામગીરીના પ્રકારને ાયાને લઇ નિયમ અનુસારની પ્રક્રિયા અનુસરીને એજન્સી/સપ્લાયર/કોન્ટ્રાકટર સાથે જોગવાઇઓ - મહાનંતર કરાર કરવામાં આવે છે. મહાનગરપાલિકાની કામગીરી સંદર્ભે તૈયાર કરવામાં આવતા દેન્કર/કરારનામામાં લખતો લખતની જરૂરીયાતને ધ્યાને લઇ આબીંદ્રેશન (Arbitration) ની જોગવાઇઓનો સમાવેશ કરવામાં આવેલ છે.

રાજકોટ મહાનગરપાલિકાની કામગીરી માટે કરવામાં આવેલ કરારનામાની શરતો અનુસંધાને અમુક એજન્સી/સપ્લાયર/કોન્દ્રાક્ટર દ્વારા છેલ્લા કેટલાક વર્ષોથી નામદાર હાઇકોર્ટ સમક્ષ આબીટ્રેટરશ્રીની નિયુક્તિ અંગે પીટીશનો કરવામાં આવે છે, જેના કારણે મહાનગરપાલિકાની કામગીરીના ભારણમાં વધારો થયેલ છે. અને સબંધિત અધિકારીશ્રીઓને વારવાંર અમદાવાદ ખાતે છજર રહેવું પડતું હોય તેના કારણે અગત્યના પ્રોજેક્ટો સહીત કચેરીની કામગીરી તેમજ પ્રજાકીય કામો ઉપર વિપરીત અસર થવા પામેલ છે, તેમજ અરજદારોને દેશન થવું પડે છે. આ અંગે કાયદાકીય, શાખાના અભિપ્રાય અને પ્રકરણની વિગતો જોતા આ કામે તૈકલ્પિક ઉપાય (allernate remody) ઉપલબ્ધ હોય મહાનગરપાલિકાના ટેન્ડર/કરારનામામાં આબીટ્રેશનની જોગવાઇઓને સામેલ કરવાનું ઉચીત જણાતું નથી.

આથી " રાજકોટ મહાનગરપાલિકાના કામે કરવામાં આવતા ટેન્ડર ડોક્યુમેન્ટ અને કરારનામામાં આબીટ્રેશન (Arbitration) ને લગત જોગવાઇઓ દુર કરવાનો," અને તેના બદલે 'ટેન્ડરની શસ્ત/કરારનામાની શસ્તના અર્થધટન સંદર્શે મહાનગરપાલિકાના કમિશનરશ્રીનો નિર્ણય આખરી અને બંધનકર્તા રહેશે," અને 'ટેન્ડરની/કરારનામાની શસ્તો અંગે કોઇ પણ બાબતે વિવાદ ઉપસ્થિત થયે રાજકોટની દિવાની અદાલતની હકમત રહેશે," તેવી શસ્તોનો મહાનગરપાલિકાના કામ અર્થે તૈયાર કરવામાં આવતા તમામ કામગીરીના પરિપત્રો/ટેન્ડર ડોક્યુમેન્ટ તેમજ કરારનામામાં સમાવેશ કરવાનો આથી હુકમ કરવામાં આવે છે.

આ ઠુકમનો અમલ તાત્કાલિક અસરથી યુસ્તપણે કરવો.

કમિશનર રાજકોટ મહનગરપાલિકા

નકલ રવાના જાણ અર્થે : નાચબ કમિશનરશ્રી (તમામ)

<sup>નકલ</sup> રવાના જરૂરી કાર્યવાહી અર્થે : તમામ શાખાધિકારીશ્રીઓ

રા.મ.ન.પા./ લીગલ/જા.નં. 122)

રાજકોટ મહાનગરપાલિકા લીગલ શાખા. રાજકોટ. તા. 2 દ/૦૮/૨૦૨૩

પરિપત્ર:

વિષય: ઇ.પી.એફ. તથા ઇ.એસ.આઇ.સી. બાબતેનો અભિપાય. સંદર્ભ: ૧) રા.મ.ન.પા./ફિસાબી/જા.નં. ૧૨૦૯ તા. ૧૦/૮૨૦૨૩ ૨) રા.મ.ન.પા. ઇન્વર્ડ નં. ૮૧૨ તા. ૨૧/૦૮/૨૦૨૩

ઉપરોક્ત તિમરા તથા સંદર્ભે અન્વચે જણાવવાનું કે, સંદર્ભ - ૧ અન્વચેના પત્રથી ફિર્સાબી શાખા દ્રારા ઇ.પી.એક. તથા ઇ.એસ.આઇ.સી. લાગુ પાડવા બાબતેનો અભિપાય માંગવામાં આવેલ હતો જે અનુસંધાને પેનલના એડવોકેટથ્રી તરફથી સંદર્ભ - રથી અભિપાય આવેલ છે. સદરકું અભિપાય રાજકોટ મહાનગરપાલિકાની તમામ શાખાને તથા શાખા હસ્તકના કોન્ટ્રાકટરોને લાગુ પડતો હોય જેથી સંબંધિત તમામ શાખાને સદરકું અભિપાય વંયાણે લેવા સુચિત કરવામાં આવે છે.

આ ઉપરાંત આપની શાખાના કર્મચારી તથા કોન્ટ્રાકટરશ્રીઓની ઇ.એસ.આઇ.સી. અન્વયેની માહિતી આપવાની બાકી હોય તે તમામે દિન - ૦૨માં પેનલના એડવોકેટશ્રીને માહિતી પહેચતી કરે અને માહિતી આપવાની બાકી હોય તે તમામે દિન - ૦૨માં પેનલના એડવોકેટશ્રીને માહિતી પહેચતી કરે અને તેની જાણ લીગુણ શાખાને કરે અન્યથા તેમાંથી ઉત્પન્ન થતી તમામ જવાબદારી માટે વ્યક્તિગત રીતે જવાબદાર ઠેરવવામાં આવશે.

સદરહું પરિપત્રનો તાત્કાલિક અસરથી યુસ્તપણે પાલન કરવું.

બિડાણ: સંદર્ભ અન્વચેના પત્રો નકલ સવિનય રવાના:

નાયબ કમિશનરશ્રી ( વે. ઝોન, ઇ. ઝોન ) તમામ શાખાશિકારીશ્રીઓ ( અમલ સારૂ )

> રાજકોટ મહાલગરપાલિકા એન્જ્રનીલ**ંગ વિભાગ** પ**્રિક**ોન ઇનવર્ડ નં. .2916....

નાયબ કમિશનરશ્રી રાજકોટ મહાનગરપાલિકા

My control

# Shraddha Associates

Corrosp. Add.:

LABOUR LAW CONSULTANT

502, Accurate Square, Tagore Road,

Nr. Atul Motors, Above Cycle Zone, Rajkot.

Ph. O. 2463380, 93767 68952 E-Mail : dodiaparag@yahoo.in



Prop. : Parag J. Dodi (Advocate & Labour Law Advisor Address : 2-Nalanda Bunglow 6-Pragati Society, Raiya Road, Rajkot-;

Ref.

Date:

-06-5053.

પતિ, લેબર ઓફીસરશ્રી, રાજકોટ મહાનગરપાલીકા, <u>રા જ ક</u>ો ટ.

વિષય :- <u>ઈપીએફ તથા ઈએસઆઈસી લાગુ પડવા રામનપા/હીસાબી/જા.ન.૧૨૦૯)</u>બાબતે અભિપાય. રેફ્ર. :- રા.મ.ન.પા./લીગલ/જા.નં. ૧૦૯૦, તારીખ ૧૦/૦૮/૨ં૦૨૩.

મે. સાહેબશ્રી,

સવિનય સાથ જણાવવાનું કે, ઉપરોક્ત વિષય અને રેફરન્સથી આપના તરફથી અભિપાય માંગવામાં આવેલ. જેની સાથે મોકલેલ ફોર્મેટ મુજબ વિગતવાર રીમાર્કસ આપેલ છે.

રાજકોટ મહાનગરપાલીકાનાં શાખા અધિકારીએ બીલ બનાવતી વખતે બીલ બનાવતી વખતે નીચે મુજબનાં ડોકયુમેન્ટસ ચેક કરી બીલ સાથે સામેલ કરવા જરૂરી છે.

દર મહીને લેવાનાં ડોકયુમેન્ટ.

- ૧. પગા૨૫ત્રક (જેમાં દરેક કર્મચારી તથા કોન્ટ્રાક્ટરની સહી/સિકકો અને જે તે શાખા અધિકારીની સહી/સિકકો)
- ર. હાજરી પત્રક. !
- 3. પી. એફ. ચલણ.
- ૪. પી.એફ. ઈ.સી.આર.
- પ. ઈ.એસ.આઈ.સી. પેઈંડ ચલણ.
- €. ઈ.એસ.આઈ.સી. લાગુ ન પડતો હોય તેવા કર્મચારી (રૂા.૨૧૦૦૦/− થી વધુ પગા૨વાળા) ની <u>WC</u> પોલીસી.
- ૭. પી.ટી. નાં ચલણ, (જે કર્મેચારીનો પગાર રૂા.૧૨૦૦૦/– કે તેથી વધુ થતો હોય તેનાં.)
   વાર્ષિક લેવાનાં ડોક્યમેન્ટ.
- 4. જો ૫૦ કે તેથી વધુ માણસો કોન્ટ્રાક્ટરમાં કામ કરતા હોય તો લેબર લાઈસન્સ.
- ર. લેબર વાર્ષિક પત્રક.
- ૩. બોનસ પત્રક.
- ૪. જે તે ડીપાર્ટમેન્ટને લાગુ પડતા સરકારશ્રીનાં લાયસન્સની નકલ ( ફુડ , ઈલેક્ટ્રીસીટી વગેરે )

દરેક શાખા હસ્તકનાં કોન્ટ્રાકટર / એજન્સી ઉપરોક્ત સંદર્ભ અન્વયે પાલન કરાવવાની જવાબદારી મુખ્ય માલીક તરીકે જે તે શાખાનાં શાખા અધિકારીની ઠરાવી શકાય.

સહકારની અપેક્ષા સહ.

આપનો વિશ્વાસુ,

બિડાણ :- ઉપર મુજબ.

SHRADDHA ASSOCIATES

PROPRIETOR 1 811-1

ellera órak ri. 78/2 nemel bras ri. -25/08/23

| ક્રમ | વારંવાર ઉદભવતા પશ્નો   | લાગુ પડે છે કે ફેમ ? |      |
|------|--|----------------------|------|
|      |  | EPF                  | ESI  |
| 1    | કોમ્પ્યુટર ખરીદી કરી અને રાજકોટ મહાનગરપાલીકાની જગ્યામાં<br>ઈન્સ્ટોલેશન કરવાનું થાય તો લાગુ પડે કે કેમ ?  | ના                   | ૃંહા |
| 2    | રાજકોટ મહાનગરપાલીકાની જગ્યાનું સંચાલન કરતા કોન્ટ્રાકટર, વેન્ડર<br>, ટ્રસ્ટ ને લાગુ પડે કે કેમ ?<br>સ્પોર્ટ સંકુલ, ગાર્ડન, પાર્કીંગ વગેરેનું સંચાલન કોન્ટ્રકટર, ટ્રસ્ટ સંસ્થા<br>વગેરે ધ્વારા કરવામાં આવે ) |                      | હા   |
| 3    | રસ્તા કામ, ડ્રેનેજ કામ, પાણી વિતરણની કામગીરી સાથે સંકળાયેલા<br>કોન્દ્રાકટરોને લાગુ પડે કે કેમ ?  | હા                   | હા   |
| 4    | જનરલ બોર્ડનાં માઈક સંચાલનનાં કોન્ટ્રાકટમાં લાગુ પડે કે કેમ ?   | હા                   | હા   |
| 5    | રાજકોટ મહાનગરપાલીકાનાં ગાઉન્ડ સંચાલન કરતા કોન્ટ્રાકટરોને લાગુ<br>પડે કે કેમ ?  | હા                   | હા   |
| 6    | અત્તઉટ સોર્સીંગ સ્ટાફનાં કોસ્સામાં વેન્ડરને લાગુ પડે કે કેમ ?  | હા                   | .હા  |
| 7    | રાજકોટ મહાનગરપાલીકાનાં રેનબસેરાનું સંચાલન કરતા કોન્ટ્રાક્ટરોને<br>લાગુ પડે કે કેમ ?  | હા                   | હા   |
|      | રાજકોટ મહાનગરપાલીકાની જગ્યામાં ઈવેન્ટમેનેજમેન્ટ કરવામાં આવે<br>ત્યારે ઈવેન્ટમેનેજમેન્ટ કંપનીને તથા ગાયક / આર્ટીસ્ટ / મ્યુઝીશીયનને<br>લાગુ પડે છે કે કેમ ?  | ના<br>,              | ના   |
| 9    | મશીન / વાહન ફક્ત પાર્ટસ ખરીદીનાં કિસ્સામાં લાગુ પડે છે કે કેમ ?  | ના                   | ના   |
| 10   | ) A 7 7m 2   | હાં                  | હા   |
| - 1: | મશીન / વાહન ફક્ત પાર્ટસ ખરીદી અને ફીટીંગ / રીપેરીંગ રાજકોટ<br>મહાનગરપાલીકાની જગ્યામાં કરવામાં આવતુ હોય તેવા કિસ્સામાં લાગુ   | ના                   | ના   |
| 1    | કોઈપણ ઈલેકટીક વસ્તુની ખરીદી તથા તેનુ ઈસ્ટોલેશન જમ કે કમેરા   | ના                   | ં હા |
| 1    | 3 મિત્ર મંડળ તથા સખી મંડળનાં કિસ્સામાં લાગુ પડે છે કે કેમ ?  | લા                   | .લા  |
| -1   |  | હા                   | ં હા |
| 1    | 5 ુર્સ / ઢાવેલ્સ ભાડે રાખવામાં આવેલ કાઈવર સહીત તેવા કીસ્સીમાં લાગુ   |                      | - 61 |
| 10   | ઈલેક્ટ્રીક પોલ ફીટ કરવા શિફ્ટ કરવા અથવા નવા ઈન્સ્ફોલ કરવા વગર  | લા                   | R    |

| 7   | એર કુલર, એ.સી. , વોટર કુલર રીપેરીંગ વગેરે કીસ્સામાં લાગુ પડે છે<br>કે કેમ ?  | હા          | . 61<br> |
|-----|--|-------------|----------|
| В   | રાજકોટ મહાનગરપાલીકાનાં કરાર આધારીત કર્મચારીનાં કીસ્સાંમાં<br>લાગુ પડે છે કે કેમ ?  | હા          | / 151    |
| 9   | રજીસ્ટેશન સમયે કુલ પગાર ઈ.પી.એક. / ઈ.એસ.આઈ.સી. નાં નિયમ<br>મુજબનાં પગારમર્યાદા કરતા ઓછી હોય પરંતુ ત્યારબાદ પગાર<br>ઈપીએક, ઈએસઆઈસી નાં નિયમ મુજબ પગાર મર્યાદા કરતા વધે તો<br>કયાં સુધી કપાત કરવી.<br>(ફ્રીક્સમાંથી કાયમીનાં કીસ્સામાં / ફ્રીક્સ પગાર વધી જાય તેવા કીરસામાં<br>) |             | ·11      |
| 20  | ફીકસ / કાયમી થાય તેવા કીસ્સામાં લાગુ પડે છે કે કેમ ?   | હા          | હા       |
| 21_ | વાલ્વ ઓપરેટર તથા પમ્પ ઓપરેટરનાં કીસ્સામાં લાગુ પડે છે કે કેમ?  | હા          | હા       |
| 22  | લીગલ, પોફેશ્નલ સર્વિસ રાજકોટ મહાનગરપાલીકાની જગ્યા પર<br>આપવામાં આવે તેવા કીસ્સામાં લાગુ પડે છે કે કેમ ?  | હા          | et       |
| 23  | રાજકોટ મહાનગરપાલીકા ધ્વારા વિડીયોગાફી / ફોટોગાફી કરાવવામા  | હા          | હા       |
| 24  | રાજકોટ મહાનગરપાલીકાની જગ્યામાં ઝેરોક્ષ મેશાન ચલાવ તેવા   | <b>-</b> 11 | -11      |
| 25  | ન્યુઝ પેપર અથવા કોઈપણ વસ્તુ કે જેની ખરીદી કરી હાય અને જ<br>રાજકોટ મહાનગરપાલીકાના પ્રીમાઈસીસ સુધી પહોંચાડવાની જવાબદારી  | •m*-        | ·u       |
| 26  | રાજકોટ શહેરમાં મોબાઈલ ડિસ્પેન્સરી ચલાવવા આપવાના આવે હત્ય   | હા          | - BL     |
| 27  | કીસ્સામાં લાગુ પડ છે કે કે કે કે કે કે લખત કામગીરી કરવાની હોય તેવા કીસ્સામાં લાગુ પડે છે કે  | •IL '       | ના       |
|     | ે કેમ !  | ં હા        | . હા     |
| 28  | આપેલ હોય તેવા કીસ્સામાં લાગુ પડ છે કે કર્ય :<br>રાજકોર મહાનગરપાલીકાની જગ્યામાં કાર્ટીઝ રીપેરીંગ તથા રીફીલીંગ   | હા          | , હા     |
| 30  | તેવા કીસ્સામાં લાગુ પડે છે કે કમ ?<br>કેટરીંગ સર્વિસ અથવા હોટલમાંથી ફુડ પાર્સલ તેમજ કુરીયર સર્વિસ<br>રાજકોટ મહાનગરપાલીકાને ડીલીવરી કરવામાં આવે તેવા કીસ્સામાં  | +11         | 411      |
| 3   | સોલાર પેનલ તથા રૂક ટોપ સોલાર પેનલના રાજકાટ   | (SL         | (A)      |



## રાજકોટ મહાનગરપાલિકા સોલિડ વેસ્ટ મેનેજમેન્ટ શાખા wow cell



'ડો. આંબેડકર ભવન, ઢેબરભાઇ રોડ, રાજકોટ

રા.મ.ન.પા./સો.વે.મે./જા.નં.-6445

તા.30-03-2024

હ્કમ:

# સંદર્ભઃ રા.મ.ન.પા./સો.વે.મે./જા.નં ૮૬૬, તા. ૦૪-૦૬-૨૦૧૯

રાજકોટ મહાનગરપાલિકા વિસ્તારમાં વિકાસ કામો અને બાંધકામ પ્રવૃત્તિનો ખૂબ જ ઝડપથી વિકાસ થઈ રહેલ છે. જેના પરિણામે શહેરમાં કન્સ્ટ્રક્શન એન્ઠ ડિમોલિશન વેસ્ટ પણ ખૂબ બહોળા પ્રમાણમાં ઉત્પન્ન થાય છે. આથી તેના કલેક્શન તથા યોગ્ય પદ્ધતિથી નિકાલની ખૂબ જ વિકટ સમસ્યા ઊભી થાય છે. કન્સ્ટ્રક્શન એન્ઠ ડિમોલિશન (સી & ડી) વેસ્ટ રુલ્સ -2016 પ્રમાણે આ વેસ્ટનું કલેક્શન, સ્ટોરેજ તથા પ્રોસેસિંગ કરી યોગ્ય નિકાલ કરવો જરૂરી છે. જે અન્વચે આ અગાઉ ઉપરોક્ત સંદર્ભિત ફુકમથી શહેરમાં ઉત્પન્ન થતા સી & ડી વેસ્ટના નિકાલ અન્વચેની માર્ગદર્શિકા નિયત કરવામાં આવેલ. જેની વધુ અસરકારકતા તથા કાર્યક્ષમતા સાથે પરિણામલક્ષી કામગીરી થઇ શકે તે માટે હવે પછીથી નીચે જણાવ્યા મુજબની વિગતે અમલવારી કરવા ફુકમ કરવામાં આવે છે.

(૧) રાજકોટ મહાનગરપાલિકાની ટાઉન પ્લાનિંગ શાખા દ્વારા શહેરમાં આવેલ હયાત/જુના બાંધકામ ધરાવતી ઈમારતોને સ્થાને નવું બાંધકામ કરવા માટેની બાંધકામ પરવાનગી ઇસ્યુ કરતા પહેલા હાલની વ્યવસ્થા મુજબ જે ડિમોલિશન ચાર્જ લેવામાં આવે છે તેની સાથે શહેરમાં આવેલ આવી જૂની ઈમારતોનું બાંધકામ માલિક/કબજેદાર/ડેવલપર દ્વારા દૂર કરવાથી કેટલો સી & ડી વેસ્ટ ઉત્પન્ન (Generate) થશે તે બાંધકામ પરવાનગી અર્થે પ્લાન સહીતની વિગતો રજૂ કરનાર પરવાનેદાર એન્જિનિચરશ્રી/આર્કિટેકટશ્રી મારફત પ્રમાણિત કરાવી તેના જથ્થા મુજબ અને બાંધકામની પરવાનગીના પ્રકાર મુજબ આ ઉત્પન્ન થનાર સી & ડી વેસ્ટને નાકરાવાડી ખાતે આવેલ સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતે નિકાલ કરવા માટેની ડિપોઝિટની રકમ પેટે રૂપિયા પ000/- (અંકે રૂપિયા પાંચ હજાર પુરા) વસુલવાની રહેશે. આ પ્રકારના તમામ કિસ્સાઓમાં ડીપોઝીટની રકમ જમા થયા બાદ જ ટાઉન પ્લાનિંગ શાખા દ્વારા શરતી બાંધકામ પરવાનગી (Conditional Permission) આપવાની રહેશે, તથા સદરહુ શરતી બાંધકામ પરવાનગીમાં સંલગ્ન જૂની ઈમારતના સી & ડી વેસ્ટને ટ્રાન્સપોર્ટ કરી સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતે મોકલી આપવામાં આવ્યાનું પ્રમાણિત થયા બાદ જ ટાઉન પ્લાનીંગ શાખા દ્વારા બાંધકામ પરવાનગી આપવામાં આવશે અને ત્યારબાદ જ અરજદારશ્રી દ્વારા નવું બાંધકામ શરુ કરવાનું રહેશે તેવો ઉલ્લેખ કરવાનો રહેશે.

શરતી બાંધકામ પરવાનગી મેળવ્યા બાદ અરજદારશ્રી દ્વારા તેઓના જુના મકાન/ઈમારતના ડીમોલીશનને કારણે નીકળેલ સી & ડી વેસ્ટને રાજકોટ મહાનગરપાલિકાના નાકરાવાડી ખાતે આવેલ સી & ડી વેસ્ટ પ્રોમેસિંગ પ્લાન્ટ પર મોકલવાની વ્યવસ્થા કરી નિકાલ કરવાનો રહેશે, તથા સી & ડી વેસ્ટ પ્રોમેસિંગ પ્લાન્ટ ખાતેથી આ અંગેની પહોંચ (રીસીપ્ટ)/પ્રમાણપત્ર મેળવી લેવાનું રહેશે.

સી. & ડી. વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતે શહેરમાંથી સી & ડી વેસ્ટના નિકાલ અર્થે આવેલ મટીરીયલ અંગેનું રજીસ્ટર નિભાવવાનું રહેશે, તથા પ્લાન્ટ ખાતે સી & ડી વેસ્ટ લઇને આવેલ તમામ વાહન તથા તેના સી & ડી વેસ્ટના જથ્થાની નોંધ ઓનલાઈન નિયત એપ્લીકેશનમાં કરવાની રહેશે. પ્લાન્ટ ખાતે મેળવવામાં આવેલ સી & ડી વેસ્ટ મટીરીયલની પહોંચ (રીસીપ્ટ)/પ્રમાણપત્ર આપવા અંગેની જરૂરી તમામ વ્યવસ્થા સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટની એજન્સી દ્વારા કરવાની રહેશે.

ટાઉન પ્લાનિંગ શાખા દ્વારા ઉપરોક્ત જણાવ્યા મુજબ જુના બંધકામ/ઈમારતના ડીમોલીશનને કારણે ઉત્પન્ન થયેલ સી & ડી વેસ્ટને અરજદારશ્રી દ્વારા નાકરાવાડી ખાતેના સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતે



- મોકલ્યાની ખરાઈ (Confirmation) કર્યા બાદ જ અરજદારશ્રી દ્વારા જમા કરવામાં આવેલ ડીપોઝીટની રકમ્ રૂ.૫૦૦૦/- (અંકે રૂપિયા પાંચ હજાર પુરા) પરત કરી બાંધકામ પરવાનગી ઇસ્યુ કરવાની રહેશે.
- (૨) ટાઉન પ્લાનિંગ શાખા દ્વારા કન્સ્ટ્રક્શન એન્ડ ડીમોલિશન વેસ્ટ રૂલ્સ 2016 ની માર્ગદર્શિકા મુજબ શહેરમાં જૂનો ઇમલો દ્વર કરનાર એજન્સીઓ કોન્ટ્રાક્ટરો દ્વારા સી & ડી વેસ્ટનું કલેક્શન તથા તેનું જરૂરી સેગ્રીગેશન કરી રાજકોટ મહાનગરપાલિકાના નાકરાવાડી ખાતે આવેલ સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતે નિકાલ કરવાનું કરજીયાત હોવાની બાબતની સમજ આપી તેઓનું રજીસ્ટ્રેશન કરાવી રાજકોટ મહાનગરપાલિકાની વેબસાઈટ પર શહેરમાં ઈમલો દૂર કરવાની કામગીરી કરતી આવી તમામ એજન્સીઓ કોન્ટ્રાક્ટરોની યાદી મૂકવાની રહેશે.
  - (3) સોલિડ વેસ્ટ મેનેજમેન્ટ વિભાગ દ્વારા ફાલ રાજકોટ મहાનગરપાલિકાના ત્રણેય ઝોનના જુદા જુદા વોર્ડ વિસ્તારના પ્લોટ તથા રસ્તાઓની સાઈડમાં પડેલ સી & ડી વેસ્ટને કલેકટ કરી નાકરાવાડી ખાતે આવેલ સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટની જરૂરીયાત મુજબ પ્લાન્ટ ખાતે પહોંચાડવા (Transportation) ની વ્યવસ્થા કરવાની રહેશે, તથા શહેરના જાહેર રસ્તાઓ કે રાજકોટ મહાનગરપાલિકાના પ્લોટ પર અનઅધિકૃત રીતે સી & ડી વેસ્ટ ડિમ્પિંગ ન થાય તે અંગેની તકેદારી રાખવા માટેની જરૂરી વ્યવસ્થા ઉભી કરવાની રહેશે.
  - (૪) રાજકોટ મહાનગરપાલિકાની તમામ તાંત્રિક શાખા દ્વારા તેમના કાર્યક્ષેત્ર હેઠળ સિવિલ કામ કરતી તમામ એજન્સીઓ (ઝોનલ તથા ટેન્ડર કામ) ને સોંપવામાં આવેલ સિવિલ કામગીરી અંતર્ગત ઉત્પન્ન થનાર સી & ડી વેસ્ટના સંપૂર્ણ જથ્થાનો નિકાલ રાજકોટ મહાનગરપાલિકાની નાકરાવાડી ખાતે આવેલ સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતે કરાવવાનો રહેશે.

આ માટે ઉત્પન્ન થયેલ સી & ડી વેસ્ટના જથ્થાને સંલગ્ન તાંત્રિક કામગીરી સંભાળતા એ.એ.ઈ.શ્રી તથા એ.ઈ.શ્રી દ્વારા તેમના નાયબ કાર્યપાલક ઇજનેરશ્રી મારફતે પ્રમાણિત કરાવી તે સી & ડી વેસ્ટના જથ્થાને સિવિલ કામની સંલગ્ન એજન્સી દ્વારા ટ્રાન્સપોર્ટેશનની વ્યવસ્થા કરી શહેરમાં અન્ય કોઈપણ જગ્યાએ નિકાલ ન કરી માત્ર નાકરાવાડી ખાતે આવેલ સી & ડી વેસ્ટ પ્રોસેસિંગ પ્લાન્ટ ખાતે જ જમા કરાવવાનો રહેશે, તથા પ્લાન્ટ ખાતેથી તે અંગેની પહોંચ (રીસીપ્ટ)/પ્રમાણપત્ર મેળવવાનું રહેશે. જે પહોંચ (રીસીપ્ટ)/પ્રમાણપત્ર સંલગ્ન તાંત્રિક શાખામાં રજુ થયા બાદ તેને સંલગ્ન તાંત્રિક સ્ટાફ દ્વારા ચકાસણી કર્યા બાદ જ સંલગ્ન નાયબ કાર્યપાલક ઇજનેરશ્રી દ્વારા એજન્સીએ કરેલ કામની રકમનું ચૂકવણું કરવા માટેની બીલ અંગેની કાર્યવાહી હાથ ધરવાની રહેશે.

(૫) રાજકોટ શહેરમાં ઉત્પન્ન થનાર સી & ડી વેસ્ટનો મહત્તમ રીયુઝ તથા રિસાયકલ થાય તે માટે કઈ કઈ બાંધકામ ઉપયોગી વસ્તુઓ (મદીરીયલ) બનાવી શકાય તથા તે તમામ મદીરીયલનો રાજકોટ મહાનગરપાલિકાના વિવિધ તાંત્રિક કામોમાં ઉપયોગ થાય તેવા મદીરીયલનો રાજકોટ મહાનગરપાલિકાના શેડ્યુલ ઓફ રેઈટસ (S.O.R.) માં સમાવેશ કરવા તથા રાજકોટ મહાનગરપાલિકાના વિવિધ સિવિલ કામમાં તેનો ઉપયોગ થાય તે સુનિશ્ચિત કરવા માટેની જરૂરી કાર્યવાહી હાથ ધરવાની રહેશે.

ઉપરોક્ત વિગતે સોંપવામાં આવેલ કામગીરીનો રિપોર્ટ નાયબ કમિશનરશ્રી (ઈસ્ટ ઝોન)ને કરવો. સદરફુ ફુકમનો અમલ તાત્કાલિક અસરથી યુસ્તપણે કરવાનો રહેશે.

કૌમેશનર

રાજકોટ મહાનગરપાલિકા

Scanned with OKEN Scanner