

રાજકોટ મહાનગરપાલિકા

બાંધકામ શાખા



૨૦૧૯ - ૨૦

એ - ટેકનિકલ બીડ

કામનું નામ:- માનનીય ધારાસભ્યશ્રી ગોવિંદભાઈ પટેલની સને ૨૦૧૮-૧૯ ધંની ગ્રાન્ટમાંથી વોર્ડ નં. ૧૮ માં આવેલ બાપાસીતારામ ચોક થી રંગીલા પાર્ક બગીચા સુધીના શ્રદ્ધાપાર્ક મેઈન રોડની બન્ને સાઈડમાં ઇન્ટરલોકિંગ પેવિંગ બ્લોકસ નાખવાનું કામ(બિજો પ્રયત્ન)

અંદાજીત રકમ	:-	રૂ.૪,૯૯,૫૦૦/-
અર્નેસ્ટ મની	:-	રૂ.૪,૯૯૫/-
ટેન્ડર ફી	:-	રૂ.૭૫૦/- (નોન-રીફંડેબલ)

સીટી એન્જીનીયર (સ્પે.)
શ્રી ઝવેરચંદ મેઘાણી ભવન, પૂર્વઝોન,
રાજમોતી ઓઈલ મીલ સામે,
રાજકોટ - ૩૬૦૦૦૩

રાજકોટ મહાનગર સેવા સદન
ટેન્ડર નોટીસ

બાંધકામ શાખા, પૂર્વ ઝોન

રાજકોટ મહાનગરપાલિકાની બાંધકામ શાખામાં નીચે જણાવેલ કામ માટેના પર્સન્ટેજ રેઇટ ટેન્ડર સરકારશ્રીના નિયમો મુજબ રજીસ્ટર્ડ થયેલ કક્ષા અને સોલવંસી સર્ટીફિકેટ ધરાવનાર કોન્ટ્રાક્ટરો પાસેથી માંગવામાં આવે છે. આ ટેન્ડરો તા.૨૭-૦૫-૨૦૨૦ અને ૨૮-૦૨-૨૦૨૦ ના રોજ સાંજના ૬-૦૦ વાગ્યા સુધીમાં નીચેની વિગતે રૂબરૂ / સ્પીડ પોસ્ટ / રજીસ્ટર્ડ પોસ્ટ / કુરીયર થી મળી જાય તે રીતે મોકલવાના રહેશે શક્ય હશે તો તે જ દિવસે આ ટેન્ડરો ખોલવામાં આવશે

- ૧) સીટી એન્જીનીયર (સ્પે.), રાજકોટ મહાનગરપાલિકા, પૂર્વ ઝોન- બાંધકામ શાખા, શ્રી ઝવેરચંદ મેઘાણી ભવન, રાજમોતી ઓઈલ મિલ સામે, રાજકોટ-૩૬૦૦૦૩.

ક્રમ	કામનું નામ	એસ્ટીમેટની રકમ રૂ.	અર્નેસ્ટમની ની રકમ રૂ.	કામની સમય મર્યાદા	ટેન્ડર ફી (નોન રીફંડેબલ) રૂ.
૧	માનનીય ધારાસભ્યશ્રી ગોવિંદભાઈ પટેલની સને ૨૦૧૮-૧૯ ર્ષની ગ્રાન્ટમાંથી વોર્ડ નં ૧૮ માં આવેલ બાપાસીતારામ ચોક થી રંગીલા પાર્ક બગીચા સુધીના શ્રદ્ધાપાર્ક મેઈન રોડની બન્ને સાઈડમાં ઇન્ટરલોકિંગ પેવિંગ બ્લોક્સ નાખવાનું કામ (બિજો પ્રયત્ન)	૪,૯૯,૫૦૦/-	૪,૯૯૫/-	૩૦ દિવસ	૭૫૦/-

સામાન્ય શરતો:

એજન્સીની નાણાંકીય ક્ષમતા ::-

- ✳ છેલ્લા સાત વર્ષનું સરેરાશ વાર્ષિક ટર્ન ઓવર કામની અંદાજીત રકમ કરતા ૫૦% થી ઓછું ન હોવું જોઈએ.
 - ✳ એજન્સીએ ઇ-૨ કે તેથી ઉંચી શ્રેણીમાં રજીસ્ટ્રેશન કરાવેલ હોવું જોઈએ.
 - ✳ એજન્સીની સોલવંશી રૂ.૧.૦૦ લાખ કરતા ઓછી ન હોવી જોઈએ.
 - ✳ એજન્સીની વર્કીંગ કેપિટલ ૨૫ % કરતા ઓછી ન હોવી જોઈએ.
- નોંધ ::- સરેરાશ વાર્ષિક ટર્ન ઓવરની ગણતરી કરવા અને છેલ્લા સાત વર્ષમાં થયેલ કામોની રકમ મેળવવા માટે નાણાંકીય બાબતોમાં દર વર્ષે ૧૦ % લેખે એન્હેન્સમેન્ટ ફેક્ટર (Enhancement Factor (લાગુ પાડવામાં આવશે

- (૧) જરૂર જણાયે લેબર લાયસન્સની જવાબદારી જે તે કોન્ટ્રાક્ટરની રહેશે તથા ઇ.પી.એફ. નંબર લેવાની જવાબદારી જે તે કોન્ટ્રાક્ટરની રહેશે.
- (૨) અર્નેસ્ટમની ડીપોઝીટની રકમ એસ્ટીમેટની રકમના એક ટકા મુજબ ભરવાની રહેશે અર્નેસ્ટમની શેડ્યુઅલ બેંકના રાજકોટ મહાનગર સેવા સદનની તરેફણા ડીમાન્ડ ડ્રાફ્ટથી ભરીને પહોંચની વિગત કવર ઉપર દર્શાવવાની રહેશે અન્યથા આવા ટેન્ડર ખોલવામાં આવશે નહીં. અર્નેસ્ટમની ડીપોઝીટ તરીકે એફ.ડી.આર. સ્વીકારવામાં આવશે નહીં.
- (૩) સિક્યોરીટી ડીપોઝીટની રકમ અઢી ટકા લેખે રોકડેથી કરારનામું કરતી વખતે તથા અઢી ટકા બીલમાંથી કપાત કરવામાં આવશે. કુલ સિક્યોરીટી ડીપોઝીટ ૫ % મુજબ ભરવાની રહેશે
- (૪) લેબર વેલ્ફેર સેસ ૧ % મુજબ કપાત કરવામાં આવશે

- (૫) આ કામના ટેન્ડર ફોર્મનું વેચાણ પૂર્વઝોન, બાંધકામ શાખામાંથી તા.૧૬-૦૫-૨૦૨૦ થી ૨૬-૦૫-૨૦૨૦ ના ૧.૦૦ વાગ્યા સુધી કરવામાં આવશે. ટેન્ડર કામની સમજૂતી તથા અન્ય વિગતો ઓફીસ સમય દરમિયાન પૂર્વ ઝોન, બાંધકામ શાખામાંથી જાણવા મળી શકશે. વધુમાં, આ કામના ટેન્ડર ડોક્યુમેન્ટ (ટેકનીકલ બીડ અને પ્રાઈસ બીડ) રાજકોટ મહાનગરપાલિકાની વેબ સાઈટ www.rmc.gov.in પરથી પણ ડાઉનલોડ કરી શકાશે અને ટેન્ડરમાં જણાવ્યા મુજબની તારીખ સુધીમાં ટેન્ડર સાથે જરૂરી દસ્તાવેજો, ટેન્ડર ફી, ઇ.એમ.ડી., આઈડેન્ટિટી પૂરૂ એડ્રેસ પૂરૂ પાન કાર્ડની પ્રમાણિત નકલ, વ્યવસાય વેરો ભર્યાની નકલ, સંપર્ક ફોન નંબર / મોબાઈલ નંબર વિગેરે એજન્સીએ રજૂ કરી દેવાના રહેશે.
- રાજકોટ મહાનગરપાલિકાની વેબ સાઈટ www.rmc.gov.in પરથી ટેન્ડર ડાઉનલોડ કરી રજૂ કરનાર એજન્સી પ્રિ-ક્વોલીફાય નહીં થાય તો તેવી એજન્સીના ભાવ ખોલવામાં આવશે નહીં તેમજ તેઓએ ટેન્ડર સાથે ભરેલ ટેન્ડર ફી પરત કરવામાં આવશે નહિ. એનેક્સર-૧માં દર્શાવેલ ફોર્મેટમાં વિગતો રજૂ કરવી ફરજિયાત છે.
- (૬) ટેન્ડર કામની સમજૂતી તથા અન્ય વિગતો ઓફીસ સમય દરમિયાન બાંધકામ શાખા, (પૂર્વ ઝોન) માંથી જાણવા મળી શકશે.
- (૭) કોન્ટ્રાક્ટરશ્રીઓએ ટેન્ડરના બંધ કવર ઉપર કામનું નામ તથા વોર્ડ નંબર સ્પષ્ટ અક્ષરે લખવાનું રહેશે.
- (૮) એજન્સીએ છેલ્લાસાત વર્ષના સમયગાળામાં સરકારી, અર્ધસરકારીમાં આ જ પ્રકારનું કોઈ પણ રકમનું ઓછામાં ઓછું એક સરખા પ્રકારનું કામ મુખ્ય કોન્ટ્રાક્ટર તરીકે પૂર્ણ કરેલું હોવું જોઈએ તથા એજન્સી પાસે કામ કરવા માટે પુરતા પ્રમાણમા સાધન સામગ્રી તથા જરૂરી અનુભવી સ્ટાફ હોવો જોઈએ.
- (૯) આ કામ બેરોજગાર ડિપ્લોમા / ડીગ્રી હોલ્ડરને કોઈ પણ ટર્નઓવર, અનુભવ કે સોલ્વન્સી વગર આપવામા આવી શકાશે પરંતુ નીચે જણાવ્યા મુજબના જરૂરી દસ્તાવેજોની 'ખરી નકલ' ટેન્ડર સાથે રજૂ કરવાના રહેશે:
- રાજ્ય સરકાર / કેન્દ્ર સરકાર / જી.ડબલ્યુ.એસ.એસ.બી.માં રજીસ્ટ્રેશન કરાવ્યાની નકલ
 - ડિપ્લોમા / ડીગ્રી નું સર્ટીફિકેટની નકલ
 - કોઈ પણ જગ્યાએ નોકરી કે ધંધો નથી કરતા તે અંગેનો રૂ.૨૦/- ના સ્ટેમ્પ પેપર ઉપર "સોગંદનામું"
- ઉપરોક્ત તમામ દસ્તાવેજો અસલ વેરીફિકેશન સમયે રજૂ કરવાના રહેશે અન્યથા નોનરેસ્પોન્સીવ ગણવામાં આવશે.
- (૧૦) ટેન્ડર ખરીદવાની માંગણી સાથે એજન્સીએ જરૂરી તમામ દસ્તાવેજોની નકલો રજૂ કરવાની રહેશે જેને આધારે પ્રી-ક્વોલીફાય થનાર એજન્સીને જ ટેન્ડર કોપી ઇસ્યુ કરવામાં આવશે.
- (૧૧) એજન્સીએ ટેન્ડર સાથે પોતાના બીઝનેસ એડ્રેસ પૂરૂ તથા પોતાનો આઇડી. પૂરૂ રજૂ કરવાનું રહેશે.
- (૧૨) આ કામે પેનલ્ટી કોન્ટ્રાક્ટ વેલ્યુના ૦.૨૦ % મુજબ પ્રતિ દિન રહેશે જે વધુમાં વધુ અંજીત કિંમતના ૧૦% સુધી કાપવામાં આવશે.
- (૧૩) એજન્સીએ જી.એસ.ટી. (G.S.T.) તથા અન્ય ટેક્સ સહિત પોતાના ભાવ ભરવાના રહેશે. કોન્ટ્રાક્ટર દ્વારા તે મુજબ જી.એસ.ટી. બ્રેક-અપ સાથેનું ઇન્વોઈસ રજૂ કરવામાં નહીં આવે તો સદરહુ ટેક્સ કોન્ટ્રાક્ટરના બીલમાંથી કપાત કરી જમા કરવામાં આવશે.
- આ ટેન્ડર કામે ખરીદવાનું થતું મટીરીયલ એજન્સી જી.એસ.ટી. (G.S.T.) નંબર ધરાવતા હોય તેવા રજીસ્ટર્ડ સપ્લાયર પાસેથી જ મટીરીયલ ખરીદ કરવાનું રહેશે જી.એસ.ટી. (G.S.T.) નંબર ન ધરાવતા હોય તેવા અનરજીસ્ટર્ડ સપ્લાયર પાસેથી મટીરીયલ ખરીદ કરવામાં આવશે તો તેવા મટીરીયલ માટેનું જી.એસ.ટી. (G.S.T.) અંગે કોઈ પણ પ્રકારનું પેમેન્ટ / રકમ ચુકવવા રાજકોટ મહાનગરપાલિકા જવાબદાર રહેશે નહીં.

- (૧૪) એજન્સીએ ટેન્ડર ફી નો ડીમાન્ડ ડ્રાફ્ટ, ઈ.એમ.ડી. નો ડીમાન્ડ ડ્રાફ્ટ તેમજ અન્ય રજુ કરવાના થતા જરૂરી ડોક્યુમેન્ટસ સાથે ઈ.એસ.આઈ.સી. રજીસ્ટ્રેશનની નકલ તેમજ ઈ.પી.એફ. રજીસ્ટ્રેશનની નકલ અત્રેની કચેરીને રજુ કરવાના રહેશે અન્યથા એજન્સીને નોન-રીસ્પોન્સીવ ગણી તેવી એજન્સીના ભાવ ખોલવામાં આવશે નહીં.
- (૧૫) ટેન્ડર ડોક્યુમેન્ટમાં દર્શાવેલ તમામ શરતો ધ્યાને લઈ ઓફર આપવાની રહેશે
- (૧૬) આ કામે આવેલ કોઈ પણ ટેન્ડર / બધા ટેન્ડરનો સ્વીકાર / અસ્વીકાર કરવાનો હક્ક રાજકોટ મહાનગરપાલિકા અબાધિત રાખે છે.

સીટી એન્જીનીયર (સ્પે.)
રાજકોટ મહાનગરપાલિકા

:: ટેન્ડર રજુ કરવા બાબતની સમજૂતી ::

૧. ટેકનીકલ બીડ તથા પ્રાઈસ બીડ અલગ-અલગ કવરમાં બંધ કરવાના રહેશે અને કવર ઉપર કામનું નામ તથા "ટેકનીકલ બીડ", "પ્રાઈસ બીડ" મોટા અક્ષારે લખવાનું રહેશે
૨. ઉપરોક્ત બન્ને કવર - એક મોટા કવરમાં બંધ કરી - ઉપર કામનું નામ તથા સંપૂર્ણ વિગતો દર્શાવી રજુ કરવાનું રહેશે
૩. નિયત સમયે "ટેકનીકલ બીડ" ખોલવામાં આવશે અને "ટેકનીકલ બીડ" માં રજુ થયેલ યોગ્ય શ્રેણીનાં રજીસ્ટ્રેશન, અનુભવની વિગત, અર્નેસ્ટ મની ડીપોઝીટ, સોલ્વન્સી વિગેરેની ચકાસણી કરવામાં આવશે. જે અન્વયે યોગ્યતા ધરાવનાર એજન્સીની જ "પ્રાઈસ બીડ" ખોલવામાં આવશે અન્ય એજન્સીઓની "પ્રાઈસ બીડ" ખોલવામાં આવશે નહીં, જે બાબત તમામ એજન્સીઓને બંધનકર્તા રહેશે

કોન્ટ્રાક્ટરની સહી તથા સીકકો

:: ચેક લીસ્ટ ::

૧. સરકારી, અર્ધ-સરકારી વિભાગમાં રજીસ્ટ્રેશન કરાવ્યાની નકલ
૨. સમાન પ્રકારના કામ કરેલ અનુભવના દાખલાની નકલ (છેલ્લા સાત નાણાકિય વર્ષ દરમિયાન કરેલ કામો પૈકીના કોઈ પણ રકમના એક કામના અનુભવનો દાખલો રજુ કરવો)
૩. કામની રકમના ૨૫.૦૦% મુજબની બેન્કનું વર્કીંગ કેપિટલ રજુ કરવું.
૪. સોલવન્સી સર્ટીફિકેટ રૂ. ૧.૦૦ લાખ નું રજુ કરવું.
૫. અર્નેસ્ટ મની ડીપોઝીટ
૬. રૂ. ૧૦૦/- ના સ્ટેમ્પ પેપર ઉપર બ્લેક લીસ્ટ થયેલ નથી તથા ડોક્યુમેન્ટની ખરાઈ તેમજ કોઈ પોલીસ ફરિયાદ થયેલ નથી તે અંગેનું સોગન્દનામું રજુ કરવાનું રહેશે

કોન્ટ્રાક્ટરનું નામ :-

સરનામું :-

અર્નેસ્ટ મનીની વિગત:- રૂ. ૪,૯૯૫/-

બેન્કનું નામ તથા વિગત

.....

ઉપરોક્ત ડોક્યુમેન્ટ રજુ કરેલ છે.

કોન્ટ્રાક્ટરની સહી તથા સીકકો

:: શ ર તો ::

- (૧) ૧. ટકા તથા રકમ અક્ષર તેમજ આંકડામાં સ્પષ્ટ લખવી.
 ૨. પેઢી કે ભાગીદાર વતી સહી કરનારે તે જ પ્રમાણે સહી કરવી.
 ૩. નિયત થયેલ જગ્યાએ લખવું.
 ૪. છેકછાકવાળું ટેન્ડર રદ કરવામાં આવશે.
 ૫. શરતો, એબસ્ટ્રેક્ટ તથા સમજૂતીમાં દરેક પાને સહી કરવી.
 ૬. અર્નેસ્ટ મની ભર્યાનો દાખલો ટેન્ડરના કવર ઉપર પહોંચ નંબર થી લખવો. અસલ પહોંચ ટેન્ડર સાથે રાખવી.
- (૨) કામ પુરા ખંતથી કરવું જોઈએ અને કરેલું સઘળું કામ કારીગરની રીતે કરેલું હોવું જોઈએ. ટેન્ડર રજુ કરનાર શખ્સ / શખ્સો કામમાં જે માલ સામાન વાપરે તે ઉત્તમ પ્રકારનો હોવો જોઈએ. અને સીટી એન્જીનીયર એ પસંદ કરેલો હોવો જોઈએ. કામ કેટલી ત્વારાથી ચલાવવું તે બાબત તથા કામ અથવા તેમાં વપરાતો માલ સામાન કેવા પ્રકારનો છે તે બાબત સીટી એન્જીનીયર જે નિર્ણય કરે તે આખરનો સમજવો જોઈએ. કામની ઝડપ અને ગતી વધારવા સીટી એન્જીનીયર નો નિર્ણય આખરી સમજવાનો રહેશે તથા લેખીત તેમજ મૌખિક સુચના તેમજ નોટીસ આપવા છતાં પણ કામની ગતી કે ઝડપ વધારવામાં નહીં આવે તો શ્રી કમિશનર સાહેબને કોન્ટ્રાક્ટ રદ કરવાનો અધિકાર રહેશે.
- (૩) સઘળી ખાણોની ફી, રોયલ્ટી, સીકયોરીટી ડીપોઝીટ અને સામાન ભરી રાખવા માટે કાંઈ જમીનનું ભાડુ આપવાનું હોય તો તે કોન્ટ્રાક્ટરે આપવાનું રહેશે.
- (૪) કોન્ટ્રાક્ટરે પોતાના કામદારોને થયેલ ઈજા માટે તથા તેને કંઈ બદલો આપવો પડે તો તે માટે તમામ રીતે જવાબદાર રહેશે. કામદારોને થયેલ ઈજા માટે યોગ્ય બદલો આપવામાં જો કોન્ટ્રાક્ટર નિષ્ફળ નીવડે અને કામ કરતા કામદારોને તેનો બદલો રાજકોટ મહાનગરપાલિકા તરફથી આપવામાં આવે તો તેવી આપેલી રકમ ટેન્ડર ભરનાર શખ્સને આપવા જોગ થયેલ રકમ માંથી અથવા આપવાના થાય તે રકમ માંથી કાપી લેવા રાજકોટ મહાનગરપાલિકા મુખત્યાર છે.
- (૫) આમાં કબુલ કરેલી તેવી કામની જુદી જુદી બાબતો માટેનો દરજજો તે બાબતો મંજૂર કરેલી સમજૂતી અનુસાર પુરી કરવામાં આવી છે એમ સ્વીકારવામાં આવે તો જ કાયદેસર ગણાશે જે તે પ્રસંગે કામની સદરહુ બાબતો એવી રીતે પુરી કરી છે એમ સ્વીકારવામાં નહીં આવે તે પ્રસંગે સીટી એન્જીનીયર છેવટના બીલો તૈયાર કરતી વખતે વ્યાજબી લાગે તેવા ઘટાડાના દરથી બીલો કરવાનો મુખત્યાર છે.

- (૬) ૧. કોન્ટ્રાક્ટરે ૧૮ વર્ષથી ઓછી ઉંમરનાં કોઈને કામે લગાડવા નહિં.
૨. કામ ઉપર જે માણસને રાખવાની સીટી એન્જીનીયર શ્રી મનાઈ કરે તે માણસને કામ પર રાખવાના નથી.
- (૭) વર્ક ઓર્ડર મળે તુરત જ કામ ચાલુ કરવાનું છે ઓર્ડરમાં જણાવેલ ૩૦ દિવસની મુદત દરમ્યાન કામગીરી કરવાની છે. જો મુદત દરમ્યાન સુચના પ્રમાણે કામ કરવામાં નહીં આવે તો શ્રી કમિશ્નર સાહેબને યોગ્ય લાગશે તો કોન્ટ્રાક્ટરના ખર્ચે અને જોખમે અન્ય કોન્ટ્રાક્ટર પાસે અગર તો ખાતા મારફત કામ પુરું કરાવશે. અને આમ બાકી રહેતું કામ પુરું કરવામાં મહાનગરપાલિકાને કોન્ટ્રાક્ટ એગ્રીમેન્ટ કરતા જો વધુ ખર્ચ થશે તો તે કોન્ટ્રાક્ટર પાસેથી કાયદેસર રીતે આ વધારાનો ખર્ચ વસુલ કરી શકશે તથા તેની સીકયોરીટી જપ્ત કરી શકશે. શ્રી કમિશ્નર સાહેબને જો યોગ્ય લાગશે તો મુદત દરમ્યાન કામ પુરું નહિં થયું હોય છતાં પણ કોન્ટ્રાક્ટર પાસે કામ ચાલુ રખાવી શકશે અને તેની મુદત સ્થોગોને લક્ષમાં રાખીને વધારી આપશે અગરતો અંદાજીત રકમના દરરોજના ૦.૨૦% લેખે દંડ કરી શકશે.
- (૮) ટેન્ડરની વેલીડીટી ૧૨૦ દિવસ રહેશે.
- (૯) કામ કરતા માલ સામાન નડતર રૂપ ન થાય તે રીતે કરવાનું છે
- (૧૦) એજન્સી દ્વારા રજૂ કરવામાં આવેલ ભાવ અત્રેથી સ્વીકાર્યા બાદ સદરહુ કામે નિયમાનુસાર ભરવાની થતી સીક્યુરીટી ડીપોઝીટ તેમજ કરાર કરવા જણાવવામાં આવ્યેથી નિયત સમય મર્યાદામાં સીક્યુરીટી ડીપોઝીટ ભરી તેમજ સ્ટેમ્પ ડ્યુટી એક્ટ ૧૯૫૮ અને તેના રીવીઝન મુજબ કરારનામું કરવાનું રહેશે જેમાં નિષ્ફળ ગયેથી ભરવામાં આવેલ અર્નેસ્ટ મની ડીપોઝીટ જપ્ત કરવામાં આવશે અને એજન્સીને રાજકોટ મહાનગરપાલિકાના કામો માટે ત્રણ વર્ષ માટે બ્લેક લિસ્ટ / ડીબાર કરવામાં આવશે.
- (૧૧) સીકયોરીટી ડીપોઝીટ તરીકે ભરેલ રકમ કામ પુરું થઈ ગયા બાદ કમ્પ્લીશન તારીખથી ૧૨ (બાર) માસ પછી પાછી આપવામાં આવશે પરંતુ તે સમય દરમ્યાન કોઈ કામ ખરાબ થયેલ અથવા નુકશાન પામેલ માલુમ પડશે તો તે કામ કોન્ટ્રાક્ટરે દુરસ્ત કરી આપવાનું રહેશે અને જો તેમ કરવામાં નાકામીયાબ નિવડશે તો દુરસ્તીતેને ખર્ચે અને જોખમે મહાનગરપાલિકા તરફથી કરાવી લેવામાં આવશે, અને તે પૈકીનો થયેલ ખર્ચ સીકયોરીટી ડીપોઝીટની રકમમાંથી કાપી લેવામાં આવશે.
- (૧૨) કામ ઉપર કોન્ટ્રાક્ટરે પોતે અથવા તેના વતી કોઈ જવાબદાર માણસને હાજર રાખવાનો રહેશે.

- (૧૩) કામ પુરૂ થઈ ગયા બાદ સાઈટ બરાબર સાફ કરી આપવીની રહેશે અને જો તેમ કરવામાં કોન્ટ્રાક્ટર નાકામિયાબ નિવડશે તો તેને ખર્ચે અને જોખમે મહાનગરપાલિકા તરફથી સાઈટ સાફ કરાવી લેવામાં આવશે.
- (૧૪) રસ્તો બંધ કરવા માટે દિવસના ભાગમાં તેવી સુચનાના બોર્ડ તથા રાત્રેબત્તી વ્યવસ્થા કોન્ટ્રાક્ટરે કરવાની રહેશે. તેને અભાવે થતી નુકશાનીની તમામ જવાબદારી કોન્ટ્રાક્ટરને શીરે રહેશે.
- (૧૫) વર્ક ઓર્ડર આપી કામમાં ચાલુ કામે અન્ય આસામીઓની મિલકતને અગર જાનમાલને કોઈપણ નુકશાન થશે તો તેની તમામ જવાબદારી કોન્ટ્રાક્ટ રાખનારની રહેશે. અને તે માટે કોઈપણ વળતરની રકમ ચુકવવાની થાય તો તે કોન્ટ્રાક્ટરે ભરી આપવાની રહેશે. જો કોન્ટ્રાક્ટર અમલ ન કરે તો તેવા વળતર વિગેરેની રકમ તેનાં બીલોમાંથી કાપી લેવામાં આવશે.
- (૧૬) કોઈ પણ કારણોસર કોન્ટ્રાક્ટર ટેન્ડરમાં દર્શાવેલ કામ કરવા અશક્તિમાન થશે કે કામ અધુરૂ છોડી દેશે અથવા કામ બંધ કરી દેશે તો તેવા સંજોગોમાં ઇ.એમ.ડી. / સીક્યુરીટી ડીપોઝીટ જપ્ત કરવામાં આવશે અને રાજકોટ મહાનગરપાલિકા એજન્સીને ત્રણ વર્ષ માટે બ્લેક લિસ્ટ / ડીબાર કરવામાં આવશે અને એજન્સીના ખર્ચે અને જોખમે આ કામ પુરૂ કરાવશે. અને આમ કરતાં ટેન્ડરમાં જણાવેલ ભાવ કરતાં વધારે ખર્ચ થશે તો મહાનગરપાલિકા કોન્ટ્રાક્ટરની સીક્યુરીટી ડીપોઝીટમાંથી કે સાઈટ ઉપર પડેલા માલ સામાનની હરરાજી કરી ખર્ચ વસુલ કરી શકશે અને તેમ કરતાં કોન્ટ્રાક્ટરનો કોઈપણ વાંધો કે હકક રહેશે નહિં.
- (૧૭) આ કામનો કોઈ પણ ભાગ સંતોષકારક રીતે કોન્ટ્રાક્ટર નહિં કરે તો મહાનગરપાલિકાનાં ઈજનેર તેઓને ૧૦ દિવસની નોટીસ કામ સુધારવા આપશે. મુદત વિત્યા બાદ મહાનગરપાલિકાનાં ઈજનેર કોન્ટ્રાક્ટરનાં ખર્ચે અને જોખમે માણસો રાખી તેમજ માલ સામાન ખરીદી કામ કરવાની કાર્યવાહી કરશે અને કોન્ટ્રાક્ટર પાસેથી ખર્ચ વસુલી શકશે આ કામ સીટી એન્જીનીયર બીજા કોન્ટ્રાક્ટર પાસે પણ કરાવી શકશે.
- (૧૮) વર્ક ઓર્ડરમાં જણાવ્યાની તારીખે કામ પુરૂ કરવા કોન્ટ્રાક્ટર નિષ્ફળ જશે તો અગાઉ કલોઝ-૭ માં જણાવ્યા પ્રમાણે પેનલ્ટી વસુલ લેવામાં આવશે. જો મહાનગરપાલિકાને કારણે સંજોગો અનુસાર કામ બંધ રહે તો જેટલા દિવસ કામ બંધ રહે તેટલા દિવસની મુદત આવામાં આવશે અથવા તો કોઈ સબબ કારણસર કામ બંધ રહે તેની જાણ કોન્ટ્રાક્ટરે મહાનગરપાલિકાના ઈજનેરને જ કરવાની રહે છે, અને જો કારણ વ્યાજબી લાગશે તો વધારાની મુદત માટે શ્રી કમિશનર સાહેબ વિચારશે અને તેનો નિર્ણય આખરી ગણાશે.
- (૧૯) આ કામ ચાલુ થયે વચ્ચેના ગાળાની સંતોષકારક પ્રગતી હશે તો દર મહીને કોન્ટ્રાક્ટરને થયેલ કામનું સ્પીંગ બીલ આપવામાં આવશે. આ રનીંગ બીલ થયેલ કામ પ્રમાણે અને ફાઈનલ

બીલના "ઉપાડ" એડવાન્સ તરીકે આપવામાં આવશે. રનીંગ બીલમાં લીધેલ કામનો જથ્થો કે કામની વિગતનું આખરી સ્વરૂપ બીલ વખતે નક્કી થયા તે રીતે રહેશે. રનીંગ બીલ આકારવામાં આવેલ બીલની વિગત બધી જ ફાઈનલ બીલમાં હોવી જરૂરી નથી

(૨૦) કોન્ટ્રાક્ટરે આ કામમાં કોઈ પણ આઈટમ સંતોષકારક રીતે સ્પેસીફિકેશન મુજબ નહીં કરી હોય તો મહાનગરપાલિકાને લાગે તે "ભાવ ઘટાડો" (રીડયુઝ રેઈટ) કરી શકશે અને જે કોન્ટ્રાક્ટરે માન્ય રાખવાનો રહેશે

(૨૧) આ કામમાં મહાનગરપાલિકાના ઈજનેર ટેન્ડરમાં જણાવ્યા મુજબના સ્પેસીફિકેશન કે ડ્રોઈંગ કે ડીઝાઈનમાં ફેરફાર કરી શકશે એટલે કે મુળ / સ્પેસીફિકેશનમાં જણાવ્યા મુજબના કામમાં ઘટાડો કરવો કે વધારો કે તદ્દન નવું કામ કરાવી શકશે અને કોન્ટ્રાક્ટરે ટેન્ડરની મુળ શરતોને કાયમ રાખી તે મુજબ કામ કરી આપવાનું છે આ ફેરફારને કારણે મહાનગરપાલિકા સાથે થયેલ કરાર રદ થઈ શકશે નહીં.

(અ) આ વધારાના ઉપર મુજબના કામમાં જો એકસ્ટ્રા આઈટમ થયા અને આઈટમ ટેન્ડરમાં જણાવેલ હશે તો તે મુજબ ભાવ અપવામાં આવશે

(બ) જો એકસ્ટ્રા આઈટમ ટેન્ડરમાં નહીં હોય પરંતુ મહાનગરપાલિકાનો જે તે વખતમાં શેડયુલ આફ રેઈટ હશે તો તે મુજબ ભાવ અપવામાં આવશે આ વખતે જો ટેન્ડર ઉંચા ભાવનું હશે તો વધારાના ટકા અપવામાં આવશે નહીં. પરંતુ જો ટેન્ડર નીચા ભાવનું હશે તો આવી આઈટમોમાંથી કોન્ટ્રાક્ટરે ભરેલા નીચા ટકા બાદ કરવામાં આવશે.

(ક) એકસ્ટ્રા આઈટમ ટેન્ડરમાં કે મહાનગરપાલિકાનો જે તે વખતમાં શેડયુલ આફ રેઈટ નહીં હોય તેવી આઈટમનો વ્યાજબી ભાવ કોન્ટ્રાક્ટર અને મહાનગરપાલિકાના ઈજનેર એક બીજાની સમજુતીથી નક્કી કરશે અને જે ભાવ શ્રી કમિશનર સાહેબની મંજૂરી આપ્યે આપી શકાશે. આવી આઈટમોના ભાવ ઉપર કોન્ટ્રાક્ટરે ટેન્ડરમાં જણાવેલ વધારે કે ઓછા ટકાની અસર થશે નહીં.

(ડ) આ મુળ જથ્થામાં કે ડ્રોઈંગ સ્પેસીફિકેશનમાં કરવો પડતો ફેરફાર કોન્ટ્રાક્ટરે કબુલ રાખવાનો રહેશે. અને આમ કરવાને કારણે મજૂરી કે માલ સામાનનો ભાવ વધારો થશે તો મહાનગરપાલિકા ઉપર કોન્ટ્રાક્ટરનો કોઈ દાવો રહેશે નહીં

(૨૨) આ કામ કોન્ટ્રાક્ટરે માલ મજૂરી સાથે કરવાનો છે. એટલે કે કામમાં જોઈતા મટીરીયલ્સ (હથીયાર, સાધનો સીડી કે ટેકા ત્રાપા) વગેરેનો સમાવેશ થાય છે. આ કામ માટે તેને જોઈતા મજદૂરો (કારીગરો કે સુપરવાઈઝરોનો સમાવેશ થાય છે). કોન્ટ્રાક્ટરે તે કામ કરનારાઓ માટે પીવાના પાણીની વ્યવસ્થા કરવાની છે. જે કોઈ આઈટમમાં સ્પેસીફિકેશન ન હોય ત્યાં મહાનગરપાલિકાના સ્પેસીફિકેશન મુજબ કામ કરવાનું જો ત્યાં પણ સ્પેસીફિકેશન ન હોય તો

જી.ડબલ્યુ.એસ.એસ.બી. ના સ્પેસીફિકેશન મુજબ કામ કરવાનું છે જો ત્યાં સ્પેસીફિકેશન ન હોય પી.એચ.ઈ. ના સ્પેસીફિકેશન મુજબ કામ કરવાનું છે આ શરતો વાંચીને કોન્ટ્રાક્ટરે દરેક પાના પર ટુંકી સહીઓ કરી આપવાની છે. કોઈ કામનું સ્પેસીફિકેશન ઉપરોક્ત જણાવેલ ખાનામાં ન હોય તો એવા કામનું સ્પેસીફિકેશન કોન્ટ્રાક્ટરે મહાનગરપાલિકાના ઈજનેર પાસેથી લેખીત મેળવવાનું રહેશે કામ બાબત કોઈ પણ જાતનો વાંધો કે વાંધાઓ પડે તો તેનો આખરી નિર્ણય શ્રી કમિશનર સાહેબનો રહેશે જે કોન્ટ્રાક્ટરને બંધનકર્તા રહેશે

- (૨૩) કોન્ટ્રાક્ટર તરફથી કામ થઈ ગયા બાદ ૨૪ કલાકમાં સાઈટ સાફ કરી આપવાનું રહે છે તે સમય દરમિયાન સાઈટ સાફ કરવામાં આવશે નહીં તો જગ્યા રોકાણ અંગેનું કામ પુરૂ થયાની તારીખથી ધોરણસર ભાડુ ચડત થશે. અને તે કોન્ટ્રાક્ટર પાસે થી વસુલ કરવામાં આવશે અથવા તો તેઓને ખર્ચે અને જોખમે સાઈટ ઉપર પડેલ માલ મહાનગરપાલિકાના ઈજનેર દ્વારા કરાવશે. અને તેની રકમ કોન્ટ્રાક્ટર પાસેથી વસુલ લેવામાં આવશે
- (૨૪) જે કામ અથવા માલ નાપાસ કરવામાં આવે તે સાઈટ ઉપરથી ૨૪ કલાકમાં ખસેડવાનો રહેશે અને તેમ કરવામાં કસુર થશે તો કોન્ટ્રાક્ટરના ખર્ચે અને જોખમે તે કામ અથવા માલ ખસેડવામાં આવશે.
- (૨૫) ટેન્ડરમાં જણાવેલ કોઈ પણ આઈટમ ખાતા મારફત કરવાની જરૂર જણાશે તો તે કામ ખાતા મારફત કરવામાં આવશે જેના માટે કોન્ટ્રાક્ટર વાંધો ઉઠાવી શકશે નહીં.
- (૨૬) દરેક કામમાં વપરાતો માલવસામાન સીટી એન્જીનીયર સમક્ષ અધિકારીશ્રી પાસે પાસ કરાવી ત્યાર બાદ જ વાપરવાનો રહેશે. યુનો ફોડયા વિનાનો સાઈટ ઉપર લાવી અમારી પાસે પાસ કરાવ્યા બાદ ફોડવાનો છે. યુના મગીયાના આરામાં વપરાતી રેતી તથા યુનો મગીયાનું પ્રમાણ ૩:૨ (૩-રેતી / ૨-યુનો) રાખવાનું છે અને ડબરીયાનું પ્રમાણમાં ૧:૨ (૧ યુનો - ૨ રેતી રાખવાનું છે આરા બરાબર ખાપી તૈયાર કરવાના છે. અને પાણી માટે ખામણા કરી પાણી ભરી તાજા રાખવાના છે. આરા ત્રણ દિવસ કોહવાયા બાદ વાપરવાના છે. તાજે તાજા આરા તથા એક અઠવાડિયાથી વધુ પડતર આરા વાપરવાના નથી. સીમેન્ટ કોંક્રીટના તથા યુના કોંક્રીટના તથા મીશ્રણ પાકા પ્લેટફોર્મ ઉપર કરવાના રહેશે. યુના કોંક્રીટ માટે એક ફુટના થરમાં કાંકરીનો ચઠો કરી તેના ઉપર ૦.૧૫ સે.મી. ૬ ઈંચના થરમાં ડબરીયો નાખી રસબસતુ તૈયાર કરવાનું છે
- (૨૭) જો કોન્ટ્રાક્ટર ચાલુ કામ છોડી જતા રહેશે અગર કામ બંધ કરી દેશે તો મહાનગરપાલિકા તેમને ખર્ચે અને જોખમે કામ ચાલુ કરી શકશે આમ કરવામાં સુધરાઈના કોન્ટ્રાક્ટરના એગ્રીમેન્ટ કરતા વધુ ખર્ચ થશે તો કોન્ટ્રાક્ટર પાસેથી કાયદેસર રીતે વસુલ કરી શકશે અને આ ઊરાંત તેમની સીકયોરીટી ડીપોઝીટ જપ્ત કરી શકશે. અગર બીજા કોન્ટ્રાક્ટર પાસે કોન્ટ્રાક્ટરના ખર્ચે અને જોખમે કામ શરૂ કરાવી શકશે અને આમ કરવામાં એગ્રીમેન્ટ કરતા વધુ ખર્ચ થશે તો

કોન્ટ્રાક્ટર પાસેથી કાયદેસર રીતે વસુલ કરી શકાશે અને તેની સીકયોરીટી ડીપોઝીટ જપ્ત થઈ જશે.

- (૨૮) કોન્ટ્રાક્ટરના દરેક પ્રોગ્રેસીવ બીલમાંથી ૧૦% રકમ મહાનગરપાલિકામાં જમા રહેશે તેનો ફાઈનલ બીલમાં સમાવેશ કરવામાં આવશે
- (૨૯) આ સાથેના પરિશિષ્ટમાં આઈટમ નં.૧ થી ૭ માં દર્શાવેલ ભાવ (દર) બાબતે ભવિષ્યમાં ગેરસમજ ઉપસ્થિત થાય તો તે અંગે સીટી એન્જીનીયર કે સમકક્ષ અધિકારીશ્રીનો નિર્ણય આખરી ગણાશે.
- (૩૦) સીટી એન્જીનીયરશ્રી મારફત ટેન્ડરો ખોલવામાં આવશે ત્યારથી એકસો વીસ (૧૨૦) દિવસમાં ટેન્ડર સ્વીકારવામાં આવેલ છે કે નહિ તેનો નિર્ણય શ્રી કમિશનર સાહેબ મારફત કરવામાં આવશે. આ મુદતમાં જો કોઈ પણ પ્રકારનાં નિર્ણયની જાણ કોન્ટ્રાક્ટરને કરવામાં નહિ આવે તો ટેન્ડરનાં ભાવો કોન્ટ્રાક્ટર કે મહાનગરપાલિકાને બંધનકર્તા રહેશે નહિ પરંતુ કોન્ટ્રાક્ટર અને મહાનગરપાલિકાના સર્વમ અધિકારીશ્રી બંનેની સહમતીથી આવેલ ભાવોનું ટેન્ડર મંજૂર કરવા માટે શ્રી કમિશનર સાહેબ આખરી નિર્ણય કરી શકશે.

ઉપરોક્ત જનરલ સમજૂતી સિવાય ટેન્ડરમાં આપેલ શરતોને આધીન રહીને કામ કરી આપવાનું રહેશે.

- (૩૧) જે કોન્ટ્રાક્ટરના ભાવ મંજૂર થશે અને ભાવ મંજૂર થવાના ખબર મળ્યેથી થયેલ ભાવથી થતી કિંમતના ૫ ટકાની રકમ સીકયોરીટી ડીપોઝીટ તરીકે મહાનગરપાલિકાની ટ્રેઝરીમાં દિવસ-૭ માં ભરી સ્ટેમ્પ ડ્યૂટિ એક્ટ મુજબની રકમના નોનજ્યુડિશિયલ સ્ટેમ્પ પેપર ઉપર મહાનગરપાલિકા દ્વારા માન્ય કરેલ ફોર્મમાં કરારનામું કરી આપવાનું રહેશે આ માટે સ્ટેમ્પ પેપર તેમજ એડહેસિવ સ્ટેમ્પનો ખર્ચ કોન્ટ્રાક્ટરે ભોગવવાનો રહેશે.
- (૩૨) વર્કમેન કોમ્પેન્સેશન એક્ટ હેઠળ ઈન્સ્યુરન્સની ડબલ્યુ.સી.ની પોલીસી લેવાની રહેશે.
- (૩૩) સાઈટ ઉપર ૧૦ કે ૧૦ થી વધુ કામદારો થયે સરકારશ્રીના લેબર એક્ટ મુજબ લેબર લાયસન્સ લેવાનું રહેશે અને તેના પ્રવર્તમાન કાયદાઓનું પાલન કરવાનું રહેશે તેમજ આ કાયદામાં સરકારશ્રી તરફથી વખતો વખત જે કોઈ ફેરફાર થાય તેનો અમલ કરવાનો રહેશે.
- (૩૪) સરકારશ્રીના પ્રવર્તમાન નિયમો અનુસાર ઈ.પી.એફ.નંબર લેવાનો રહેશે તથા આ કાયદામાં વખતો વખત જે કોઈ ફેરફાર થાય તેનો અમલ કરવાનો રહેશે.
- (૩૫) સર્વિસ ટેક્સના કાયદા અનુસાર સર્વિસ ટેક્સ ભરવાની જવાબદારી જે તે કોન્ટ્રાક્ટરશ્રીની રહેશે.

- (૩૬) કચેરી તરફથી સુચવવામાં આવતા કામે લગતા જરૂરી ટેસ્ટ રીપોર્ટ કોન્ટ્રાક્ટરે પોતાના ખર્ચે કરાવી આપવાના રહેશે.
- (૩૭) ગુજરાત સરકારશ્રીના શ્રમ અને રોજગાર વિભાગના જી.આર. નં.સી.ડબલ્યુ.એ/ ૨૦૦૪/૮૪૧/એમ-૩ તા.૩૦.૦૧.૦૬ ના ઠરાવ મુજબ શ્રમીકોના કલ્યાણ માટે બીલની કુલ રકમના ૧% (એક ટકા) લેખે સેસ રકમ રાજકોટ મહાનગરપાલિકા રનીંગ બીલમાંથી કપાત કરશે, તેમજ તેના માટે જરૂરી રજીસ્ટ્રેશન એજન્સીએ સ્વ.ખર્ચે કરવાનું રહેશે.
- (૩૮) કામ રાખનાર કોન્ટ્રાક્ટરશ્રી ૧૦ કે તેથી વધુ કામદારો કામે રાખેલ હશે તો કોન્ટ્રાક્ટરશ્રીએ ઈ.એસ.આઈ. (એમ્પ્લોઈઝ સ્ટેટ ઇન્સ્યોરન્સ) એક્ટ હેઠળ રજીસ્ટ્રેશન કરાવી જરૂરી રજીસ્ટ્રેશન નંબર મેળવવાનો રહેશે. કોન્ટ્રાક્ટરશ્રીએ તેમના હસ્તકના કામદારોને ઈ.એસ.આઈ.એક્ટ હેઠળ મળવાપાત્ર તમામ લાભો આપવાના રહેશે. કોન્ટ્રાક્ટરશ્રીએ ઈ.એસ.આઈ.એક્ટના જે તે સમયે પ્રવર્તમાન તમામ ધારા-ધોરણોનું પાલન કરવાનું રહેશે.
- (૩૯) આ સાથે સામેલ રાખેલ આ કચેરી હુકમ નં.રામનપા/સી/૧૩૨ તા.૧૦.૦૬.૨૦૧૩ તથા પરિપત્ર નં.રામનપા/સી/૩૨૯ તા.૨૨.૧૨.૨૦૧૨ તેમજ અન્ય સામેલ પરિપત્રો વાંચીને તેમાં સહી સીકકા કરી ટેન્ડર સાથે રજૂ કરવાના રહેશે.
- (૪૦) કામાં પુરા પાડવાના હોય તેવા પેવીંગ બ્લોક આઈએસ.આઈ. માર્ક વાળા અને એમ-૩૦ ગ્રેડ ના હોવા જોઈએ જે સક્ષમ અધિકારી પાસે મંજૂર કરાવી ત્યાર બાદ જ કામમાં ઉપયોગમાં લેવાના રહેશે.

એડી.આસી. એન્જીનીયર
રાજકોટ મહાનગરપાલિકા

ડે.એકઝી.એન્જીનીયર
રાજકોટ મહાનગરપાલિકા

સીટી એન્જીનીયર (સ્પે.)
રાજકોટ મહાનગરપાલિકા

કોન્ટ્રાક્ટરની સહી તા સીકકો :

રાજકોટ મહાનગરપાલિકા

બાંધકામ શાખા

સ્પેસીફિકેશન (સમજૂતી)

Item No.1 :

Earth work in cutting including preparing the slope and stacking or utilizing the cutting stuff in bans as directed up to RMC limit from the end of cutting with all leads and lift.

The land with required for the road way shall be cleared of all trees having a girth of 30 cms and less, loose stones, vegetation, bushes, stumps and all other objectionable materials. The roots of trees and stumps shall be removed to a depth of 30 cms below the grade of formation and slope of excavation filled up with excavated materials and compacted. All the materials cleared will be the property of Rajkot Municipal Corporation.

After clearing the site, the alignment of the road shall be properly set out true to lines, curves, grades and sections as shown on plan or directed by the engineer-in-charge. The contractor shall provide all labour and materials such as lime, strings, pegs, nails, bamboos, stone mortal, concrete etc. required for setting out alignment establishing bench marks and giving profiles. The contractor will be responsible for maintaining BM alignments, and other stakes and marks.

The excavation shall be finished neatly smooth and evenly to correct lines, curves, grades if loose shall be scarified watered and compacted. The contractor shall on no account excavate beyond the slope or below the specified level or outside the section. It shall not be paid for and the contractor shall be required to fill up at his own cost with good and approved material by engineer in charge.

All necessary traffic arrangement is to be done by contractor. No extra will be paid for this.

All the excavated materials shall be property of government. The useful excavated material is to be directly deposited at the required location in the specified layers within RMC limit and all lift as per instructions of engineer-in-charge.

The payment shall be made at Rs.12.00/- per square meter basis for excavation up to 20 cm depth. Beyond 20 cm depth, the payment shall be made at Rs.0-50 paisa per square meter per every 5 cm additional depth for additional excavation.

Item No.2:

Removal of flooring of type Shabadi ladi / cement / tiles flooring:

The work of removal of flooring of type Shabadi ladi / cement / tiles flooring shall have to be carried with due care at the place where as instructed and as per requirement of work including cleaning and clearing the site as instructed there after utilizing the same, if required at site as per the instructions of site Engineer. The whole work of removal of should be carried out such that no damage occurs to the same. The transportation of removed material should be done from site by loading, unloading, stacking in Tractor as instructed and dumped within the City limit or Store of Rajkot Municipal Corporation.

The payment will be made for a unit of square meter.

Item No.3**Excavation of Paver Road (except for Road works)****1.0 General:**

- 1.1 Any soil which generally yields to the application of the pickaxes and shovels, phawaras rakes or any such ordinary excavation implement or organic soil, gravel, slit, sand turf lawn, clay, peat etc. fall under this category.

2.0 Cleaning the site:

- 2.1 The site on which the structure is to be built shall be cleared, and all obstructions, loose stone, materials and rubbish of all kind, bush, wood and trees shall be removed as directed. The materials so obtain shall be property of the government and shall be conveyed and stacked as directed within RMC limit. The roots of the tree coming in the sides shall be cut and coated with a asphalt.
- 2.2 The rate of site clearance is deemed to be included in the rate of earth work for which no extra will be paid.

3.0 Setting out:

After clearing the site, the center lines will be given by the engineer-in-charge. The contractor shall assume full responsibility for alignment, elevation and dimension and of each and all parts of the work. Contractor shall supply labors, materials, etc required for setting out the reference marks and bench marks and shall maintain them as long as required and directed.

4.0 Excavation:

The excavation in foundation shall be carried out in true line and level and shall have the width and depth as shown in the drawings or as directed. The contractor shall do the necessary shoring and strutting or providing necessary slopes to a safe angle, at his own cost. The bottom of the excavated area shall be leveled both longitudinally and transversely as directed by removing and watering as required. No earth filling will be allowed for bringing it to level, if by mistake or any other reason excavation is made deeper or wider than that shown on the plan or directed. The extra depth or width shall be made up with concrete of same proportion as specified for the foundation concrete at the cost of the contractor. The excavation upto 1.5 mt depth shall be measured under this item.

5.0 Disposal of the excavated stuff:

The excavated stuff of the selected type shall be used in filling the trenches and plinth or leveling the ground in layers including ramming and watering etc.

The balance of the excavated quantity shall be removed by the contractor from the site of work to a place as directed within RMC limit and all lift.

Mode of Measurement and Payment:

The measurement of excavation in trenches for foundation shall be made according to the sections of trenches shown on the drawing or as per sections given by the engineer-in-charge. No payment shall be made for surplus excavation made in excess of above requirement or due to stopping and sloping back as found necessary on account of conditions of soil and requirements of safety.

The rate shall be for a unit of one square Meter.

Item No.4

Providing and laying in foundation and plinth/ floors lime concrete with black trap metal 4-9 cm nominal size and 50% mortar comprising of 1 Lime putty : 2 fine sand and curing complete including cost of form work.

1.0. Materials:

1.1. Water shall conform to M-I. Sand shall conform to M-6. Lime shall conform to M-2. Graded aggregated 40 mm, nominal size shall conform to M-I2.

2.0. Workmanship:**2.1. General**

2.1.1. Before starting the concrete the bed of the foundations trenches shall be cleared of all loose materials and watered and rammed as directed.

2.2. Proportion of Mix :

2.2.1. The proportion of lime, sand and aggregate shall be specified in the item of the work and shall be measured by volume.

2.2.2. The lime mortar shall consist of proportion of 1 Lime putty : 2 sand volume. The lime mortar shall be prepared by wet process Power driven mill shall be used for preparation of lime mortar. The slaked lime shall be placed in the Mill in even layers and ground for 180 revolutions with sufficient water. The water shall be added as required during grinding (and care shall be taken not to add more water) so that it will bring the mixed materials to a consistency of stiff paste, thoroughly wetted sand shall then be added evenly and the mixture ground for another 180 revolutions.

2.2.3. Lime mortar shall be kept damp, protected from sun and rain till used-up, covering it by tarpauline or open sheds.

2.2.4. All the lime mortar shall be used as soon as possible after grinding. It should be used on the day of which it is prepared but in no case mortar made earlier than 36 hours shall be permitted for use.

2.3. Mixing :

2.3.1. The stack of black trap metal having size 4 cm to 9 cm of good quality having height of 30 cm with lime mortar height of 15 cm over it shall have to be done at the site. Accordingly, the lime concrete is to be mixed properly or it should be mixed as per the instructions of engineer in charge satisfactorily and spreaded at site, properly rammed and compacted and complete the work of lime concrete as per requirement of this item.

Mode of measurement and payment:

The lime work shall be measured in length, breadth and depth as specified in drawing or as directed, correct upto largest centimetre and cubical content shall be worked out upto two places of decimals.

3 2. The rate shall be for a unit of one cubic metre.

Item No.5:

Supply & Fixing of 80 mm M-30 Grade cement concrete rubber mold paving inter locking paving block (Grey colour) after bedding of black stone powder in line and CC on the edge in proportion of 1:2:4 with curing etc. complete.

Scope work:

The scope of work includes supplying and laying of **ISI Mark** approved precast paver blocks at site, as mentioned in the Item. All relevant provisions of IS 15658:2006 shall apply. Laying of paver blocks at site as per requirement in technical specification, within shortest possible time. The site is public place hence care should be taken to ensure that the routine activities shall not be disturbed. The job of laying may required to be carried out during night also. The work shall be executed in perfect line and level as per instructions of Engineer in charge. Colored concrete paver blocks shall be manufactured as per specifications using approved color pigment. The color shade shall be as selected by employer before commencement of the work. The contractor shall guarantee that all material and components designed, fabricated, supplied and laid by him shall be free from any type of defect due to faulty material and/Workmanship/erection For a period of One year from the date of completion of work.

1.0 MATERIALS**1.1 Cement and Cement Admixtures****1.2 Aggregates****1.2.1 Coarse Aggregates**

1.2.1.1 Coarse aggregates shall comply with the requirements of IS 383. As far as possible crushed semi-crushed aggregates shall be used. For ensuring adequate durability, the aggregate used for production of blocks shall be sound and free of soft or honeycombed particles.

1.2.1.2 Other types of aggregates such as slag and crushed, over-burnt brick or tile which maybe found suitable with regard to strength, durability of concrete and freedom from harmful effects may be used in preparation of concrete for production of paver blocks. However such aggregates shall not contain more than 0.5 percent of sulphates as SO₃ and shall not absorb more than 2 percent of their own mass of water.

1.2.1.3 Heavy weight aggregates or light weight aggregates such as bloated clay aggregates and sintered fly ash aggregates may also be used provided the purchaser is satisfied with the data on the properties of concrete made with them.

1.2.1.4 The nominal maximum size of coarse aggregates used in production of paver blocks shall be 12 mm.

1.2.2 Fine Aggregates

Fine aggregates shall conform to the requirements of IS 383. Both river/quarry sand and stone dust meeting the requirements can be used.

1.3 Admixtures

Admixtures, when used shall conform to IS 9103. Previous experience with and data on such materials should be considered in relation to the specified standards of mechanization, supervision and workmanship in production of blocks. They may be added for specific requirements without affecting other quality parameters.

1.4 Pigments

1.4.1 Synthetic or natural pigments may be used in concrete mix to obtain paver blocks with desired shades of colours. The pigment used should result in durable colours of paver blocks. It shall not contain matters detrimental to concrete. Pigments, either singly or in combination, conforming to the following Indian Standards may preferably be used:

<i>Pigments</i>	<i>Relevant Indian Standard</i>
Black or Red or Brown pigment	IS 44
Green pigment	IS 54
Blue pigment or	IS 55 IS 56
White pigment	IS 411
Yellow pigment	IS 50

Pigment quantity to be restricted to a maximum of 9 percent by weight of cement content. The pigment should be finer than the cement (Fineness value between 2-15 m²/kg).

1.4.2 The pigments shall not contain zinc compounds or organic dyes.

1.4.3. Lead pigments shall not be used unless otherwise specified by the purchaser.

1.5 Water

The water used in production of paving blocks shall conform to the requirements specified in IS 456.

2 PHYSICAL REQUIREMENTS

2.1 General

2.1.1 The physical requirements of paver blocks are categorized into two groups, namely:

- a) Obligatory requirements shall be for ensuring durability of pavements constructed with paver blocks as well as obtaining better levels of service in block paving work, and
- b) Optional requirements shall be as per the specific demands of the purchaser. These are described in 6.2 and 6.3.

2.1.2 All paver blocks shall be sound and free of cracks or other visual defects which will interfere with the proper paving of the unit or impair the strength or performance of the pavement constructed with the paver blocks.

2.1.3 When two layer paver blocks are manufactured there shall be proper bonding between the layers. Delamination between the layers shall not be permitted. The compressive strength of the two layer blocks shall meet the specified requirements.

- 2.1.4 When paver blocks with false joints, surface reliefs or projections are supplied, the same shall be specified. Also, the surface features shall be well formed and be devoid of any defects.

2.2 **Obligatory Requirements**

2.2.1 ***Visual Inspection***

Visual inspection of quality of paver blocks shall be carried out in natural daylight, prior to the tests for other properties. The inspection shall be conducted by the purchaser and the manufacturer jointly at a location agreed to between them, normally at the site or factory. Visual inspection shall be conducted as per 7.1.

NOTE— When efflorescence occurs and it is not deleterious to the performance of the blocks in use and is not considered significant.

2.2.2 ***Dimensions and Tolerances***

2.2.2.1 The recommended dimensions and tolerances for paver blocks, measured as per the method in Annex B, are given in Table 2. Minimum block thickness shall be 50 mm and maximum 120 mm. The thicknesses 60 mm, 80 mm, 100 mm and 120 mm will be considered as standard thicknesses under this specification.

2.2.2.2 All blocks manufactured to meet this specification shall have arris/chamfer as per the dimensions and tolerances given in Table 2.

2.2.3 ***Thickness of Wearing Layer***

When paver blocks are manufactured in two layers, the wearing layer shall have minimum thickness as specified in Table 2. The thickness of the wearing layer shall be measured at several points along the periphery of the paver blocks. The arithmetic mean of the lowest two values shall be the minimum thickness of the wearing layer.

2.2.4 ***Water Absorption***

The water absorption, being the average of three units, when determined in the manner described in Annex C, shall not be more than 6 percent by mass and in individual samples, the water absorption should be restricted to 7-percent.

2.2.5 ***Compressive Strength***

2.2.5.1 Compressive strength of paver blocks shall be determined as per the method given in Annex D. Paver block strength shall be specified in terms of 28 days compressive strength. In case the compressive strength of paver blocks is determined for ages other than 28 days, the actual age at testing shall be reported. The average 28 days compressive strength of paver blocks shall meet the specified requirement. Individual paver block strength shall not be less than 85 percent of the specified strength. In case blocks of age less than 28 days are permitted to be supplied, correlation between 28 days strength and the strength at specified age for identified batch/mix of blocks shall be established.

2.2.5.2 The specified average 28 days compressive strengths of different grades of paver blocks are given in Table 3 and the minimum specified strengths of individual paver blocks are given in 6.2.5.1.

Table 2 Recommended Dimensions and Tolerance for paver Blocks
(Clauses 6.2.2.1, 6.2.2.2, 6.2.3 and 9. 1.2)

Sr No	Dimensions	Measurement method, Ref. to	Recommended Values	Tolerance limit for paver block	
				Thickness < 100 mm	Thickness \geq 100 mm
1	2	3	4	5	6
i)	Width, W	Annex-B	To be specified by manufacturer	± 2 mm	± 3 mm
ii)	Length, L	Annex-B	To be specified by manufacturer	± 2 mm	± 3 mm
iii)	Thickness, T	Annex-B	50 to 120 mm	± 3 mm	± 4 mm
iv)	Aspect ratio (L/T)	Annex-B	Maximum : 4.0	+ 0.2	+ 0.2
v)	Arris/chamfer	Annex-B	Maximum : 5.0 Maximum : 7.0	± 1 mm	± 1 mm
vi)	Thickness of wearing layer	6.2.3	Maximum : 6.0	± 2 mm	± 2 mm
vii)	Plan area, A_{Sp}	Annex-B	Maximum: 0.03 m ²	+ 0.001 m ²	+ 0.001 m ²
viii)	Wearing face area, A_{SW}	Annex-B	Minimum 75 percent of Plan Area	-1 percent	-1 percent
ix)	Squareness	Annex-B	Nil	± 2 mm	± 3 mm

Table 3 Compressive Strength Requirements of Concrete Paver Blocks
(Clauses 6.2.5.2 and 9.1 .4)

Sr.No.	Grade of paver blocks	Minimum average 28 days compressive strength N/mm ²
1	2	3
i)	M-30	$\geq f_{ck} + 0.825 \times$ established standard deviation (rounded off to nearest 0.5 N/mm ²)
ii)	M-35	
iii)	M-40	
iv)	M-50	
v)	M-55	

2.2.6 Abrasion Resistance

The abrasion resistance of paver blocks should be determined as per the method given in Annex E. It may be specified the limits to the test results, which should be complied with by the manufacturer.

2.3 Optional Requirements

2.3.1 Tensile Splitting Strength

The tensile splitting strength of paver blocks should be determined as per the method given in Annex F. When required by the purchaser, the test values for tensile splitting strength of paver blocks may be specified by the manufacturer.

2.3.2 Flexural Strength/Breaking Load

The flexural strength/breaking load of paver blocks should be determined as per the method given in Annex G. When required by the purchaser, the test values for flexural strength breaking load of paver blocks may be specified by the manufacturer.

2.3.4 Colour and Texture

When required, the colour and texture of paver blocks should be mutually agreed to between the purchaser and the manufacturer.

3 TEST METHODS

- 3.1 Visual inspection shall be conducted by first examining each paver block from a sample lot for any elimination. The blocks shall then be laid out on a level floor in any desired paving pattern, approximately covering a square area of 1m². Any visual defects of paver blocks, including cracks and flaking, shall be recorded by observing the paved blocks from a distance of approximately 2 m from each edge of the paved area. The texture and colour of the paver blocks shall be compared with the manufacturer's tie samples supplies earlier to the purchaser.
- 3.2 Tests other than for visual aspects shall be carried out in a laboratory agreed to between the purchaser and the manufacturer. Wherever applicable, calibrated equipment shall be used for tests.
- 3.3 Compliance with the obligatory physical requirements laid down in 6.2 shall be ensured by conducting tests as described in Annexes B to E.
Compliance with optional physical requirements laid down in 6.3 shall be ensured by conducting tests as described in Annexes F to H.
- 3.4 Unless otherwise specified in the enquiry or order, the cost of the tests shall be borne as follows:

4 SAMPLING

- 4.1 The paver blocks selected for testing shall be representative of the consignment, the points of selection being evenly distributed through the consignment.
- 4.2 The number of blocks to be sampled from each batch for each test shall be as given in Table 4.

Table 4 Sampling Requirements
(Clause 8.5)

Sr No	Property	Requirement Ref to C1 No.	Test method Ref to	Number of paver blocks for test	
				Quality assurance by Third Party	Quality assurance by Manufacturer / Purchaser
1	2	3	4	5	6
i)	Visual Inspection	6.2.1	7.1	8 ²⁾	4(16) ²⁾
ii)	Dimensions	6.2.2	Annex B	8 ²⁾	4(16) ²⁾
iii)	Thickness of wearing layer ³⁾	6.2.3	6.2.3.	8 ²⁾	4(16) ²⁾
iv)	Water absorption	6.2.4	Annex C	3	3
v)	Compressive strength	6.2.5	Annex D	8	4(16)
vi)	Tensile splitting strength	6.3.1	Annex E	8	4(16)
vii)	Flexural strength / breaking load	6.3.2	Annex F	8	4(16)
viii)	Abrasion resistance	6.2.6	Annex G	8	4(16)

- 1) The number within brackets is the number to be sampled to avoid secondary sampling from the batch if on -the basis of the conformity criteria, additional blocks are required to be tested to assess conformity.
- 2) These blocks may be used for subsequent test.%

- 4.6 The sample paver blocks shall be marked for future identification of the consignment it represents. The block shall be kept under cover and protected from extreme conditions of temperature, relative humidity and wind till they are required for test. The test shall be undertaken as soon as practicable after the sample has been taken.

5 ACCEPTANCE CRITERIA

5.1 **Obligatory Requirements**

- 5.1.1 The lot shall be considered as conforming to the requirements of this specification if the conditions mentioned in 9.1.2 to 9.1.4 are satisfied.
- 5.1.2 The sampled blocks tested for dimensions, aspect ratio, chamfer, plan area, wearing face area, deviation from squareness, and, in the case of two layer blocks, thickness of wearing layer shall meet the tolerance limit specified in Table 2. Blocks with visual defects with sample lot shall not be more than three.
- 5.1.3 For water absorption, the mean value of 3 samples determined shall be not more than the maximum limit specified in 6.2.4.
- 5.1.4 The 28 days compressive strengths and tolerance of 8 numbers of paver blocks manufactured as per the grades of paver blocks recommended in Table 1 shall be as given in Table 3.

5.2 **Optional Requirements**

Acceptance criteria for optional requirements shall be as per mutual agreement by the purchaser and manufacturer.

Care should be taken to see that single sized sands with excessive amount of fines or plastic fines should not be used. The shape of sand particles should preferably be sharp rather than rounded. Since the sharp possess higher strength and resist the migration of sand from under the block to less frequently trafficked areas. Even though sharp sands are relatively more difficult to compact than rounded sands, the use of sharp sands should be preferred for the more heavily trafficked pavements. The beddings and should be free of deleterious materials.

If necessary to restrict fines (silt and/or clay) to 10 percent, since excessive fines make joint filling very difficult. Similarly, it is not advisable to use cement in the joint filling sand which will not only make it difficult to completely fill the joints but would also adversely affect the desired flexibility characteristics of the paving block layer. The joint filling sand should be as dry as possible; otherwise complete filling of joints will be difficult. To overcome the problem of efflorescence on the surface of paving block layer, the joint filling sand should be washed to remove soluble salts.

Preparation of Subgrade: This is the foundation layer on which the block pavement is constructed. The prepared subgrade should be graded and trimmed to a tolerance of ± 20 mm of the design levels, and its surface evenness should have a tolerance of within 15 mm under a 3 m straight edge.

Placing and screeding of bedding sand:

The thickness of the sand bed after compaction should be in the range of 20-40 mm, whereas, in the loose form it can be 25 to 50 mm. It is preferable to restrict the compacted thickness to 20-25 mm to reduce the risk of any localized precompaction, which would affect the final block surface level. Bedding sand should not be used to fill up local depressions on the surface of a base or sub base. The depressions should be repaired in advance before placing sand.

Sand to be used should be uniformly in loose condition and should have a uniform moisture content. Best moisture content is that when sand is neither too wet nor too dry and have a value of 6 to 8 percent. Requirement of sand for a day's works should be prepared and stored in advance and covered with tarpaulin or polythene sheets.

The processed sand is spread with the help of screed boards to the required thickness. The screed boards are provided with nails at 2-3 m apart which when dragged gives the desired thickness. The length of nail should take into account the surcharge to be provided in the uncompacted thickness. Alternatively, the screed can be dragged on edge strips kept on both sides as guide. The sand is subsequently compacted with plate vibrators weighing 0.6 tonnes or more. Level checks shall be carried out on a grid pattern to establish that the desired level is achieved. Local correction can be done either by removing or adding extra sand followed by levelling and compacting the layer. There will be some settlement of sand after the blocks are placed and compacted, which must be allowed for, while fixing the level of sand bed.

The blocks will settle after trafficking in such a manner that the surface profile becomes parallel to base / sub base profile. Sand bed assumes uniform thickness under moving loads.

Laying of Blocks:

Blocks can be laid generally by manual labour but mechanical aids like hand-pushed trolleys can expedite the work.

Normally, laying should commence from the edge strip and proceed towards the inner side. When dentated blocks are used, the laying done at two fronts will create problem for matching joints in the middle. Hence, as far as possible, laying should proceed in one direction only, along the entire width of the area to be paved.

While locating the starting line, the following should be considered:

- On a sloping site, start from the lowest point and proceed uphill on a continuous basis to avoid downhill creep in complete areas.
- In case of irregular shaped edge restraints or strip, it is better to start from straight string line.
- Influence of alignment of edge restraints on achieving and maintaining laying bond

Compaction:

For compaction of the bedding sand and the blocks laid over it, vibratory plate compactors are used over the laid paving units; at least two passes of the vibratory plate compactor are needed. Such vibratory compaction should be continued till the top of each paving block is level with its adjacent blocks. It is not good practice to leave compaction till end of the day, as some blocks may move under construction traffic, resulting in the widening of joints and corners contact of blocks, which may cause spalling or cracking of blocks. There should be minimal delay in compaction after laying of the paving blocks to achieve uniformity of compaction and retention of the pattern of layer; however, compaction should not proceed closer than 1 m from the laying face exception after completion of the pavement.

During the vibratory compaction of the laid blocks, some amount of bedding sand will work its way into the joints between them; the extent sand getting worked up in to the joints will depend on the degree of pre-compaction of sand and the force

applied by the block compactor. Standard compactors may have a weight of about 90 kg, plate area of about 0.3 m² and apply a centrifugal force of about 15 kN, while heavy duty compactors may weigh 300-600 kg, have a plate area of about 0.5-0.6 m² and apply a centrifugal force of 30-65 kN. Where the bedding sand has been pre-compacted and for heavily trafficked block pavements, heavy duty compactors should be used. After compaction by vibratory plate compactors, some 2 to 6 passes of a vibratory roller (with rubber coated drums or those of static weight less than 4 tonnes and nominal amplitude of not more than 0.6 mm) will further help in compaction of bedding sand and joint filling.

Joint Filling:

The importance of complete joint filling cannot be over-emphasised. Unfilled or partially filled joints allow blocks to deflect, leading to loose blocks possibly spalling the edges and a locally disturbing bedding sand layer.

After the compaction of the bedding sand has been completed (and some bedding sand has been forced up in the joints between blocks) the joints should be completely filled with sand meeting the desired specifications. The joint filling sand should be stockpiled at suitable locations for convenience. There should be minimum delay in joint filling the process should in any case, be completed by the end of the day's work.

The operation of joint filling comprises of spreading a thin layer of the joint filling sand on the block surface and working the sand into each joint by brooming. Following this, a few passes of heavy plate compactor are applied to facilitate fine sand to fill the joints. The sand should be broomed or spread over the surface with a small surcharge.

Dry sand and dry blocks are best for the filling of joint, as damp sand tends to stick at the very top of the joints; also, if the blocks are wet and the sand dry, the sand will again stick at the joint top. Hence, if either the blocks or sand are wet, one may get a false impression of the joints being full, but the next rain will reveal that they are actually hollow. If the weather does not allow sand and blocks to be dry, the joint filling sand should be washed in by light sprinkling of water. In this case, several cycles of application of sand, water sprinkling and plate compaction will be necessary to completely fill the joints.

Opening of Traffic:

Until all the joints are completely filled, no traffic should be permitted over the block pavement. In case of lime or cement treated layers in the pavement, it must be ensured that these are given at least 14 to 7 days respectively to cure, before traffic is permitted. The block pavement should be inspected frequently, to ensure that any incompletely filled joints, exposed by traffic and / or weather are promptly filled. Such frequent inspection should be continued till dust and detritus from the roadway tightens the surface of the joints.

Laying and Surface Tolerance:

While the laying, the surface tolerance, given below may be observed:

Layer / Item	Tolerance
Subgrade	+0, -25 mm of nominated level
Select Subgrade / Sub-base	+0, -20 mm of nominated level
Base course	+0, -10 mm of nominated level
	10 mm deviation from a 3 m straight edge

Plan deviation: from any 3 m line from any 10 m line	10 mm (Maximum) 20 mm (Maximum)
Vertical deviation from 3 m line at kerbs intrusions, channels, edge restraints elsewhere	+ 3 mm, -0 mm
Maximum difference in surface level between adjacent paving units.	+ 10 mm, -15 mm
Deviation of finished surface level from designated level	+ 10 mm, -15 mm
Joint width range	2 mm to 4 mm
Percentage of joints outside range	10% max. along 10 m line
Nominal joint width	3 mm

Laying of concrete paving blocks:

Laying of the blocks shall be done, precisely at the indicated level and profile and in a way that a good surface draining to the gulley chambers is assured.

Around gulley chambers and inspection pits the pavement shall have a level of 5 mm higher than the above mentioned elements.

The blocks shall be laid to the pattern directed by the Engineer or the pattern recommended by the designer. The blocks shall be laid as tight as possible to each other. The maximum joint width shall be limited to 4 mm

Laying of broken blocks is not allowed except along connections or edges. The maximum length of a purpose broken block is 100 mm. Breaking of the blocks shall be done with a "block splitter" or a mechanical saw.

Fine angular sand as per specification shall be brushed into the joints, and thereafter compaction shall be done with a vibrating plate compactor on a clean surface. After compaction, again fine angular sand shall be brushed in to the joints.

Field Laboratory Tests:

Necessary field / laboratory tests shall be carried out by the contractor while executing the work at his own cost.

The field / laboratory tests may be conducted in an Engineering College / approved technical institution as directed by the engineer in charge.

The agency shall have to carry out the testing for paving block at Government approved laboratory at his own cost and submit the test report to this office or other relevant provisions of IS:15658-2006 shall apply. The agency shall have to carry out the testing of paving blocks as per the instructions and in the presence of the engineer-in-charge.

Item No.6

Foundation filling with CC work in proportion of 1:2:4 using 1.5 cm to 2.0 cm aggregate including Ramming, Curing etc.

1.0. Materials

- 1.1 Water shall conform to M-1. Cement shall conform to M-2. Sand shall conform to M-4. Stones aggregate 20 mm. nominal size shall conform to M-12.

2.0 Workmanship**2.1 General**

- 2.1.1 Before starting concrete the bed of foundation trenches shall be cleared of all loose materials, leveled, watered and rammed as directed.

2.2 Proportion of Mix

- 2.2.1 The proportion of cement, sand and coarse aggregate shall be one part of cement, 2 parts of sand and 4 parts of stone aggregate; and shall be measured by volume.

2.3. Mixing

- 2.3.1. The concrete shall be mixed in a mechanical mixer at the site of work. Hand mixing may however be allowed for smaller quantity of work if approved by the Engineer-in-charge. When hand mixing is permitted by the Engineer-in-charge in case of break-down of machineries and in the interest of the work, it shall be carried out on a water tight platform and care shall be taken to ensure that mixing is continued until the mass is uniform in colour and consistency. However in such cases 10% more cement than otherwise required shall have to be used without any extra cost. The mixing in mechanical mixer shall be done for a period 1. 1/2 to 2 minutes. The quantity of water shall be just sufficient to produce a dense concrete of required workability for the purpose.

2.4 Transporting & placing the concrete.

- 2.4.1 The concrete shall, be handed from the place of mixing to the final position in not more than 15 minute by the method as directed and shall be placed into its final position, compacted and finished within 30 minutes of mixing with water i.e. before the setting commences.
- 2.4.2 The concrete shall be laid in layers of 15 cms to 20 cms.

2.5. Compacting:

- 2.5.1 The concrete shall be rammed with heavy iron rammers and rapidly to get the required compaction and to allow all the interstices to be filled with mortar.

2.6. Curing

- 2.6.1 After the final set, the concrete shall be kept continuously wet if required by ponding for a period of not less than 7 days from the date of placement.

2.7. Mode of measurements and payment:

- 2.7.1 The concrete shall be measured for its length, breadth, and depth, limiting dimensions to those specified on plan or as directed.
- 2.7.2 The rate shall be for a unit of one cubic metre.

Item No.7**Removal of Excavated Stuff and Laying within the sites specified in Notification as directed by Engineer-in-Charge**

After Refilling the pipe / chamber trenches by the excavated stuff is 15 cm thick layer, including ramming, watering and consolidating up to possible extent as specified in excavation & refilling item, the surplus stuff shall be disposed off at the following sites as directed within the prescribed limits of Notification as directed by the engineering in charge.

1. Beside Kotharia Police Station near Stone Quarry
2. All Quarry areas of Raiya Smart City

If the contractor fails to dispose the excavated stuff as specified, penalty will be imposed by Rajkot Municipal Corporation as per the Notification for C&D waste,

After refilling surplus earth shall have to carted by the contractor within specified limit including loading transporting unloading spreading without any extra cost.

Mode Of Measurement And Payment:

The rate shall be per Cubic Meter of truck-body basis.

એડી.આસી. એન્જીનીયર
રાજકોટ મહાનગરપાલિકા

ડે.એકઝી.એન્જીનીયર
રાજકોટ મહાનગરપાલિકા

સીટી એન્જીનીયર (સ્પે.)
રાજકોટ મહાનગરપાલિકા

કોન્ટ્રાક્ટરની સહી તા સીકકો :

GENERAL TECHNICAL GUIDELINE

- 1.0 All the items occurring in the work and as found necessary during actual execution shall be carried out in the best workman like manner as per specifications and the written order of the Engineer in charge
- 1.1 Extra Claim in respect of extra work shall be allowed only if such work is ordered to be carried out in writing by the Engineer in charge
- 1.2 The contractor shall engage a qualified Engineer for the Execution of work who will remain present for all the time on site and will receive instructions and orders from the Engineer in charge or his authorized representative. The instruction and orders given to the contractor representative on site shall be considered as it given to the contractor himself.
- 1.3 The work order book as prescribed shall be maintained on the site of the work by the contractor and the contractor shall sign the orders given by the inspecting officers and shall carry out them properly.
- 1.4 Quantities specified in the tender may vary at the time of actual execution and the contractor shall have no claim for compensation on account of such variation
- 1.5 Unexcavated lengths shall be left wherever required and so directed by the Engineer in charge during the currency of the contract and shall be tackled. If required, before completion of work.
- 1.6 Diversion of road, if necessary, shall be provided and maintained during the currency of the contract by the contractor at his cost.
- 1.7 Figured Dimensions of drawing shall supersede measurements by scale, special dimensions or directions in the specifications shall supersede all other dimensions.
- ~~1.8 The contractor shall be responsible to take regular level on the approved alignment before actually starting the work. The levels shall be commensurate to the G.T.S. levels and shall be got approved from the Engineer in charge~~
- 1.9 If the arrangement of temporary drainage or waterway is required to be made during any work of this Contract, this shall be made by the Contractor without claiming any extra cost.
- 2.0 The rates are inclusive of dewatering, if required.
- 3.0 Testing of the materials like Paving Blocks, Sand, Field Metal, Aggregate, etc. should have to be tested periodically as suggested by the Engineer-in-charge at Government approved material testing Laboratory and testing charges for the same has to be borne by the contractor.

Addl.Asst.Engineer
Rajkot Muni. Corporation

Dy.Ex.Engineer
Rajkot Muni. Corporation

City Engineer (Sp.)
Rajkot Muni. Corporation

Signature of contractor

Bidders are required to fill up all blank spaces in this Bid Form

The Commissioner
Rajkot Municipal Corporation
Dr. Ambedkar Bhavan
Dhebar Road
Rajkot

Dear Sir,

SUB : માનનીય ધારાસભ્યશ્રી ગોવિંદભાઈ પટેલની સને ૨૦૧૮-૧૯ ધ્વની ગ્રાન્ટમાંથી વોર્ડ નં. ૧૮ માં આવેલ બાપાસીતારામ ચોક થી રંગીલા પાર્ક બગીચા સુધીના શ્રદ્ધાપાર્ક મેઈન રોડની બન્ને સાઈડમાં ઇન્ટરલોકિંગ પેવિંગ બ્લોક્સ નાખવાનું કામ

Having visited the site and examined the Bid Documents, Drawings, Conditions of Contract, Specifications, Schedules, Annexures, Preamble to Price Schedules, Price Schedules etc. including Addenda/Amendments to the above, for the execution of the above Contract, we the undersigned offer to carry out as given in Conditions of Contract and in conformity with the Drawings, Conditions of Contract, Specifications, Preamble to Price Schedules, Price Schedules, Annexures, Bidding Documents, including Addenda Nos. _____ (insert numbers) for _____ %age (in figure) _____ (in words) below / above than the rates given in Price Schedule.

2. I / We agree that

- (a) if we fail to provide required facilities to the Employer's representative or any other person/agency by the employer to perform on his behalf for carrying out the inspection and testing of materials and workmanship
- or
- (b) if we incorporate into the Works, materials before they are tested and approved by the Engineer's representative
- or
- (c) if we fail to deliver raw water of required quantity according to the conditions/stipulations of the Contract, the Engineer will be at liberty to take any action including termination of Contract and impose at his absolute discretion any penalties, and/or reject the work.

- 3. We undertake, if our Bid is accepted, to complete and deliver the Works in accordance with the Contract within the time limit as described in the tender document, from the date of Work order issued to us by you.
- 4. We agree to abide by this Bid for a period of 120 days from the date fixed for receiving the same and it shall remain binding upon us and may be accepted at any time before the expiry of that period.

5. In the event of our Bid being accepted, we agree to enter into a formal Contract Agreement with you incorporating the conditions of Contract thereto annexed but until such agreement is prepared this Bid together with your written acceptance thereof shall constitute a binding Contract between us.
6. We agree, if our Bid is accepted, to furnish Performance Bond/Security in the forms and of value specified in the Conditions of Contract of a sum equivalent to 5% of the Contract price for due performance of the Contract.
7. We have independently considered the amounts of liquidated damages shown in Appendix to Bid and agree that they represent a fair estimate of the damages likely to be suffered by you in the event of the Work not being completed by us in time.
8. I/We agree to pay the Government Income-Tax, CGST, SGST, Sales Tax on contraction, Labour Cess, Professional Tax and Other Taxes prevailing from time to time on such items on which the same leviable and the rates quoted by me/us are inclusive of the same.
9. We understand that you are not bound to accept the lowest or any Bid you may receive.

Dated this _____ day of _____ 2020.

(Signature)

(Name of the person)

(In the capacity of)

Company Seal

(Name of firm)

Duly authorised to sign Bid for and on behalf of
(Fill in block capitals)

Witness

Signature

Name

Address

ADDITIONAL CONDITIONS

1. The contractor shall have to provide his own level instrument for this work.
2. The safety of the traffic is the prime important factor. Along the trenches on both the side, a hump of excavated stuff shall have to be provided till the work is got completed. However, where there is no defined road, in such area, the fencing/ lighting etc., requires to be provided as per clause 1.1.15. Sign Board shall have to be provided at required locations, so that there will not be any fatal accident.
3. While the work in progress, there is possibility of change in location line according to the site conditions. Under these circumstances, the contractor shall have to carry out the work accordingly, for which, no extra payment shall be made in such situations. Over and above, the decision of Engineer-in-charge for change in line shall be final and binding to the contractor.
4. In case of any ambiguity found in inspections / drawings, specifications, etc, the decision of engineer-in-charge shall be final and binding to the contractor.
5. Rates quoted in Bill of Quantities to cover everything necessary for complete Execution of work :

The rates quoted will be held to cover everything necessary of the due and complete execution of the work according to the drawings and the several conditions and the stipulations of the contract, including specification, or the evident intent and meaning of all or either of them or according to customary usage and for the periodical and final inspection and test and proof of the work in every respect and for measuring, numbering or weighing the same including setting out and laying or fixing in position and the provision of all materials,

Power, tool rammers, beaters, labour, tackle platforms with impervious lapped joints for scaffolding ranging rods, straight edges, centering and boxes, wedges, moulds, templates, post straight rails, boning-staves, measuring rods, page boards, shores, barriers, fencing, lighting, pumping apparatus, temporary arrangements of passage of traffic, access to premises and continuance of drainage, water supply and lighting (if interrupted by the work) lard temporary sheds and buildings nahanis roofed in or otherwise haulage, painting, varnishing, polishing, establishments for efficient supervision and watching arrangements for the efficient protection of life and property and all requisite plant, implements and appliances every kind, except only such matter and things as it may be distinctly stated here in are to be supplied by the contractors. A rate for anyone description of work is to be held to include such items of other classes of and for these on separate specific charge will be admitted. The contractors shall keep every portion of the work clear of accumulation from time to time and shall leave every portion of the work clean, clear, perfect and at the conclusion of whole, providing at their own cost all such material implement appliances and labour as the Engineer may require to prove if it is to be so.

6. The contractors are particularly directed to observe from the Articles of Agreement and the specifications, what is to be included in their rates for the several portions of the work and also under what conditions payments are to be made.
7. The contractor shall have to avail P F Code as per the prevailing Circular of Government for the employees on work. The process for preparation of bill will be taken up only after submission of the Challan for the amount of P.F. deposited

every month for the employees on work, which will binding to the contractor. The required documents shall have to be submitted every month by the contractor to the competent authority.

8. The contractor shall have to get registered under ESI (Employer's State Insurance) Act and obtain ESI Registration number if the number of workers are 10 Nos. or more. Also, the agency shall have to give all the benefits to the workers as available under the ESI Act. The agency should follow all the rules and regulations of ESI Act as per prevailing norms.
9. This office Circular bearing No.RMC/C/329 dated 22-12-2012 and Order No.RMC/C/132 dated 10-06-2013 are uploaded separately as a part of tender document. The Contractors/Consultants quoting their rates shall have to read, implement, and submit the same duly signed along with the documents to be submitted during physical submission.
10. In reference to the above Circular and Order cited para above, the Contractors/Consultant who have quoted their rates for this work will be called in person for verification of original documents. The date and time for verification of original documents will be as prescribed in the tender document.
11. After issuance of work order for this tender, if the work falls under any kind of dispute then Rajkot Municipal Corporation reserves the right to terminate the contract for this work awarded to the contractor or execute part work. The decision of Rajkot Municipal Corporation in this regard will be final and binding to the contractor.
12. Till the Completion Certificate is issued by Rajkot Municipal Corporation, the agency will be the sole responsible for security of material and structure at site.
13. The quantities given in the Schedules are provisional. The Rajkot Municipal Corporation reserves the right to increase or decrease the quantity of work or totally omit any item work and the contractor shall not be entitled to claim any extras or damages on these grounds & he is bound to execute the work as per the instruction of the Engineer-in-charge. Rajkot Municipal Corporation will not entertain any dispute in this regard.
14. It is further clarified that Performance Guarantee (SD) for extra work will also be recovered @ 10% from the bill of extra work i.e. works beyond tender amount.
15. The bidder must understand clearly that the prices quoted are for the totally works or the part of the total works quoted for and include all costs due to materials, labour, equipments, supervision, other services, royalties, taxes, duties, etc., and to include all extra to cover the cost. No claim for additional payment beyond the prices quoted will be entertained and the bidder will not be entitled subsequently to make any claim on any ground.
16. Qualified engineer must be deployed on site and at Plant. The details of qualified engineers are to be given to RMC at the time of bidding of this tender.
17. The whole work shall be executed by qualified Site Engineer. ~~The required L Section and Cross section is to be prepared by contractor at his own cost. The work should be done by leveling instrument. The Drawings shall be submitted accordingly in advance before starting the work. No extra payment will be made for the above work. Contractor has to submit Bill form with hard copy and soft~~

~~copy of cross section and L-section of work completed. No bill be accepted without above drawings.~~

18. If any irregularities found during the work then penalty will be imposed by Engineer-in-charge or any higher officer. If any disputes arises regarding penalty imposed by Engineer-in-charge than decision of Municipal Commissioner will be final and binding to agency.
19. The time limit will remain same as mentioned in the tender document and the work is to be completed accordingly.
20. Tender of such Contractor not having registration in appropriate Class and Category, will be treated as non-responsive. In case of any conflicting provisions between registration of appropriate category and Pre-qualification criteria, the later shall govern the process of bid evaluation.
21. The agency shall have to quote their rates only after visiting the site and looking to the site conditions.
22. DEFECTS: Date of completion for start of defect liability period for a particular road will be considered as the last date mentioned in the completion of work recorded in Measurement Book. The contractor shall be required to make good all the damages / defects identified and conveyed to him, during the entire defect liability period. The method and time limit of rectification will be decided by the Engineer in charge. If the contractor fails to carry out rectification as per the instructions, the same will be carried out at his cost and the cost will be recovered from the amount retained.
23. Joint venture shall not be allowed under this tender.
24. After the completion of work, at the interval of every month, joint inspection must be done by the agency and RMC staff and then agency has to submit the report stating the condition of road to Rajkot Municipal Corporation. The final checking report stating the condition of road is also to be submitted by the agency before one month of the expiry of defect liability period to the competent authority.
25. The Royalty of each and every material, required to be paid is to be borne by the contractor.
26. Testing of each material as and when required by Rajkot Municipal Corporation, is to be carried out in Government approved laboratory by the contractor at his own cost. Schedule of testing of material will be as per R&B, State Government Manual and I S Code provision.
27. Necessary tests for material quality, soil tests etc. shall be carried out as per the instructions of engineer-in-charge by contractor at his own cost and reports to be submitted to the engineer-in-charge.
28. The testing of metal and the design as per IRC shall have to carried out by the contractor at his own cost.
29. As the the work is required to be carried out on both the sides of the road near building line, all due precautions should be taken so that no damage occurs to any of the services like; water connection, drainage connection, water pipeline, drainage line or any other services. However, if any damage occurs to any of such

service(s) then the contractor shall have to carry out necessary repairs immediately and satisfactorily, at his own cost.

30. Wherever the rolling with the road roller is not possible on metalling work and murrum work, the compaction with hand roller or by any other means at such places shall have to be carried out by the contractor satisfactorily as per instructions of engineer-in-charge
31. The Contractor shall carry out modifications in the procedure of work, if found necessary, as directed by the Engineer during inspection. Works falling short of quality shall be rectified/ redone by the Contractor at his own cost, and defective work shall also be removed from the site of works by the Contractor at his own cost.
32. **Defective Materials:** All materials which the Engineer/ his representative has determined as not confirming to the requirements of the Contract shall be rejected whether in place or not; they shall be removed immediately from the site as directed. Materials, which have been subsequently corrected, shall not be used in the work unless approval is accorded in writing by the Engineer. Upon failure of the Contractor to comply with any order of the Engineer/ his representative given under this clause, the Engineer-in-charge shall have authority to cause the removal of rejected material and to deduct the removal cost thereof from any payments due to the contractor.
33. All levels (LS & CS) and Drawings with total station survey of the aforesaid area as well as nearby main roads etc., are to be submitted to the competent authority of RMC and shall have to be got approved from the Engineer-in-charge.
34. The word "Arbitration" or "Arbitration Clause" wherever mentioned in this tender document, is now to be treated as "Deleted". In this context, an Order bearing No.RMC/Legal/1858 dated 18-02-2017 of Legal Department of Rajkot Municipal Corporation is uploaded separately along with this tender, which Order, will hereafter be referred and taken into consideration for Arbitration related purpose for the tenders of Rajkot Municipal Corporation.
35. **Interpretations of Technical Specifications**
If RMC finds discrepancies, or omission in the Technical specifications or other documents or should be in doubt as to their meaning, Addl. City Engineer, R.M.C will accordingly interpret such technical specifications of this tender as per actual requirement of work/item. Such interpretation / decision in the Technical specifications will be binding to the contractor to execute and complete the whole work accordingly.

Addl.Asst.Engineer
Rajkot Muni. Corporation

Dy.Ex.Engineer
Rajkot Muni. Corporation

City Engineer (Sp.)
Rajkot Muni. Corporation

Signature of Contractor

Note on Schedule

1. The bid is percentage rate bid.
2. The rates and prices shall be submitted in the formats given in the Price Schedules. Rates and prices received in any other formats will be rejected and the Bids will be disqualified.
3. It will be entirely at the discretion of the Employer to accept or reject the bidder's proposal, without giving any reasons whatsoever.
4. In Price Schedule, bidder shall quote his percentage Equal/Above/Below for items listed in the schedule. Prices quoted in Schedule only will be considered for price evaluation & shall form a part of the Contract Agreement.
5. The Only Price Schedule will be considered for financial evaluation of the bid with the successful bidder.
6. The bidder shall be deemed to have allowed in his price for provision, maintenance and final removal of all temporary works of whatsoever nature required for construction including temporary bunds, diverting water, pumping, dewatering etc. for the proper execution of works. The rates shall also be deemed to include any works and setting out that may be required to be carried out for laying out of all the works involved.
7. Where there is a discrepancy between the unit rates and the amount entered, the latter shall govern.
8. The Price Schedules are to be read in conjunction with the Conditions of Contract, the Specifications and other sections of these bid documents and these documents are to be taken as mutually explanatory of one another.
9. Prices quoted by the bidder shall be firm for the entire period of Contract without any escalation.
10. The bidder shall interpret the data furnished and carry out any additional survey work, or investigative work required at his own cost.
11. The prices quoted shall also include the cost of materials utilized for testing.
12. The bidder should acquaint himself with the site conditions including the access to Worksite. The successful bidder shall have to make suitable access to worksites at his own cost. These accesses will be used by the other contractors working for RMC.
13. The material shall be inspected Departmentally, the cost of which, if any, is to be borne by contractor.

14. The contractor shall have to quote their rates including GST and other taxes and the Invoice with break-up of GST is to be submitted accordingly, failing which, such amount will be deducted from the bill of the agency and deposited accordingly.

The contractor shall have to purchase the material required for this tender work, only from the supplier having registered GST Number. RMC will not be responsible to pay any amount towards GST if the material is purchased from the unregistered supplier / not having GST Number.

15. Necessary tests for material quality, Paving Blocks, soil tests etc. shall be carried out as per the instructions of engineer-in-charge by contractor at his own cost and reports to be submitted to the engineer-in-charge.
16. In case of extra item, no On %age i.e. +ve %age rate will be given but if there is Down %age i.e. -ve %age rate, that will be applied to that rate of that extra item.

Addl.Asst.Engineer
Rajkot Muni. Corporation

Dy.Ex.Engineer
Rajkot Muni. Corporation

City Engineer (Sp.)
Rajkot Muni. Corporation

Signature of Contractor.

(રૂપીયા ૧૦૦/- ના સ્ટેમ્પ પેપર ઉપર - નોટરાઈઝ્ડ કરેલ)

:: સોગંદનામું ::

હું / અમો આથી જાહેર કરું છું / કરીએ છીએ કે ભારત સરકાર / ગુજરાત સરકાર અથવા અન્ય રાજ્ય બોર્ડ / કોર્પોરેશન દ્વારા અમો / અમારી કંપની ને બ્લેક લિસ્ટ / ટર્મિનેટ / ડિબાર કરવામાં આવેલ નથી અને કંપની / સંસ્થાની શરૂઆત થી જ કોઈ પણ ઇન્કવાયરી / કેસ પેન્ડિંગ નથી, વધુમાં મારી / અમારી વિરુદ્ધ કોઈ પ્રકારની પોલિસ ફરિયાદ થયેલ નથી. સદરહુ કામે રજૂ કરેલા વેરીફાય કરવાના થતાં તમામ ઓરિજનલ ડોક્યુમેન્ટ્સ સાચા છે

આથી હું / અમો ફરી ખાતરી આપું છું / છીએ કે ઉપરોક્ત સોગંદનામું ખોટું / અસત્ય અથવા ગેરમાર્ગે દોરનાર સાબિત થશે તો મારું / અમારું ટેન્ડર રદબાતલ ગણશે.

તારીખ:

સ્થળ :

સંસ્થા / કંપનીના અધિકૃત વ્યક્તિની સહી

તથા સિક્કો

R.M.C./C./ ૧૩૨

કમિશનર વિભાગ,
રાજકોટ મહાનગર સેવાસદન
તા. ૧૦/૬/૨૦૧૩

હુકમ :-

વિષય:- ઈ-ટેન્ડર / ઓપન ટેન્ડર પદ્ધતિથી મંગાવવામાં આવતી તમામ પ્રકારની ઓફરો સાથે બિનઅધિકૃત રજુ થતાં ડોક્યુમેન્ટસ સામે કડક કાર્યવાહી હાથ ધરવા બાબત.

સંદર્ભ :- આ અગાઉનાં પરીપત્ર નં. આર.એમ.સી./સી./૩૨૯, તા.૨૨/૧૨/૨૦૧૨.

રાજકોટ મહાનગર સેવાસદનના ત્રણ જોનનાં તમામ વોર્ડમાં શહેરનાં વિકાસ તથા જાળવણી માટે વિવિધ કામગીરી કરાવવા ઈ-ટેન્ડર / ઓપન ટેન્ડર પદ્ધતિથી અલગ-અલગ એજન્સીઓ પાસેથી સ્પર્ધાત્મક ધોરણે અખબારી પ્રસિધ્ધિથી ભાવો દુ બીડ સીસ્ટમ (૧) ટેકનીકલ બીડ (૨) પ્રાઈઝ બીડ ધી મંગાવવામાં આવે છે.

સંદર્ભના પ્રસિધ્ધ કરેલ પરીપત્ર મુજબ તમામ ઈ-ટેન્ડર / ઓપન ટેન્ડરથી મંગાવવામાં આવતાં ભાવો સાથે ભાવ ભરનાર એજન્સીઓ / બીડરો દ્વારા ટેન્ડર બીડ માટે રજુ કરવાનાં થતાં તમામ ડોક્યુમેન્ટસ ફરજિયાતપણે ખરી નકલમાં અથવા સેલ્ફ એટેસ્ટેડ રજુ કરવા આદેશ કરવામાં આવેલ છે. જે સંબંધે નીચે મુજબનાં હુકમની અમલવારી તાત્કાલીક અસરથી કરવા આદેશ કરવામાં આવે છે.

(૧) તમામ ટેન્ડરકામોના ટેકનીકલ બીડ ઓપન કરતી વખતે જે ટેન્ડર બીડ ભરનાર એજન્સીઓ દ્વારા તમામ ડોક્યુમેન્ટસ કે તે પૈકી કોઈપણ એક ડોક્યુમેન્ટસ ખરી નકલમાં અથવા સેલ્ફ એટેસ્ટેડ રજુ કરેલ ન હોય તો રજુ થયેલ ટેકનીકલ બીડ ઓપન કરવાની કાર્યવાહી દરમ્યાન ટેકનીકલ બીડ ઓપન કરનાર સંબંધિત અધિકારીશ્રી / કર્મચારીશ્રીએ Disqualify પ્રકારનો રબર સ્ટેમ્પ બિનઅધિકૃત રજુ થયેલ ટેન્ડરનાં તમામ પાને લગાવી ટેકનીકલ બીડમાં ટેન્ડર Disqualify ફરજિયાતપણે કરવાનું રહેશે.

જે ટેન્ડર ખરી નકલ કે સેલ્ફ એટેસ્ટેડ સાથે રજુ થયેલ નથી, તેવું ટેકનીકલ બીડમાં ધ્યાને આવ્યેથી રજુ થયેલ ટેન્ડરને Disqualify ન કરી, તે બીડરનું જો પ્રાઈઝ બીડ ખોલવામાં આવશે તો આવા પ્રાઈઝ બીડ ખોલનાર તમામ સંબંધિત અધિકારીશ્રી / કર્મચારીશ્રી સામે સખત શિક્ષાત્મક પગલાં લેવાની ફરજ પડશે.


(૨) તમામ ટેન્ડરોનાં કિસ્સાઓમાં સંબંધિત ખરી નકલમાં રજુ થયેલ તમામ ડોક્યુમેન્ટસની મુજબ (ઓરીજીનલ) નકલ મંગાવી તેની ખરી નકલની ચકાસણી ફરજિયાતપણે સંબંધિત ડી.ઈ.ઈ.શ્રી તથા મ.ઈ.શ્રી / અ.મ.ઈ.શ્રીએ કરવાની રહેશે. જે મુજબ નકલ સાથે વેરીફાઇ કર્યાની સહી ફરજિયાતપણે દરેક ખરી નકલમાં સંબંધિત ડી.ઈ.ઈ.શ્રી / મ.ઈ.શ્રી / અ.મ.ઈ.શ્રીએ કરવાની રહેશે. તે પહેલાં તે ટેન્ડરની પ્રાઈઝ બીડ ઓપન કરી શકાશે નહીં, જેમાં ફરજિયાત થયેથી સંબંધિત જવાબદાર ડી.ઈ.ઈ.શ્રી / મ.ઈ.શ્રી / અ.મ.ઈ.શ્રી ની સામે કડક ખાતાકીય પગલાં લેવાની ફરજ પડશે.

(૩) ક્રમ નં. (૧) તથા (૨) મુજબની ચકાસણી કરવા છતાં જે કિસ્સામાં ટેકનીકલ બીડ ઓપન કરતાં બીડર દ્વારા કોઈપણ પ્રકારનાં ફોડ ડોક્યુમેન્ટસ રજુ કરી કામ મેળવવા માટે પ્રયાસ કર્યાનું સાબિત થશે, તેવા કિસ્સામાં બીડર / એજન્સીને બ્લેકલીસ્ટ કરી, આવા બીડર સામે ફરજિયાતપણે ફોજદારી કાર્યવાહી સંબંધિત શાખાના વડા તથા વીજલન્સ અધિકારીશ્રી (પ્રોટેક્શન) દ્વારા જોઈન્ટલી દિન-૭ માં કરવા આદેશ કરવામાં આવે છે. જેની લેખિતમાં

જાણ તાત્કાલીક અંગે કરવાની રહેશે. જેમાં ચૂક થયેલી સંબંધીત તમામ અધિકારીશ્રી / કર્મચારીશ્રી સામે કડક પગલાં લેવા ફરજ પડશે.

- (૪) સંદર્ભનો પરીપત્ર તથા આ હુકમ તમામ પ્રકારનાં ટેકનીકલ કામના દરેક ટેન્ડર પ્રસિધ્ધ કરતી વખતે ટેન્ડરનો હિસ્સો ગણી ટેન્ડરના ભાગ તરીકે પ્રસિધ્ધ કરવાનું ફરજિયાત રહેશે, તથા બીડર દ્વારા ટેન્ડરમાં પ્રસિધ્ધ થતાં સંદર્ભનાં પરીપત્ર તથા આ હુકમનાં દરેક પાને સહી સિક્કા સાથે ભરેલ ટેન્ડરની ટેકનીકલ બીડ ફરજિયાત રજુ કરવાની રહેશે.

ઉપરોક્ત હુકમનો તાત્કાલીક અસરથી ચુસ્તપણે અમલ કરવા આદેશ કરવામાં આવે છે.


કમિશ્નરશ્રી

રાજકોટ મહાનગર સેવાસદન

નકલ રવાના (જાણ અર્થે):-

નાયબ કમિશ્નરશ્રીઓ (તમામ)

નકલ જાણ તથા અમલવારી અર્થે :-

(૧) સહાયક કમિશ્નરશ્રીઓ (તમામ)

(૨) શાખાધિકારીશ્રીઓ (તમામ)

આર.એમ.સી./સી. ૩૨૪

રાજકોટ મહાનગરપાલિકા


કમિશનર વિભાગ

તા.૨૨/૧૨/૨૦૧૨

પરિપત્ર:-

ઇ-ટેન્ડર પદ્ધતિ / ઓપન ટેન્ડર પદ્ધતિથી માંગવામાં આવતી ઓફરોમાં એજન્સીઓ દ્વારા ટેકનીકલ બીડમાં રજૂ કરવામાં આવતા ડોક્યુમેન્ટ્સ જેવા કે ટર્નઓવર, અનુભવના પ્રમાણપત્રો વિગેરે ખરી નકલમાં રજૂ કરવામાં આવતા નથી. આથી હવે પછીથી એજન્સીઓ દ્વારા રજૂ થતાં ટેકનીકલ બીડમાં રજૂ કરવામાં આવતા ડોક્યુમેન્ટ્સ ખરી નકલમાં અથવા સેલ્ફ એટેસ્ટેડ હોવા જરૂરી છે તેમજ જે એજન્સીનું ટેન્ડર ટેકનીકલ બીડમાં ક્વોલીફાય થાય અને ખરી નકલ ગેઝેટેડ ઓફીસર મારફત પ્રમાણિત કરાવેલ ન હોય તેવા કેસમાં તેના ઓરીજીનલ ડોક્યુમેન્ટ્સ પ્રાઇસબીડ ખોલતા પહેલા ચકાસી અને ખરી નકલ રજૂ કરાવીને જ ખોલવાના રહેશે તથા આ બાબતનું શાખાધિકારીશ્રીઓએ ચુસ્તપણે પાલન કરાવવાનું રહેશે. આમ ન થયેથી પુરતી ચકાસણીને અભાવે જો કોઇ એજન્સીને ખોટા કે અધુરા આધારો સાથે કામ આપવાની ક્ષતિજનક બાબત જાણમાં આવ્યે તે ટેન્ડર ડોક્યુમેન્ટ્સની ચકાસણી કરનાર કર્મચારીશ્રીઓ તેમજ શાખાધિકારીશ્રીની જવાબદારી નક્કી કરવામાં આવશે, જેની સર્વે શાખાધિકારીશ્રીઓએ નોંધ લેવી.

ઉપરોક્ત બાબતનો અમલ તાત્કાલિક અસરથી કરવો.



કમિશનર

રાજકોટ મહાનગરપાલિકા

નકલ રવાના :- (જાણ અર્થે)


- નાયબ કમિશનરશ્રીઓ (તમામ)

નકલ જાણ તથા અમલવારી અર્થે :-

- સહાયક કમિશનરશ્રીઓ (તમામ)

- શાખાધિકારીશ્રીઓ (તમામ)

જોજદારી કાર્યરીતી અધિનિયમ ૧૯૭૭ (૧૯૭૪ના નં.૨) ની કલમ ૧૪૪ અન્વયે કહેલ હુકમ



ક્રમાંક: એસ.બી./મજુર/જાહેરનામું/૫૬૭૬૨૦૧૪.

પોલીસ કમિશનરીની કચેરી,

રાજકોટ શહેર, રાજકોટ.

તા. ૨૬/૦૪/૨૦૧૪

સાજીતરમાં રાજકોટ શહેરમાં ઘરફીડ ચોરીના બનાવો વધવા પામ્યા છે. ભુતકાળના રાજકોટ શહેરમાં બનેલ ઘરફીડ ચોરીના બનાવોની તપાસ કરતા તપાસમાં આવા ગુનો કરનાર (ઘરફીડીયા) પકડાયેલ છે. ત્યારે તપાસમાં આવા ગુનો વાળા આરોપીઓ ગુનાના બનાવના હિલસો અગાઉ રાજકોટ શહેરમાં નવા બંધાતા મકાનોમાં જુદી જુદી ઓધોગીક કંપનીઓમાં, કોર્પોરેશનમાં મજુરી કામ અને ટેલીફોન કંપનીઓ દ્વારા તથા ગેસ પાઇપ લાઇન માટે ખોદાતા ખાડાઓની મજુરી કામ મેળવી અથવા તેના બહાના હેઠળ આવી રોકાણ કરી આગુવાગુની સ્થાનિક પરીસ્થિતિનું સર્વે કરી માફિતગર થઇ મિલકત વિરુદ્ધના ગુનોઓ આચરતા હોય છે. મજુરી કામના બહાના હેઠળ આતંકવાદીઓ પણ આશરો મેળવી લેતા હોય છે જેથી જાહેર જનતાની જાન-માલ (મિલકત)ની સલામતી તથા સુરક્ષા કાઠુ થોડા નિયંત્રણો મુકવા જરૂરી જણાય છે.

જેથી હું મોકલ ગ્રા (I.P.S.), પોલીસ કમિશર, રાજકોટ શહેર જોજદારી કાર્યરીતી અધિનિયમ (સી.આર.પી.સી.) ૧૯૭૩ (૧૯૭૪ ના નં.૨) ની કલમ ૧૪૪ અન્વયે અમોને મળેલ સત્તાની હેઠળે આથી હું હુકમ કરું છું કે, રાજકોટ શહેરના પોલીસ કમિશનર વિસ્તારમાં લેબર કોન્ટ્રાક્ટર/મુકાદમાઓએ પોતાની પાસે જે મજુર કામે રાખેલ હોય અને મજુરી કામકાજ માટે સપ્લાય કરતા હોય તેઓએ નીચે જણાવેલ કોમ મુજબ દરેક મજુરોના ચાલક-અલગ કોમ ભરી ફરજીયાત પાસે સ્થાનિક પોલીસ સ્ટેશનને જણા કરવાની રહેશે તથા મજુરી જવારે મજુરી કામ તથા રાજકોટ શહેર છોડી જતા રહે ત્યારે લેબર કોન્ટ્રાક્ટર/મુકાદમે તે અંગેની જાણ નામ/સરનામા સહિતની વિગત સાથે સ્થાનિક પો.સ્ટે.મા કરવાની રહેશે

૧	લેબર કોન્ટ્રાક્ટર / મુકાદમા (સપ્લાયર) નું પૂરું નામ સરનામું	-
૨	મો.નં., નંબર સહિત	-
૩	મજુરનું નામ તથા ઉ.વ.	-
૪	મજુરનું કાલનું સરનામું ટેલીફોન નંબર	-
૫	મજુરનું પૂર્ણ વતનનું સરનામું ગામ, તાલુકો, જિલ્લો	-
૬	કાલની મજુરીનું સ્થળ / કંપનીનું નામ	-
૭	મજુરનું વતનનું સ્થાનિક પો.સ્ટે.નું નામ તથા ટેલીફોન નંબર	-
૮	મજુરના વતનના આગેવાનનું નામ, સરનામું, ટેલીફોન નંબર	-
૯	મજુર અગાઉ કોઇ પોલીસ ગુનામાં પકડાયેલ હોય તો તેની વિગત	-
૧૦	કચારશી મુકાદમો / કોન્ટ્રાક્ટરે મજુરી કામ માટે લખેલ છે	-
૧૧	મજુરનું બોલાવ માટેનું આણ.કો.પુર (કોટા સાથે નું)	-
૧૨	રાજકોટ શહેરમાં કઇ તારીખથી મજુરી કામ કરે છે ? અને કઇ તારીખે જવાનો છે ?	-
૧૩	રાજકોટ શહેરમાં નજીકના સંબંધી કોઇ કોઇતો તેનું નામ, સરનામું	-

મજુરનો તાજેતરનો ફોટા

મજુરના અંગુઠાનું નિર્માણ

મુકાદમા/સપ્લાયર/કોન્ટ્રાક્ટરની સહી

નામ

આ હુકમ તા. ૦૧/૦૫/૨૦૧૪ થી તા.૩૦/૦૬/૨૦૧૪ સુધી અપરમા રહેશે.

આ હુકમનો હેતુ કરનાર વ્યક્તિ ભુતકાળના હુકમ ૧૮૮ મુજબ શિક્ષાને પાત્ર થશે.

રાજકોટ નામના પાસપોર્ટ

સરનામું

સરનામું

સરનામું

સરનામું

તમામને વ્યક્તિગત રીતે મોટીસની બજાવણી કરવી શક્ય ન હોય આથી એકત્રીકી દુકમ કરૂં છું. જાહેર જનતાની જાણ સારું સ્થાનિક વર્તમાન પણ બહાસવાણી અને દુરદર્શન કેન્દ્ર પારકતે પ્રસિધ્ધી દ્વારા તાજા પોલીસ સ્ટેશનના પોલીસ ઇન્સ્પેક્ટર, મહાનગર પોલીસ ઇન્સિસ્ટર, બાયસ પોલીસ ઇન્સિસ્ટર તથા પોલીસ કમિસર કચેરીના મોટીશ બોર્ડ ઉપર દુકમની નકલ ચોટાડી પ્રસિધ્ધી કરવામાં આવશે તેમજ સહેલાઈથી જોઈ શકાય તેવી જાહેર જગ્યાઓ ઉપર દુકાનની નકલ ચોટાડી પ્રસિધ્ધી કરવામાં આવશે ગુજરાત પોલીસ એક્ટ હાલ ૧૬૩ મુજબ પોલીસ અધિકારીઓ પણ આ દુકમની જાહેરાત કરવા અધિકૃત ગણાશે.

આજ તારીખે મોટીશ-૨૦૧૪ ના રીજ મારી સહી અને સિક્કો કરી આગેલ છે.



(મોકલ આ)
પોલીસ કમિસર
રાજકોટ શહેર, રાજકોટ

નકલ રવાના:-

- (૧) અગ્ર સચિવશ્રી, ગૃહ વિભાગ, ગાંધીનગર.
- (૨) પોલીસ મહાનિદેશક અને મુખ્ય પોલીસ અધિકારીશ્રી, ગુ. રા. ગાંધીનગર.
- (૩) અધિક પોલીસ મુખ્ય નિદેશકશ્રી (ઈન્ડે.) ગુ. રા. ગાંધીનગર.
- (૪) પોલીસ કમિસરશ્રી, અમદાવાદ શહેર, વડોદરા શહેર, સુરત શહેર.
- (૫) બાસ મુખ્ય પોલીસ અધિકારીશ્રી, રાજકોટ નેશનલ, રાજકોટ.
- (૬) જીલ્લા પોલીસ અધિકારીશ્રી, રાજકોટ જિલ્લો, રાજકોટ.
- (૭) કલેક્ટરશ્રી, રાજકોટ શહેર.
- (૮) મ્યુનિસિપલ કમિસરશ્રી, રાજકોટ શહેર.
- (૯) નિયામકશ્રી, માહિતી ખાતું રો. જીવરજી શહેર જિલ્લો મુખ્ય સચિવાલય બ્લોક નં.૩, વીજા માળે, ગુ. રા. ગાંધીનગર.
- (૧૦) જીલ્લા મારકાડી વહિવટીશ્રી, સેશન્સ કોર્ટ, રાજકોટ.
- (૧૧) મેનેજરશ્રી, નર્મીંગલ પેસ, રાજકોટ. (એકેડેમી બાજુના માં પ્રસિધ્ધ કરવા માટે).
- (૧૨) મહાનગર પોલીસ કમિસરશ્રી, પૂર્વ/ પશ્ચિમ વિભાગ, રાજકોટ શહેર.
- (૧૩) આર્.કમિસરશ્રી, (ઈન્ડે.), રાજકોટ રીક્રીમલ, રાજકોટ.
- (૧૪) બાયસ પોલીસ અધિકારીશ્રી/પી.ઈન્ડે.શ્રી, રાજકોટ રેલ્વે જંકશન પી.સી.
- (૧૫) તમામ પો.સે.ઈન્ચાર્જશ્રીઓ, રાજકોટ જંકશનકલો ચોટાડી લાઉટ સ્પીકર વાઠન દ્વારા જાહેરાત કરાવવા માટે.
- (૧૬) તમામ સ્થાનિક તથા ગ્રામી ઈન્ચાર્જશ્રીઓ, રાજકોટ શહેર.
- (૧૭) ઇન્ડોર ઈન્ચાર્જશ્રી, રાજકોટ શહેર (૧૦ નકલ) વર્તમાનપત્રોને આપવી.
- (૧૮) લેબર કમિસરશ્રી, ... તમામ ખાતેની સભ્યશ્રીને જાવગત કરવા માટે.

નકલ રવાના રવાના:-

- (૧) રજીસ્ટ્રારશ્રી, રાજકોટ. ગુ. રા. સોલારીસ ખાતેવાળા.
 - (૨) રજીસ્ટ્રારશ્રી, ડીસ્ટ્રીક્ટ એન્ડ સેશન્સ કોર્ટ, રાજકોટ.
 - (૩) રજીસ્ટ્રારશ્રી, સીક જમુડીયાલ મેજી. શ્રી કોર્ટ, રાજકોટ.
 - (૪) રજીસ્ટ્રારશ્રી, એડીશનલ સેશન્સ જજ કોર્ટ, રાજકોટ.
 - (૫) એડીકયુટીવ મેજી.શ્રી, રાજકોટ શહેર.
 - (૬) એડીકયુટીવ મેજી.શ્રી, રાજકોટ ન બુકા.
 - (૭) સચૂકત માહિતી નિયામકશ્રી, રાજકોટ.
- (સ્થાનિક વર્તમાનપત્રો, બહાસવાણી તથા દુરદર્શન કેન્દ્રમાં પ્રસિધ્ધ કરવા અને વર્તમાનપત્રોની કાપડીઓ મોકલવા માટે)

૧૨
૭



રાજકોટ મહાનગરપાલિકા

હિસાબી શાખા

ડો.આંબેડકર ભવન, ઢેબરભાઇ રોડ, રાજકોટ - ૩૬૦ ૦૦૧.

રા.મ.ન.પા./હિસાબી/જા.નં. ૪૨૧

તા. ૧૬/૬/૨૦૧૭

નોંધ -

વિષય - Vendor Regi. માં GST No. Update કરવા બાબત

ઉપરોક્ત વિષયે જણાવવાનું કે રાજકોટ મહાનગરપાલિકા નાં તમામ વેન્ડર / કોન્ટ્રાક્ટરો ની Vendor Registration માં GST No. ની જરૂરીયાત હોય તાત્કાલીક અપડેટ કરવા વિનંતિ. Temporary Vendor નાં Regi. આપની શાખામાં જ થઇ જશે જ્યારે Permanent Vendor નાં GST No. અપડેટ કરવા શાખા અધિકારીશ્રી નાં જરૂરી સહી સીક્કા સાથે નીચે મુજબ વિગત નું ધત્રક બનાવી દિવસ - ૭ માં હિસાબી શાખામાં માહિતી મોકલાવી આપવા વિનંતી.

Vendor Name	Existing Vendor Regi. No.	PAN	GST NO.

જાવે
સ્ટેડી (૯૨)
પા.મ.ન.પા.માં
નોંધ - તમામ વિગતો ચકાસીને અપડેટ કરવી / ચકાસીને મોકલવી અન્યથા સપ્લાયર્સ ને TDS ની

ચીફ એકાઉન્ટન્ટ
રાજકોટ મહાનગરપાલિકા

કેડીટ મળશે નહીં જેની નોંધ લેવા વિનંતી.

નકલ અમૂલવારી અર્થે

૧. તમામ શાખા અધિકારીશ્રી ઓ

નકલ સવિનય જાણ અર્થે

- માન. કમિશ્નર સાહેબશ્રી
- માન. નાયબ કમિશ્નર સાહેબશ્રી

રાજકોટ મહાનગરપાલિકા
સે. ઝોન માંધકામ શાખા
ઈન્વર્ડ નંબર ૭૩૭
તારીખ ૧૬/૬/૧૭

જાહેરનામું

આથી હું બંછાનિધિ પાની (IAS), મ્યુનિસિપલ કમિશનર, રાજકોટ મહાનગરપાલિકા, રાજકોટ ગુજરાત પ્રોવીન્સીયલ મ્યુનિસિપલ કોર્પોરેશન એક્ટ-૧૯૪૮ ની જોગવાઈ અનુસંધાને મળેલ સત્તા મુજબ, જાહેર હિતને ધ્યાને લઈ રાજકોટ મહાનગરપાલિકા વિસ્તારમાં ઇમારત તોડવા, સમારકામ અથવા તો નવા બાંધકામ દરમ્યાન ઉપસ્થિત થતા બાંધકામને લગત કચરા (Construction and Demolition Waste) નો રાજકોટ મહાનગરપાલિકા દ્વારા નિયત કરાયેલ જગ્યા સિવાય નિકાલ કરવા પ્રતિબંધ ફરમાવું છું.

એવું ધ્યાનમાં આવેલ છે કે રાજકોટ મહાનગરપાલિકા વિસ્તારમાં ઇમારત/ઇમારતોના બાંધકામ દરમ્યાન નળીયા, પથરા, ઇંટો, સાંકળીયો, ઇમારત બાંધવાના માલસામાન, અને એવા માલસામાનનો કાટમાળ ગમે તે જગ્યાએ નિકાલ / એકઠો કરવામાં આવે છે. જેનાથી એવી જગ્યાએ ઉંદરો, અથવા અન્ય જીવ જંતુઓનું આશ્રય સ્થાન અથવા ઉત્પત્તિ સ્થાન બને છે. તેમજ સદરહું જગ્યાનો ભોગવટો કરનારાઓને અથવા પડોશમાં રહેતી વ્યક્તિઓના ભય અને ઉપદ્રવનું કારણ બને છે. તેના કારણે રોગચાળો ફેલાવવાનો ભય અને લોકોના આરોગ્ય તથા જાનમાલને નુકશાન થાય તેવી સ્થિતિ ઉત્પન્ન થાય છે. તેમજ તે કચરો (Construction and Demolition Waste) દૂર કરવા રાજકોટ મહાનગરપાલિકાને ખુબજ મોટો ખર્ચ થાય છે, તેમજ માનવ સમય બગડે છે. આમ, લોકોના જાનમાલના અને આરોગ્યના નુકસાનના ભોગે આવી ગેરકાયદેસર પ્રવૃત્તિ ચાલી રહેલ છે, આવી કોઇપણ પ્રવૃત્તિ જન આરોગ્ય માટે બીન સલામતી નોતરે તેમ હોય ગુજરાત પ્રોવીન્સીયલ મ્યુનિસિપલ કોર્પોરેશન એક્ટ અનુસુચી-ક ના પ્રકરણ-૧૪ ની જોગવાઈઓ અનુસંધાને આવી તમામ પ્રવૃત્તિ કરવાનો આ જાહેરનામાથી જાહેરહિતમાં પ્રતિષેધ ફરમાવું છું. આવા કચરા (Construction and Demolition Waste) ના નિકાલ માટે રાજકોટ મહાનગરપાલિકાએ નીચે દર્શાવેલ સ્થળો નિયત કરેલ છે.

(૧) કોઠારીયા પોલીસ ચોકીની બાજુમાં, પથ્થરની ખાણ પાસે.

(૨) રૈયા સ્માર્ટ સીટીના તમામ ખાણ વિસ્તાર.

ઉપરોક્ત નિયત કરેલ સ્થળો સિવાય અન્ય કોઇપણ જગ્યાએ કોઇપણ ઇસમ/ઇસમો છકડો, ટ્રેક્ટર અથવા ડમ્પર દ્વારા (Construction and Demolition Waste) નો નિકાલ કરતાં પકડાશે તો પ્રથમ વખત છકડો/ટ્રેક્ટર દિઠ રૂ.૭,૫૦૦/- તથા ડમ્પર દિઠ રૂ.૧૫,૦૦૦/- તથા બીજી વખતે છકડો/ટ્રેક્ટર દિઠ રૂ.૧૫,૦૦૦/- તથા ડમ્પર દિઠ રૂ.૩૦,૦૦૦/- તથા ત્રીજી વખતે છકડો/ટ્રેક્ટર દિઠ રૂ.૫૦,૦૦૦/- તથા ડમ્પર દિઠ રૂ.૧,૦૦,૦૦૦/- લેખે વહીવટી ચાર્જ વસુલ કરવામાં આવશે. તેમજ વાહન જપ્ત કરવા સુધીની કાર્યવાહી કરવામાં આવશે.

રાજકોટ.

તા.

બંછાનિધિ પાની (IAS)
કમિશનર
રાજકોટ મહાનગરપાલિકા



રાજકોટ મહાનગર સેવાસદન

ડો. આંબેડકર ભવન, ઢેબરભાઈ રોડ, રાજકોટ - ૩૬૦ ૦૦૧.

વેબસાઈટ : www.rmc.gov.in

રા.મ્યુ.કો./વીજી.ટેક./જા. નં. ૧૦૨

૨૯/૮/૧૮

તા. ૨૯/૮/૨૦૧૮

પરિપત્ર:-

- રાજકોટ મહાનગરપાલિકામાં ત્રણ ઝોન (ઇસ્ટ, સેન્ટ્રલ, વેસ્ટ) માં ઝોનલ કામમાં કે ટેન્ડરથી થતા કામમાં પેવર બ્લોકની કામગીરી કરવામાં આવે છે. જેથી, ક્વોલિટી કન્ટ્રોલ માટે પેવર બ્લોકની કામગીરીમાં વપરાશ કરવામાં આવતા પેવર બ્લોકનું ટેસ્ટિંગ કરવું જરૂરી હોય, વોર્ડમાં ઝોનલ કામ, ટેન્ડર કામ તેમજ વિવિધ શાખા હસ્તક ચાલતા પ્રોજેક્ટ કામમાં વપરાશ કરવામાં આવતા તમામ પ્રકારના પેવર બ્લોકના કામમાં કામ કરાવનાર RMC ટેકનીકલ ટીમ દ્વારા IS 15658:2006 મુજબ Government લેબોરેટરી કે Government માન્ય લેબોરેટરીમાં હાજરીમાં ફરજિયાતપણે ટેસ્ટિંગ કરાવવાનું રહેશે.
- આ ઉપરાંત, રાજકોટ મહાનગરપાલિકાની, વિવિધ શાખા હસ્તક ચાલતાં બાંધકામ તથા રસ્તાકામને લગત, દરેક મહત્વના પ્રોજેક્ટના અગત્યનાં તબક્કે કામગીરી કરાવનાર પ્રોજેક્ટ એક્ઝીક્યુશન ટેકનીકલ ટીમ દ્વારા આગળના દિવસે વિજીલન્સ (ટેક.) ટીમને SMS/Whatsapp થી જાણ કરવામાં આવે છે. તે જ રીતે પેવર બ્લોક બાબતે RMC એક્ઝીક્યુશન ટેકનીકલ ટીમ દ્વારા હાલ ચાલુ હોય તેમજ હવે પછી થનાર તમામ પેવર બ્લોકના કામો માટે આગળના દિવસે વિજીલન્સ (ટેક.) ટીમને SMS/Whatsapp થી જાણ કરવાની રહેશે. જે અન્વયે વીજીલન્સ શાખા (ટેક.) દ્વારા રેન્ડમ સેમ્પલીંગ કરી, IS 15658:2006 મુજબ Government લેબોરેટરી કે Government માન્ય લેબોરેટરીમાં હાજરીમાં ફરજિયાતપણે ટેસ્ટિંગ કરાવી, અત્રે રીપોર્ટ કરવાનો રહેશે.

ઉપરોક્ત બાબતની અમલવારી તાત્કાલિક અસરથી ચુસ્તપણે કરવાની રહેશે.

કમિશ્નર

રાજકોટ મહાનગરપાલિકા

નકલ રવાના (જાણ તથા અમલવારી અર્થે)

- નાયબ કમિશ્નરશ્રી (ઇસ્ટ, સેન્ટ્રલ, વેસ્ટ-ઝોન)

નકલ રવાના (અમલવારી અર્થે)-

- તમામ સીટી એન્જીનીયરશ્રી, એડી. સીટી એન્જીનીયરશ્રી, એક્ઝીક્યુટીવ એન્જીનીયરશ્રી

2018-8-29 12:55



રાજકોટ મહાનગરપાલિકા

ડો. આંબેડકર ભવન, ઢેબર રોડ, રાજકોટ - ૩૬૦૧૧૦.

વેબસાઈટ : www.rmc.gov.in

આર.એમ.સી./સી./

તા. ૨૭/૧૨/૨૦૧૬

પરીપત્ર:-

રા.મ્યુ.કો./વિજી./જા.નં. ૧૮૦.....
૨૭/૧૨/૨૦૧૬

- રાજકોટ મહાનગરપાલિકામાં ત્રણ ઝોન (ઇસ્ટ, સેન્ટ્રલ, વેસ્ટ) માં ઝોનલ કામમાં કે ટેન્ડરથી થતા કામમાં પેવર બ્લોકની કામગીરી કરવામાં આવે છે. જેથી, ક્વોલિટી કન્ટ્રોલ માટે પેવર બ્લોકની કામગીરીમાં વપરાશ કરવામાં આવતા પેવર બ્લોકનું ટેસ્ટીંગ કરવું જરૂરી હોય, રા.મ્યુ.કો./વિજી. (ટેક.)/જા.નં.-૧૦૨, તા.૨૯/૦૮/૨૦૧૮ થી વોર્ડમાં ઝોનલ કામ, ટેન્ડર કામ તેમજ વિવિધ શાખા હસ્તક ચાલતા પ્રોજેક્ટ કામમાં વપરાશ કરવામાં આવતા તમામ પ્રકારના પેવર બ્લોકના કામમાં ફરજિયાતપણે ટેસ્ટીંગ કરાવવા માટે પરીપત્ર કરવામાં આવેલ છે.
- જે પરીપત્ર અન્વયે આ પરીપત્રથી હવે પછી કરવાનાં થતા તમામ ટેન્ડર કામ તેમજ નવા ઝોનલ કોન્ટ્રાક્ટના કામોમાં નીચે પ્રમાણે યુસ્ત અમલવારી કરવાની રહેશે.
- આ પરીપત્ર પહેલાના કોઇપણ ઝોનલ કે ટેન્ડર કામ માટે જે તે Grade ની સાપેક્ષ પરિણામ ન મળે તો જે તે મળેલ પરિણામ પ્રમાણે Rate Reduce કરવાનાં રહેશે.
- કોઇપણ Grade ના પેવર બ્લોક માટે Compressive Strength નું સરેરાશ પરિણામ 10% કરતા વધારે ઓછું (દા.ત. M-30 Grade માટે Compressive Strength 27 N/mm² થી ઓછી) મળશે તો તે પેવરબ્લોક Reject કરવામાં આવશે એટલે કે તેમનું Payment કરવામાં આવશે નહિ.
- કોઇપણ Grade ના પેવર બ્લોક માટે Compressive Strength નું સરેરાશ પરિણામ 10% ની મર્યાદામાં ઓછું (દા.ત. M-30 Grade માટે Average Compressive Strength 27 N/mm² થી 29.99 N/mm² ની વચ્ચે) મળશે તો તે પેવરબ્લોક માટે Minimum 5 % તેમજ Maximum 10% મળેલ Average Compressive Strength પ્રમાણે Rate Reduce કરવાનાં રહેશે.
- કોઇપણ Grade ના પેવર બ્લોક માટે Water Absorption નું સરેરાશ પરિણામ 6% થી વધારે આવશે તો તે પેવરબ્લોક Reject કરવામાં આવશે એટલે કે તેમનું Payment કરવાનું થશે નહિ.

Compressive Strength માટે કુલ ૮ પેવર બ્લોકનું ટેસ્ટીંગ કરવાનું રહેશે જે ૮ પેવર બ્લોક (ગ્રેડ મુજબ સરેરાશ પરિણામ મળશે તો પણ) પૈકી જો ૧ થી ૨ Individual Sample નું પરિણામ ૮૫% કરતા ઓછું મળશે તો ૧૦% Rate Reduce કરવામાં આવશે તેમજ ૮ પેવર બ્લોક પૈકી જો ૨ થી વધારે Individual Sample નું પરિણામ ૮૫% કરતા ઓછું મળશે તો તે પેવરબ્લોક Reject કરવામાં આવશે એટલે કે તેમનું Payment કરવામાં આવશે નહિ.

- ૧૨.૦૦ મી. કે તેથી મોટા રોડના Side Shoulder માટે M-30 Grade (ISI Mark) Rubber Mould Paving Block વાપરવાના રહેશે. ૧૨.૦૦ મી. થી નાની પહોળાઈના રસ્તાઓ પર Side Shoulder માં M-30 Grade (ISI Mark) Non Rubber Mould Paving Block વાપરવાના રહેશે.
- પહોળાઈમાં ૫.૦૦ મી. કે તેથી ઓછી પહોળાઈ વાળી શેરી હોય ત્યાં જ આખી શેરીમાં Paving Block ની કામગીરી કરી શકાશે. જનભાગીદારી યોજના હોય ત્યાં ૫.૦૦ મી. કે તેથી વધુ પહોળાઈ વાળી શેરીમાં Rubber Mould Paving Block ની કામગીરી કરી શકાશે.
- આ પરીપત્રને ટેન્ડરના એક ભાગ તરીકે રાખવાનો રહેશે.

ઉપરોક્ત બાબતની અમલવારી તાત્કાલિક અસરથી ચુસ્તપણે કરવાની રહેશે.

Indi P.

કમિશ્નર

રાજકોટ મહાનગરપાલિકા

નકલ રવાના (જાણ તથા અમલવારી અર્થે)

- નાયબ કમિશ્નરશ્રી (ઇસ્ટ, સેન્ટ્રલ, વેસ્ટ ઝોન)

નકલ રવાના (અમલવારી અર્થે)

- તમામ સીટી એન્જીનીયરશ્રી, એડી. સીટી એન્જીનીયરશ્રી, એક્ઝીક્યુટીવ એન્જીનીયરશ્રી, એન્વાયરમેન્ટ એન્જીનીયરશ્રી (S.W.M.)
- ડી.ઇ.ઇ.શ્રી (વીજીલન્સ શાખા - ટેક.)